

Title

Material Submittal for
Fire Alarm System

Brand

Avenger



Index

- ***Technical Catalogues.***
- ***Avenger Certificates.***
- ***Bill of Materials.***
- ***Data Sheets.***
- ***UL Listed.***
- ***FM Approvals.***
- ***Avenger Approvals.***
- ***List of Projects.***

Avenger Certifications

SECRETARY OF STATE



NEVADA STATE BUSINESS LICENSE

AVENGER SYSTEMS, LLC

Nevada Business Identification # NV20151238133

Expiration Date: 04/30/2027

In accordance with Title 7 of Nevada Revised Statutes, pursuant to proper application duly filed and payment of appropriate prescribed fees, the above named is hereby granted a Nevada State Business License for business activities conducted within the State of Nevada.

Valid until the expiration date listed unless suspended, revoked or cancelled in accordance with the provisions in Nevada Revised Statutes. License is not transferable and is not in lieu of any local business license, permit or registration.

License must be cancelled on or before its expiration date if business activity ceases. Failure to do so will result in late fees or penalties which, by law, cannot be waived.



IN WITNESS WHEREOF, I have hereunto set my hand and affixed the Great Seal of State, at my office on 03/04/2026.

FVAguilar

Certificate Number: B202603046530996

You may verify this certificate

online at <https://www.nvsilverflume.gov/home>

FRANCISCO V. AGUILAR
Secretary of State

Certificate of Registration



This is to certify that the Quality Management System of

Avenger Systems LLC

11586 Zagarolo Lane, Las Vegas, NV 89141 USA

is in accordance with the requirements of the following standard

ISO 9001:2015

(Quality Management System)

SCOPE

Manufacturing of Fire Alarm Systems, Wet Chemical Fire Suppression Systems, Clean Agents Fire Suppression System

(IAF Code: 18)

Certificate Number : 211124010108

Initial Registration Date : 21-Nov-2024

1st Surveillance Date : 21-Oct-2025

2nd Surveillance Date : 21-Oct-2026

Certificate Expiry Date : 20-Nov-2027

To verify certificate, visit at :

www.arscert.com

www.uafaccreditation.org

www.iafcertsearch.org

Issued by ARS Assessment Private Limited


Managing Director



CB-MS-3923



UAF Address : 400, North Center Dr, STE 202, Norfolk, VA 23502, United States of America

This certificate remains the property of ARS and must be returned to ARS on Cancellation or Suspension of the certificate. Validity of the certificate is subject to successful completion of surveillance audits. Further clarification regarding the scope of this certificate and the applicability of standard may be obtained by consulting the Organisation on info@arscert.com

Certification

Awarded to
AVENGER SYSTEMS LLC

Head Office
11586 Zagarolo Lane, Las Vegas, NV 89141 USA.

Reliable Certification Ltd. certifies that the management system of the above organisation has been audited and found to be in accordance with the requirements of the management standard detailed below

Standard
ISO 14001:2015
ENVIRONMENTAL MANAGEMENT SYSTEM

Scope of Certification
Manufacturing of Fire Alarm Systems, Wet Chemical Fire Suppression Systems & Clean Agents Fire Suppression Systems.

Certificate number: RCLQ1001400

Initial Certification date: 23-JUL-2025

Recertification date: 22-JUL-2028

Subject to the continued satisfactory operation of the organization's management system



Director



Certification Body: RELIABLE CERTIFICATION LTD.
Address: 412 Allied Sainif House Greenford Rd, London UB6 9AH.
For further information, please contact info@reliablecert.uk
To check the validity of this certificate, please visit: www.reliablecert.uk
Accreditation by UNITED KINGDOM INTERNATIONAL CERTIFYING BOARD (UKICB)
Address: 4 The Ridgeway, Ridgeway Trading Estate, Iver, England, SLO 9HW.
For further clarification regarding accreditation, please visit www.ukicb.co.uk

Certification

Awarded to
AVENGER SYSTEMS LLC

Head Office
11586 Zagarolo Lane, Las Vegas, NV 89141 USA.

Reliable Certification Ltd. certifies that the management system of the
above organisation has been audited and found to be in accordance with
the requirements of the management standard detailed below

Standard
ISO 45001:2018
HEALTH AND SAFETY MANAGEMENT SYSTEM

Scope of Certification
Manufacturing of Fire Alarm Systems, Wet Chemical Fire Suppression Systems &
Clean Agents Fire Suppression Systems.

Certificate number: RCLQ1001401

Initial Certification date: 23-JUL-2025

Recertification date: 22-JUL-2028

Subject to the continued satisfactory operation of the organization's management system



Director



Certification Body: RELIABLE CERTIFICATION LTD.
Address: 412 Allied Sainif House Greenford Rd, London UB6 9AH.
For further information, please contact info@reliablecert.uk
To check the validity of this certificate, please visit: www.reliablecert.uk
Accreditation by UNITED KINGDOM INTERNATIONAL CERTIFYING BOARD (UKICB)
Address: 4 The Ridgeway, Ridgeway Trading Estate, Iver, England, SLO 9HW.
For further clarification regarding accreditation, please visit www.ukicb.co.uk

Bill Of Materials

BILL OF MATERIALS

Model #	Description Detail
OA902H6-10	Oasis, M6, 1 aperture, 12 Loop, 5.25A, Red (Deep Enclosure)
S723	Oasis network module (Ethernet and IFAM)
AS5050-250	Addressable Optical Smoke Detector - 7th Edition
AS5500-450	Addressable Heat Detector
AS5050-350	Addressable Multisensor Smoke & Heat Detector -7th Edition
AS5000-210	Addressable UL Base 4"
AS56000-005	Dual Action Addressable Manual Pull Station
AS56000-006	UL Manual Pull Station Backbox
AS58000-011	Open Area Sounder Beacon - Indoor / Outdoor
AS4705-700	Addressable UL Input Module (OPTIONAL)
AS4705-701	Addressable Relay Module (OPTIONAL)

Datasheets

OASIS

2-16 LOOP ANALOG ADDRESSABLE FIRE ALARM CONTROL PANELS



Standard Features

- UL Listed (Tenth Edition)
- Supports Apollo and Hochiki Protocols
- 2 to 8 loop or 2 to 16 loop versions - 127 Devices Per Loop
- 400mA loop current
- 4 programmable NACs Class B or 2 Class A with internal synchronization
- 5.25 A or 10.25 A power supply options
- 3 programmable inputs and 5 programmable relay outputs
- 7 inch, full-color resistive touch screen with intuitive user interface
- Up to 24 programmable soft function keys
- Up to 64 user login accounts
- Hard-wired fire and trouble routing inputs and outputs Modular and expandable electronics
- 400 sub-address points per loop (800 per loop module)
- Option to invert inputs and outputs
- 5000 programmable cause and effects; over 50,000 inputs and outputs
- Can be networked with programmable functionality
- Programming via USB port to PC or memory stick

Product Overview

The all new Oasis product range of fire alarm control equipment combines the very latest hardware and software to produce a control and indication system, which is powerful and sophisticated, yet simple to use and understand. The flexibility of the Oasis platform is such that it can be re-configured to realize many other control and indication applications, with direct integration into intelligent buildings.

Moving away from the simple, price driven competitive model used by most manufacturers today, the Oasis concept is designed to add value to System Designers, Integrators, Service Providers, and end users. Developed from the "ground up" and using some of the most advanced technology available, Oasis is designed as one of the most powerful, intelligent, and technically robust fire alarm products available. Not only do the products and services offered under the Oasis brand provide solutions to the most technically challenging applications in life safety, Oasis will deliver added value, market advantage, and a competitive edge to your business.



Optional Panel Peripherals

- **LatiView Graphics**
L@tiView enables the creation of a 2D map of any site or building to monitor fire safety and detection, and automatically switches to an area where a fire device has been activated to allow immediate viewing and investigation of an event.
- **Dual Loop Panel Module (\$758)**
The Dual Loop Panel Module monitors loop device status and provides status to the panel processor. It holds device configurations and operates in a standalone manner when catastrophic failures occur.
- **16 Channel I/O Interface Card (\$560)**
The 16 Channel I/O Interface enhances the versatility of the alarm system by providing additional input and output capabilities to the Oasis Fire Alarm Control Panel. Inputs or outputs can be selected for up to 16 individual channels, and are configured in the same way as devices connected to addressable loops of the panel. The 16 Channel I/O Interface can be configured to contribute or act upon cause and effect logic.
- **Media Gateway™ Panel Module (\$788)**
The Media Gateway Panel Module provides connectivity to monitoring centers using IP (Sur-Gard), or dial-up connectivity. The Media Gateway may also be used to meet integration application requirements.
- **8 Channel Relay Panel Module (\$791)**
The 8 Channel Relay Panel Module has 8 voltage-free changeover relay contacts, each of which can be individually programmed. All outputs are configurable in the same way as devices connected to the loops and all may be acted upon by cause and effect logic. These boards are typically used in applications which require more than the five standard relay outputs, such as signaling to other systems or plant control.
- **Network Module (\$723)**
The Network Module provides enhanced high-speed communication for networking fire control panels. The network provided by this module can support combinations of Fire Alarm Control Panels and Vision units. Fire Alarm Control Panels can receive events from other panels in the network. The Class X networking used in conjunction with the Network Module provides tolerance against open and short circuit trouble conditions.
- **Printer (\$768)**
The Printer is an optional feature for printing fire system events as they occur. The printer is located on the fascia, below the Zone LEDs (if present). It is a thermal printer and never requires replacement ink. Printing is performed on heat-sensitive paper rolls. A trouble message is reported when the paper runs out. The printer includes a front-loading feature for replacing paper rolls.
- **Zone LED Module (\$771)**
The Zone LED module contains 48 LEDs and is connected to the LCD Main Processor Board of the Oasis Fire Alarm Control Panel. A maximum of three Zone LED modules can be connected to provide the fascia with 144 Zone LED indicators.
- **4 Channel NAC Panel Module (\$793)**
FUTURE ENHANCEMENT
Additional NAC output capability can be added to by using 4 Channel NAC Modules. These boards have 4 supervised NAC outputs, each of which can be individually programmed. The circuits can be configured for class A or B operation. These circuits can be configured to act upon cause and effect logic.
- **8 Channel Conventional Zone Panel Module (\$792)**
FUTURE ENHANCEMENT
The 8 Channel Conventional Zone Panel Module has 8 supervised detection circuits (Class B). Each circuit can support up to 20 conventional detectors and approved devices. Individual circuits may be configured for trigger resistor or short circuit activation. These circuits may be used for any of the standard input actions and can be configured to contribute to cause and effect logic. Each pair of circuits (e.g., 1 and 2, 3 and 4, etc.) can be joined to form a single Class A configuration.
- **16 Channel I/O Interface Panel Module (\$772)**
FUTURE ENHANCEMENT
The 16 Channel I/O Interface Panel Module will provide the same functionality as the 16 Channel I/O Interface Card, with the convenience of a plug-in module.



Technical Specifications

2 TO 8 LOOP (4 SLOT) ENCLOSURE

Size	Standard Cabinet: 420mm (W) x 590mm (H) x 153mm (D), or 16.5in (W) x 23.2in (H) x 6in (D) Deep Cabinet: 420mm (W) x 590mm (H) x 203mm (D), or 16.5in (W) x 23.2in (H) x 8in (D)
Construction	Mild sheet steel enclosure, 1.5 mm
Cable Entry	Standard Cabinet: 28 knockouts top, 19 knockouts back, 1 knockout each side, 2 knockouts bottom Deep: 38 knockouts top, 19 knockouts back, 1 knockout each side, 2 knockouts bottom
Optional Semi-Flush Mounting Kit	Semi-Flush Mounting Collar Kit KM5FCRD - Red KM5FCGY - Gray KM5FCBS - Black
Battery Capacity	Standard Cabinet: Up to 28 Ah (Power Sonic PS-12280) Deep Cabinet: Up to 40 Ah (Power Sonic PS-12400)


2 TO 16 LOOP (8 SLOT) ENCLOSURE

Size	Standard Cabinet: 540mm (W) x 720mm (H) x 160mm (D), or 21.3in (W) x 28.3in (H) x 6.3in (D) Deep Cabinet: 540mm (W) x 720mm (H) x 212mm (D), or 21.3in (W) x 28.3in (H) x 8.3in (D)
Construction	Mild sheet steel enclosure, 1.5 mm
Cable Entry	Standard Cabinet: 38 knockouts top, 25 knockouts back, 2 knockouts each side, 2 knockouts bottom Deep Cabinet: 50 knockouts top, 25 knockouts back, 2 knockouts each side, 2 knockouts bottom
Battery Capacity	Standard Cabinet: Up to 28 Ah (Power Sonic PS-12280) Deep Cabinet: Up to 40 Ah (Power Sonic PS-12400)

ALL MODELS

Finish	Epoxy powder coated
Enclosure Color	● Red (RAL3002) ● Gray (BS 00 A 05) ● Black (RAL9005)
Power Supply Voltage	115 V AC or 230 V AC
Power supply rating at 24V DC	5.25 A (charges up to 60 Ah) 10.25 A (charges up to 100 Ah)
Display	Full-color 800 x 480 LCD with resistive touch screen and automatic backlight dimming
Software Zones	2000
Software Groups	5000
Cause and Effects	5000
Event Log	10,000 events, 1 second resolution. Filterable and printable
Detection Loops	2 to 16 added 2 at a time (S758 dual loop cards)
Detection Loop Current	400 mA each
AUX 24V Output	2 - each rated at 900 mA
NACs	4 - each rated at 2.5 A Class B or 2 Class A.
Programmable Relay Outputs	5 - 30 V DC 1 Amp
Programmable Inputs	3 - designed to be activated by voltage-free contacts
Network Connection	Optional network card provides communication for networking 127 fire control panels
NAC Synchronization	Internal Support of System Sensor, Wheelock, Gentex, and Amseco protocols
Printer (OPTIONAL)	40 column, front-loading thermal
Zone LED Indicators (OPTIONAL)	Up to 3 banks of 48 (144) as standard
Operating Temperature	23°F to 120°F (-5°C to 49°C)
Operating Humidity	to 95% (non condensing)

Panel Model Numbers



Panel Options	Valid Entries	Description
Product Style	OA	Oasis Fire Alarm Control Panel
	OV	Oasis Network Vision Annunciator
Enclosure Style	1	4 Slot Standard Enclosure
	2	4 Slot Standard Plex-Door Enclosure
	3	4 Slot Deep Enclosure
	4	4 Slot Deep Plex-Door Enclosure
	7	8 Slot Standard Enclosure - 16 Loop
	8	8 Slot Standard Plex-Door Enclosure - 16 Loop
	9	8 Slot Deep Enclosure - 16 Loop
	A	8 Slot Deep Plex-Door Enclosure - 16 Loop
	C	Annunciator
Language	0	English
	1	Portuguese
	2	Spanish
	3	Taiwanese
	0	None
Power Supply	1	5.25 A 115V
	2	5.25 A 230V
	3	10.25 A (auto-voltage sensing)
Loop Modules & Communication Modules	00	Not Fitted
	NC	Network Module only (Network Vision Annunciator)
	H#	2-Loop Panel Module, Hochiki Protocol
	I#	2-Loop Panel Module, Hochiki Protocol, and Media Gateway™
	J#	2-Loop Panel Module, Hochiki Protocol, and Network Module
	K#	2-Loop Panel Module, Hochiki Protocol, Network Module, and Media Gateway™
Cabinet Color	1	Red (RAL3002)
	4	Gray (BS 00 A 05)
	6	Black (RAL9005)
Printer, Zone LEDs & Aperture	0	No Printer / No Zone LEDs
	1	No Printer / No Zone LEDs, Blank 2nd Aperture
	3	Printer / No Zone LEDs
	4	Printer / 48 Zone LEDs
	5	No Printer / 48 Zone LEDs
	6	No Printer / 96 Zone LEDs
	7	No Printer / 144 Zone LEDs
Optional Peripheral Cards	a	16 Channel I/O Panel Module (S772)
	b	8 Channel Relay Panel Module (S791)
	c	8 Channel Conventional Zone Module (S792)
	d	4 Channel NAC Module (S793)

AS5050-250 Smoke Detector



Product Overview

Product	XP95A Smoke Detector
Part No.	AS5050-250
Digital Communication	XP95 protocol

Approvals



Product Information

The XP95A Smoke Detector uses new sensing technology, Purelight®, to detect smoke particles entering the chamber. This reduces the possibility of false alarms whilst increasing the reliability of detection of a real fire.

- Approved to UL268 7th edition
- Purelight® optical technology provides enhanced smoke detection and false alarm management
- Internal drift compensation
- Easy installation
- Backwards compatible with XP95 systems
- Base locking mechanism (grub screw)
- Polarity insensitive wiring
- In-built self test
- XPERT card addressing

Technical Data



CAUTION: System compatibility
The XP95A Smoke Detector, Part No AS5050-250 can only be used on existing systems operating with XP95 protocol.

This detector is a direct replacement for the 55000-650 XP95A Smoke Detector.

All data is supplied subject to change without notice. Specifications are typical at 24 V, 73 °F and 50 % RH unless otherwise stated.

<i>Detection principle</i>	<i>Photo-electric light scattering</i>
<i>Sensor configuration</i>	<i>Chamber with surface-mount infrared emitter and prism. Solid state integrated photo-diode and amplifier.</i>
<i>Digital communication protocol</i>	<i>XP95 protocol only</i>
<i>Supply wiring</i>	<i>Two wire supply, polarity insensitive</i>
<i>Sampling frequency</i>	<i>Once per second 1.2 -2.1%/ft</i>
<i>Sensitivity</i>	<i>17 V – 28 V dc</i>
<i>Supply voltage (Vmin- Vmax) Modulation voltage</i>	<i>5 V – 9 V peak to peak 340 µA</i>
<i>Supervisory current</i>	<i>1.0 mA</i>
<i>Switch-on surge current</i>	<i>4.0 mA</i>
<i>Alarm/operated current, LED On</i>	<i>Alarm (Red)</i>
<i>Status indicator</i>	<i>5 mA maximum</i>
<i>Additional Remote LED current</i>	<i>32 °F to 131 °F (0°C to 55°C)</i>
<i>Product operating temperature</i>	<i>0% to 95% RH (no condensation or icing)</i>
<i>Humidity</i>	<i>None</i>
<i>Effect of atmospheric pressure</i>	<i>0 - 300 fpm</i>
<i>Air velocity</i>	<i>IP44</i>
<i>IP rating</i>	
<i>Standards and Approvals</i>	<i>UL 268 7th Edition, 4 in. (100 mm) diameter x 1.41 in. (36 mm) height</i>
<i>Dimensions</i>	<i>(1.88 in. (48) mm height with XPERT 8 Intelligent Mounting Base) 2.93 ozs. (83 g)</i>
<i>Weight</i>	<i>Housing: White flame-retardant polycarbonate</i>
<i>Materials</i>	<i>Terminals: Tin plated stainless steel</i>

Electrical Description

The XP95A Smoke Detector is designed to be connected to a two-wire loop circuit carrying both data and a 17 V - 28 V dc supply. The detector is connected to the incoming and outgoing supply via terminals L1 and L2 in the mounting base. A remote LED indicator may be connected between the +R and -R terminals. A ground connection terminal is also provided.

Operation

The low profile design of the XP95A Smoke Detector is sleek and evolutionary, with a 360° LED indicator which illuminates red when in alarm.

At the heart of the smoke sensor of the XP95A Detector is Purelight® Sensing Technology which incorporates:

- Cone technology combined with a high-intensity infra-red LED to provide stability and accurate sensitivity to smoke
- A sophisticated dynamic algorithm, providing transient rejection and compensation for drift whilst maintaining accurate sensitivity

The smoke chamber of the detector is a unique cone shape which serves to reduce any stray reflection. This ultra dark internal light chamber also contains a high-intensity infra-red LED that is highly sensitive to smoke particles. When smoke enters the chamber, infra-red light is scattered and registered by the photodiode and amplifier that are included in an application-specific integrated circuit (ASIC). This circuit ensures long term reliability, even in extreme conditions.

System Compatibility

This XP95A detector has been designed to operate with XP95A detectors and loops. This XP95A detector can operate on an approved XPERT intelligent mounting base, however, the eighth bit of the address will be ignored.

The device will compensate for drift internally and the fire panel will see this as an increase in analog value. When internal drift limits are reached a fault analog value will be generated.

Maintenance And Service

Maintenance has to be done in accordance with all applicable standards. Clean the detector externally using a soft damp cloth.

Compatible Bases

Part Number	Product Name
AS5000-210	Soteria UL Base - 4"
AS5000-230	Soteria UL Base – 6"
AS5300-800	Soteria UL CO Sounder Base - 6" High Frequency
AS5300-802	Soteria UL Sounder Base - 6" High Frequency
AS5300-805	Soteria UL CO Sounder Base - 6" Low Frequency
AS5300-806	Soteria UL Sounder Base – 6" Low Frequency

	Smoke	Multi-Criteria	Heat
For existing XP95A installations choose:	AS5050-250 XP95A Smoke Detector	AS5050-350 XP95A Multi- Criteria Detector (Smoke/Heat)	AS5500-450 XP95A Heat Detector

This datasheet is to be used for marketing purposes only. Please do not use it for installation purposes. For more information, please refer to the product installation guide or contact your sales manager. All information on this datasheet is subject to change without notice.

AS5500-450

XP95A Heat Detector - UL521 7th Ed



Product Overview

Product	XP95A Heat Detector
Part No.	AS5500-450
Digital Communication	XP95 protocol

Approvals



Product Information

The XP95A Heat Detector monitors temperature by using a single thermistor which provides a voltage output proportional to the external air temperature. It is classified as an ordinary detector by UL.

- Compatible with all devices from the latest UL268 7th Edition approved XP95A range
- Electronic temperature sensing
- Alarm flag for fast alarm responding
- Automatic addressing with the XPERT 7 card
- Electronic free 4" or 6" bases
- Easy installation
- Elegant design
- Ideal for environments that are dirty or smoky under normal circumstances
- Well suited for warehouses, loading docks and parking areas

Technical Data



CAUTION: System compatibility The XP95A Heat Detector, Part AS5500-450 can only be used on existing systems operating with XP95 protocol.

All data is supplied subject to change without notice. Specifications are typical at 24 V, 73°F and 50% RH unless otherwise stated.

Sensor	Single NTC
Sampling frequency	thermistor One second
Digital communication	XP95
Supply voltage	17 - 28 V dc
Modulation	5 V to 9 V peak to peak
Voltage at Detector	
Supervisory current	250 µA
Surge current	1 mA
Alarm current	3 mA max
Operating temperature range	32 °F to 151°F
Humidity	
Standards and approvals	0% to 95% RH (no condensation or icing)
Dimensions	UL, FM
Weight	3.93" diameter x 1.65" height
Materials	3.70 oz Housing: White flame-retardant polycarbonate
Test method	Terminals: Tin plated stainless steel
Spacing	Hair dryer
Smooth ceiling to wall or partition	60ft 25 ft

All information in this document is given in good faith but Avenger Systems LLC cannot be held responsible for any omissions or errors. The company reserves the right to change the specifications of products at any time and without prior notice.

Operation

The XP95A Heat Detector has a common profile with the ionisation and optical smoke detectors but has a low air flow resistance case made of white polycarbonate.

The device monitors heat using a single thermistor network which provides a voltage output proportional to the external air temperature.

Electrical description

The XP95A Heat Detector is designed to be connected to a two wire loop circuit carrying both data and a 17 V to 28V dc supply. The detector is connected to the incoming and outgoing supply via terminals L1 and L2 in the mounting base. A remote LED indicator requiring not more than 1 mA may be connected between the +R and L2 terminals. An earth connection terminal is also provided. The detector is calibrated to give an analogue value of 25 ± 5 counts at 70°F . This value increases with rising temperature. A count of 55 corresponds to the UL alarm sensitivity level of 135°F .

When the detector is energized the ASIC regulates the flow of power and controls the data processing. The thermistor provides an output over normal operating ranges that is proportional to the external air temperature. The voltage output is processed in the analogue to digital converter and stored by the communications ASIC. It is transmitted to the control equipment when the device is interrogated. When a count of 55 is exceeded the alarm flag is initiated and the device address is added to the data stream every 32 polling cycles from its last polling for the duration of the alarm level condition, except when an alarming device is being interrogated. This can provide a location identified alarm from any device on the loop in approximately two seconds.

Environmental characteristics

The XP95A Heat Detector range is unaffected by wind or atmospheric pressure. Standard detectors are rated at 200°F .

This datasheet is to be used for marketing purposes only. All information on this datasheet is subject to change without notice. Technical information about installation can be found in the product installation guide which can be found on our website.


Response characteristics of XP95A Heat Detector

Type of fire	Heat Detector
OverHeating/Heat combustion	Very poor
Smouldering/glowing combustion	Very poor
Flaming combustion	Poor
Flaming with high Heat output	Moderate/Good
Flaming - clean burning	Moderate/Good

Part #	Product Name
AS5000-210	Soteria UL Base - 4"
AS5000-230	Soteria UL Base - 6"
AS5300-800	Soteria UL CO Sounder Base - 6" High Frequency
AS5300-802	Soteria UL Sounder Base - 6" High Frequency
AS5300-805	Soteria UL CO Sounder Base - 6" Low Frequency
AS5300-806	Soteria UL Sounder Base - 6" Low Frequency

	Smoke	Multi-Criteria	Heat
For existing XP95A installations choose:	AS5050-250 XP95A Smoke Detector	AS5050-350 XP95A Multi-Criteria Detector (Smoke/Heat)	AS5500-450 XP95A Heat Detector

Addressable Heat Detector Diagram



All information in this document is given in good faith but Avenger Systems LLC cannot be held responsible for any omissions or errors. The company reserves the right to change the specifications of products at any time and without prior notice.

AS5050-350

Multi-Criteria Detector (Smoke/Heat)



Technical Data



CAUTION: System compatibility
The XP95A Multi-Criteria Detector (Smoke/Heat), Part No AS5050-350 can only be used on systems operating with XP95 protocol

This detector is a direct replacement for AS55000-886 XP95A Multisensor Detector (Smoke/Heat)

All data is supplied subject to change without notice. Specifications are typical at 24 V, 73 °F and 50 % RH unless otherwise stated.

<i>Detection principle</i>	<i>Smoke</i> <i>Heat</i>	<i>Smoke light scattering</i> <i>Thermistor</i>
<i>Sensor configuration</i>	<i>Smoke</i>	Chamber with surface-mount infrared emitter and prism. Solid state integrated photo-diode and amplifier.
	<i>Heat</i>	Dual exposed heat sensing elements
<i>Digital communication protocol</i>	<i>XP95 protocol</i>	
<i>Supply wiring</i>	<i>Two wire supply, polarity insensitive</i>	
<i>Sampling frequency</i>	<i>Once per second</i>	
<i>Sensitivity</i>	<i>1.2 - 2.1 %/ft</i>	
<i>Supply voltage (Vmin-Vmax)</i>	<i>17 V – 28 V dc</i>	
<i>Modulation voltage</i>	<i>5 V – 9 V peak to peak</i>	
<i>Supervisory current</i>	<i>340 µA</i>	
<i>Switch-on surge current</i>	<i>1.0 mA</i>	
<i>Alarm/operated current, LED On</i>	<i>4.0 mA</i>	
<i>Status indicator</i>	<i>Alarm (Red)</i>	
<i>Additional Remote LED current</i>	<i>5 mA maximum</i>	
<i>Product operating temperature</i>	<i>32 °F to 131 °F (0°C to 55°C)</i>	
<i>Humidity</i>	<i>0% to 95% RH</i> <i>(no condensation or icing)</i>	
<i>Effect of atmospheric pressure</i>	<i>None</i>	
<i>Air velocity</i>	<i>0 - 300 fpm</i>	
<i>IP rating</i>	<i>IP44</i>	
<i>Standards and Approvals</i>	<i>UL 268 7th Edition, ULC S529, FM 3230</i>	
<i>Dimensions</i>	<i>4 in. (100 mm) diameter x 1.50 in. (38mm) height</i> <i>(2in. (50) mm height with XPERT Intelligent Mounting Base)</i>	
<i>Weight</i>	<i>2.93 oz. (83 g)</i>	
<i>Materials</i>	<i>Housing: White flame-retardant polycarbonate</i> <i>Terminals: Tin plated stainless steel</i>	

Product Overview

Product	XP95A Multi-Criteria Detector (Smoke/Heat)
Part No.	AS5050-350
Digital Communication	XP95 protocol

Approvals



Product Information

The XP95A Multi-Criteria Detector (Smoke/Heat) uses new photoelectric sensing technology, Purelight®, to detect smoke particles entering the chamber. It reduces the possibility of false alarms whilst increasing the reliability of detecting a real fire.

- Approved to UL 268 7th edition and UL 521
- Purelight® optical technology provides enhanced smoke detection and false alarm management
- Internal drift compensation
- Compatible with XP95A systems
- Easy installation
- XPERT card addressing
- Base locking mechanism (grub screw)
- Polarity insensitive loop wiring
- In-built self-test
- Dual heat sensors

Electrical Description

The XP95A Multi-Criteria Detector (Smoke/Heat) is designed to be connected to a two-wire loop circuit carrying both data and a 17 V - 28 V dc supply. The detector is connected to the incoming and outgoing supply via terminals L1 and L2 in the mounting base. A remote LED indicator may be connected between the +R and -R terminals. A ground connection terminal is also provided.

Operation

The low profile design of the XP95A Multi-Criteria Detector (Smoke/Heat) is sleek and evolutionary, with a 360° LED indicator which illuminates red when in alarm.

At the heart of the photoelectric smoke sensor is Purelight® Sensing Technology which incorporates:

- Cone technology combined with a high-intensity infra-red LED to provide stability and accurate sensitivity to smoke.
- A sophisticated dynamic algorithm, providing transient rejection and compensation for drift whilst maintaining accurate sensitivity.

Signals from the photoelectric smoke chamber and temperature sensors are independent and represent the smoke level and air temperature respectively in the vicinity of the detector; the detectors micro-controller processes both signals. The temperature signal processing extracts only rate-of-rise information for combination with the smoke signal.

The optical sensor will trigger an alarm at 1.2 %/ft and the heat sensor at 69.8 °F (21 °C) rise. Minimum time to alarm is ten seconds.

The detector will not respond to slow increases in temperature, but a large, sudden change can cause an alarm without the presence of smoke.

The sensor will respond to smoke or heat, or a combination of both.

System compatibility

This XP95A detector has been designed to operate with XP95A detectors and loops. This XP95A detector can operate on an approved XPERT intelligent mounting base, however, the eighth bit of the address will be ignored.

The device will compensate for drift internally but will not report drift values to the fire alarm control panel. When internal drift limits are reached a fault analog value will be generated.

Maintenance and Service

Maintenance has to be done in accordance with all applicable standards. Clean the detector externally using a soft damp cloth.

Compatible Bases

Part Number	Product Name
AS5000-210	Soteria UL Base - 4"
AS5000-230	Soteria UL Base - 6"
AS5300-800	Soteria UL CO Sounder Base - 6" High Frequency
AS5300-802	Soteria UL Sounder Base - 6" High Frequency
AS5300-805	Soteria UL CO Sounder Base - 6" Low Frequency
AS5300-806	Soteria UL Sounder Base - 6" Low Frequency

	Smoke	Multi-Criteria	eat
For existing XP95A installations choose:	AS5050-250 XP95A Smoke Detector	AS5050-350 XP95A Multi-Criteria Detector (Smoke/Heat)	AS5500-450 XP95A Heat Detector

This datasheet is to be used for marketing purposes only. Please do not use it for installation purposes. For more information, please refer to the product installation guide or contact your sales manager. All information on this datasheet is subject to change without notice.

Technical Data P 5A Detectors

Detector Model No	AS5000-250	AS5000-350	AS5500-450
Detector Type	XP95A Smoke Detector	XP95A Multi-Criteria Detector (Smoke/Heat)	XP95A Heat Detector
Equivalent Obsolete Detector	AS55000-650	AS55000-886	AS55000-450
UL Listed Voltage	17 - 28 V dc	17 - 28 V dc	17 - 28 V dc
Modulation Voltage peak to peak	5 - 9 V	5 - 9 V	5 - 9 V
Maximum Alarm Current Load	4 mA	4 mA	2.5 mA
Surge Current	1 mA	1 mA	1 mA
Supervisory Current	340 µA	500µA	250µA
Additional Remote Load Current	5 mA	5 mA	5 mA
Operating Temperature Rating	N/A	Rate of Rise (RoR) 20°F/min (11°C/min)	131°F (55°C)
Sensitivity	UL 1.23%/Ft -2.09%/Ft ULC 1.44%- 2.3%/Ft	UL 1.23%/Ft -2.09%/Ft ULC 1.44%- 2.3%/Ft	N/A
UL Listing Instruction	Smoke-automatic fire detector for use with a S5022 UL/ULC listed base	Smoke-automatic fire detector head with integral heat detector for use with a S5022 UL/ULC listed base	Heat-automatic fire detector for use with a S5022 UL/ULC listed base
Test Method	Please refer to the panel manufacturer instructions Spray with any of the following smoke products: Solo Detector Testers Solo A10 • Smoke Sabre Smoke Detector Tester • Solo Detector Testers Solo 365 • Solo Detector Testers Testifie		Hair Dryer

Technical Data Soteria L Detectors

Detector Model No	AS5150-650**	AS5150-750**	AS5800-450
Detector Type	Soteria UL Smoke Detector	Soteria UL Multi-Criteria Detector (Smoke/Heat)	Discovery/Soteria UL Non-isolating Heat Detector
Equivalent Obsolete Detector	AS58000-650	AS58000-750	AS58000-450
UL Listed Voltage	17- 28 V dc	17 - 28 V dc	17- 28 V dc
Modulation Voltage peak to peak	5 - 9 V	5 - 9 V	5 - 9 V
Maximum Alarm Current Load	4 mA	4 mA	3.5 mA
Surge Current	1 mA	1 mA	1 mA
Supervisory Current	500 µA	500µA	500µA
Additional Remote Load Current	5 mA	5 mA	5 mA
Operating Temperature Rating	N/A	Modes 1,3,4 Rate of Rise (RoR) 20°F/min (11°C/min). Mode 5 135°F (57°C)	135°F (57°C) - 210°F (99°C)
Sensitivity	AS5000-250	AS5000-350	N/A
UL Listing Instruction	Smoke-automatic fire detector for use with a S5022 UL/ULC listed base	Smoke-automatic fire detector head with integral heat detector for use with a S5022 UL/ULC listed base	Heat-automatic fire detector for use with a S5022 UL/ULC listed base
Test Method	Please refer to test methods in the table above		

* All current measurements made with polling off **Isolation feature is only available in AS5150-650 and AS5150-750

XP95A & Soteria UL 268 7th Edition Detectors Installation Instructions

General

These instructions apply to the Avenger Soteria UL Bases. Please refer to the table below for instructions on how to install:

Applicable Wiring Diagram (page 3)	Applicable Products
Fig. 1 - New Installs (supports isolation)	AS5000-210 – Soteria UL Base - 4" AS5000-230 – Soteria UL Base - 6"
Fig. 2 - Retrofits or Isolator bypassed with a Remote LED	AS5000-210 - Soteria UL Base - 4" AS5000-230 - Soteria UL Base - 6"
Fig. 3 - Retrofits or Isolator bypassed with a Common Remote LED	AS5000-210 - Soteria UL Base - 4" AS5000-230 - Soteria UL Base - 6"

Installation

These products must be installed in accordance with the applicable NFPA standards, local codes and jurisdictional authorities. Failure to follow these instructions may result in failure of the detectors to report an alarm condition. Avenger Fire Detectors Limited is not responsible for detectors which are improperly installed, maintained or tested.

Before installing these products, check the continuity, polarity and insulation resistance of all wiring. Check that installation is in accordance with the fire system drawings and conforms to all applicable local codes such as NFPA 72.

Use 3" octagonal box for direct connection to the base. 4" octagonal and 4" square boxes may be used with compatible UL listed mounting brackets. When mounting on a wall, install 4" to 12" from the ceiling. Secure the base to the electrical box with appropriate screws. **Do not overtighten the screws.** For information on how to set the address of each device correctly refer to the section 'XPRT 8 Card Addressing' overleaf.

If you are using shielded cable, please follow the instructions below:


1. Connect the shield to the PE terminal on the base.
2. When shielded loop cable is used, connection of the shield, also known as the functional earth (FE), must be terminated in accordance with the control panel manufacturer's recommendations and local codes.
3. Unless instructed otherwise, ensure that all segments of the loop cable has functional earth (FE) continuity and take care that it is isolated from building earth (also known as protective earth (PE)) points such as metalwork, cable trays or junction boxes.

PLEASE NOTE:

Smoke detectors are NOT to be used with detector guards.

During construction work it is essential that the detector has its dust cover fitted. The build-up of dust inside a detector can lead to a trouble signal or false alarm.

Installation Diagram



Wiring

CAUTION: Do not use looped wire under wiring terminals. Break wire run to provide supervision of connections. Terminals L1 and L2 are polarity sensitive. It is recommended the wiring be no smaller than 18AWG (0.8mm²). Wire sizes up to 14 AWG (3.3mm²) may be used.

Warning: Check the base compatibility before installing
Check the polarity for Soteria UL detector installation




Fig. 1 Schematic Wiring Diagram: Soteria UL Base wiring with remote LED connection. To be used with new installs for XP95A and Soteria UL detectors




Fig. 2 Schematic Wiring Diagram: Soteria UL Base Detector to bypass isolator with remote LED connection. To be used in a retrofit application for the older version of XP95A or Discovery UL product. Can also be used when the isolator feature is not required





Fig. 3 Schematic Wiring Diagram: Soteria UL Base to bypass isolator with a Common Remote LED. To be used in a retrofit application for the older version of XP95A or Discovery UL product. Can also be used when the isolator feature is not required

AS45681-211

XP95 ISOLATOR BASE

This isolator base is for use with negative type isolators. The negative isolator which connects to this base is polarity sensitive and should be connected in accordance with the diagram below.



The earth terminal provided is for continuity of screen. Connection to this terminal is not required for operation of the base or isolator connected to it.

AS4705-700

SWITCH MONITOR MODULE



Product Overview

Product	Switch Monitor Module
Part No.	AS4705-700
Digital Communication	XP95 and Discovery

Product Information

The Switch Monitor Module is a loop-powered device incorporating a monitored input circuit for connection to remote switches, for indoor use only.

- Built-in isolator
- Visible LEDs
- Loop Powered
- Ground fault detection
- Selectable priority to monitor equipment where a fast response is required
- Interrupt facility
- Improved design for ease of wiring



Approvals

Technical Data

All data is supplied subject to change without notice Specifications are typical at 24 V, 73°F and 50% RH unless otherwise stated.

General	
Product Operating Temperature	32°F to 120°F
Humidity	10% to 93% RH (no condensation or icing)
Standards and Approvals	UL, ULC, FM, CSFM
Dimensions	4.9" W x 4.9" H x 1.175" D
Materials	Housing: UL94 V-0 polycarbonate
Wire Size	12 - 24 AWG

LED Status		
LED Color	Description	XP95/Discovery Compatibility
Green	Polling	x
Yellow (solid)	Isolation	x
Red	Alarm	x

Single Line Circuit (SLC) - Supervised Power Limited	
Supply Voltage	17 V to 28 V DC
Modulation Voltage	5 V - 9 V peak to peak
Supervisory Current	500 μ A
Switch-on Surge Current	900 μ A
Alarm/Operated Current, LED ON	1.6 mA per LED
Maximum Loop Current	1 A

Initiating Device Circuit (IDC)	
Wiring Styles	Supervised power limited Class A and Class B
Voltage	3.3 V DC
Line Impedance	100 Ω Max
End-of-Line Resistors*	47 k Ω

*Note: A UL listed end-of-line resistor is available at Avenger - Part No. 44251-146

AS4705-701
RELAY OUTPUT MODULE



Product Overview

Product	Relay Output Module
Part No.	AS4705-701
Digital Communication	XP95 and Discovery

Product Information

The Relay Output Module is a loop-powered device which incorporates a 240 V rated volt-free relay output. The module can be used outdoors if mounted in a suitable weatherproof enclosure.

- Built-in isolator
- Visible LEDs
- Loop Powered
- Improved design for ease of wiring

Technical Data

All data is supplied subject to change without notice Specifications are typical at 24 V, 73°F and 50% RH unless otherwise stated.

General		
Product Operating Temperature	32°F to 120°F	
Humidity	10% to 93% RH (no condensation or icing)	
Standards and Approvals	UL, ULC, FM, CSFM	
Dimensions	4.9" W x 4.9" H x 1.175" D	
Materials	Housing: UL94 V-0 polycarbonate	
Wire Size	12 - 24 AWG	
LED Status		
LED Color	Description	XP95/Discovery Compatibility
Green	Polling	x
Yellow (solid)	Isolation	x
Single Line Circuit (SLC) - Supervised Power Limited		
Supply Voltage	17 V to 28 V DC	
Modulation Voltage	5 V - 9 V peak to peak	
Supervisory Current	500 µA	
Switch-on Surge Current	900 µA	
Alarm/Operated Current, LED ON	1.6 mA per LED	
Maximum Loop Current	1 A	
Output Circuit		
Relay Output	Non-Supervised	
	Programmable	
	Dry Contact	
	30 V DC - 4 A - resistive	
	240 V AC - 4 A - resistive	

Approvals



AS56000-005

Intelligent Apollo Protocol Dual Action Polycarbonate Pull Station

The Avenger Intelligent Dual Action Polycarbonate Pull Station (AS56000-005) is a low profile, high quality addressable manual pull station. Easily recognizable during a fire situation, the AS56000-005 station is constructed of rugged polycarbonate for long life and reliability, with a red finish and raised white "FIRE" lettering. A red LED visible through the face of the station flashes during polling and turns on steady in alarm. Each station includes a key-lock for resetting (CAT B / CAT 30) which is common with the Axis AX Series Intelligent Fire Alarm Control Panels.

The AS56000-005 stations are UL 38 Listed, meet the ADAAG controls and operating guidelines, and the ADA requirements for five pound maximum activation force.

The AS56000-005, Intelligent Dual Action Polycarbonate Pull Station, can be mounted semi-flush onto a standard single-gang electrical outlet box. If installations require surface mounting, an optional polycarbonate surface back box (AS56000-006) is available.



Features

- ADA and ADAAG Compliant
- Dual Action Design
- Rugged Polycarbonate Construction
- Red Status LED
- Easy Key-Lock Reset
- Yellow Activation Stripe


Listings and Approvals

- UL 38 Listed: UNIU.S24867 / ML File: S25235
- ETL ANSI/UL 864 Listed: 101564744NYM-001
- NYCFCO COA: #6105A2

Operation

The AS56000-005 stations are operated by pushing in on the plate marked "PRESS", and then pulling down on the handle marked "PUSH", this will latch the handle in the down/activated position. Once latched, a bright yellow activated stripe will appear at the bottom of the station face. To reset the station, simply unlock the station with the reset key (keyed to match Axis AX Series Intelligent Fire Alarm Control Panels) and allow the door to open. This action resets the handle; while closing the door automatically resets the toggle switch to its "STDBY" position.

Wiring Diagram



Specification

Operating Voltage	20-28 VDC, with Communication Pulses 5-9 VDC
Operating Current	
Quiescent	0.2 mA
Alarm	3.8 mA
Operating Temperature	32 °F (0 °C) to 120 °F (49 °C)
Relative Humidity	10% to 93% Non-Condensing
Dimensions	
Pull Station	5 1/2 " H x 4 1/4 " W x 1" D
Surface Back Box	5 1/2 " H x 4 1/4 " W x 1 1/2 " D
Weight	
Pull Station	7.04 oz
Pull Station with Surface Back Box	11.5 oz
Analog Value	16 = Normal, 64 = Alarm, 4 = Trouble
Address Range	1 - 126 (DIP Switch Programmable)
Color	Red with Raised White Letters, White "PRESS" and "PUSH" Bars

Order Codes and Options

AS56000-005	Intelligent Dual Action Polycarbonate Pull Station
AS56000-006	Polycarbonate Surface Back Box

AS58000-011

Open-Area Sounder Visual Indicator



Product Overview

Product	Open-Area Sounder Visual Indicator
Part No.	AS58000-011
Digital Communication	Discovery (XP95 and CoreProtocol® compatible)

Compliance



Product Information

The Discovery UL Open-Area Sounder Visual Indicator is an alarm device made up of a sounder, visual indicator and short-circuit isolator. It is used to provide audible and visual warning of fire and is controlled by the fire control panel.

- 15 evacuation tones + 15 secondary or alert tones
- Seven volume levels
- Alarm switching by individual device, of all devices on the loop
- Independent control of sounder and beacon
- Set-up and testing of devices at point of installation
- Isolator status information
- Sounder automatically silences after 20 minutes (optional)
- Class change bell tone

Technical Data

All data is supplied subject to change without notice. Specifications are typical at 24V, 73°C and 50% RH unless otherwise stated.

Operating voltage*	17 V - 28 V dc*
Digital communication	Discovery, (XP95 and CoreProtocol compatible)
Supervisory current	< 750 µA
Switch-on surge current Sounder	< 2.6 mA for 1 second
operating Temperature	Variable
range Humidity	32°F to 100°F (0°C to 38°C)
	10% to 93% RH (no condensation or icing)
IP Rating	IP65
Standards & approvals	UL, CSFM
Dimensions	3.85 in. (98 mm) diameter x 4.09 in. (104 mm) height
Weight	3.7 oz (105 g)
Materials	Housing Red flame-retardant polycarbonate
	Terminals Nickel plated stainless steel

*Note: *Special application per UL 464. Requires a compatible control unit for proper operation.*

The right tone for your installation

The Discovery UL Open-Area Sounder Visual Indicator offers a choice of 15 evacuation tones, including the standard Avenger evacuation tone. One of these tones is selected during commissioning in order to suit local regulations or customs.

Whichever evacuation tone is selected, there is a secondary tone which may be used for alerting or warning of a possible evacuation.

The right level of sound

The sounder is set during commissioning to one of seven levels of sound.

Sounder; visual indicator or both

The Discovery UL Open-Area Sounder Visual Indicator normally switches both sounder and visual indicator to provide an alert or evacuation signal. There might be instances where a flash or a sounder would not be permitted.

It is a simple choice as to whether to switch both sounder and visual indicator together or to switch either as necessary.

Location specific volume setting

Detectors and sounder visual indicators are installed in many different types of environment. When configuring the Discovery UL Open-Area Sounder Visual Indicator the adjustment of the volume can be done at the point of installation.

The commissioning engineer simply sets the control panel to 'Set-up' and then walks from one device to the next to set the required volume, using a magnetic wand. When all devices have been set the engineer simply presses a button on the control panel which then registers all the individual volume settings.

The Discovery UL Sounder Visual Indicator Base offers a choice of 15 evacuation tones, including the standard Avenger evacuation tone. One of these tones is selected during commissioning in order to suit local regulations or customs.

The tones include those required by UK, Dutch, Swedish, German, Australian, New Zealand and North American standards.

Whichever evacuation tones is selected there is a secondary tone which may be used for alerting or warning of a possible evacuation.

In many installations a fire alarm must be raised by switching more than one sounder visual indicator to alert or alarm simultaneously. This is achieved with Sounder Visual Indicator Bases by assigning devices to groups on commissioning, with the group information being stored in each device. One command will then switch on all devices in the group.

Tone Settings

Byte value	Primary tone		Tone No.	Secondary tone		Tone No.
1	Apollo Evacuation Tone	567 Hz for 0.5 seconds 850 Hz for 0.5 seconds	T1	Avenger Alert Tone	1 second off, 1 second 850 Hz	T0
2	Alternating - Hochiki and Fulleon	925 Hz for 0.25 seconds 626 Hz for 0.25 seconds	T12	Continuous Hochiki and Fulleon	925 Hz	T11
3	Medium Sweep	800 Hz to 970 Hz at 1 Hz	T14	Continuous	970 Hz	T13
4	Fast Sweep	2500 Hz -2850 Hz at 9 Hz	T16	Continuous	2850 Hz	T15
5	Dutch Slow Whoop - sweep	500 Hz to 1200 Hz for 3.5 sec, 0.5 sec off	T3	Continuous	850 Hz	T2
6	DIN Tone - sweep	1200 Hz to 500 Hz for 1 sec	T4	Continuous	850 Hz	T2
7	Swedish Fire Tone	660 Hz, 150 ms on, 150 ms off	T18	Swedish all clear signal - continuous	660 Hz	T17
8	Australia - fast rise sweep	3 x (500 Hz - 1200 Hz for 0.5 sec), 0.5 sec off	T6	Australia Alert Tone	420 Hz, 0.625 sec, 0.625 sec off	T5
9	New Zealand -slow rise sweep	500 Hz - 1200 Hz for 3.75 sec, 0.25 sec off	T7	New Zealand Alert Tone	420 Hz, 0.625 sec, 0.625 sec off	T5
10	US Temporal LF ISO8201*	3 x (970 Hz, 0.5 sec on, 0.5 sec off) 1 sec off	T19	Continuous	970 Hz	T13
11	US Temporal HF ISO8201*	3 x (2850 Hz, 0.5 sec on, 0.5 sec off) 1 sec off	T20	Continuous	2850 Hz	T15
12	Simulated Bell-Continuous	Continuous	T8	Simulated Bell - Intermittent	1 second on 1 second off	T9
13	Emergency Warning Siren	N/A	T10	Emergency Warning - All Clear	N/A	T10
14	Evacuation Tone	970 Hz continuous	T13	Alert Tone	Silence for 1 second 970 Hz for one second	T19
15	Apollo Evacuation Tone	567 Hz for 0.5 sec, 850 Hz for 0.5 sec	T1	Avenger Alert Tone	1 second off 1 second 850 Hz	T0

* UL compliant tone

UL Listings

Control Unit Accessories, System

COMPANY

Avenger Systems LLC

11586 Zagarolo Lane
Las Vegas, NV 89141 United States

S35689

View model for additional information

Fire Alarm Equipment, Model(s): [AS4705-600](#), [AS4705-706](#), [AS4705-720](#)

Isolator modules (Isolator Base), Model(s): [AS45681-211](#)

Isolator modules (Isolator), Model(s): [AS55000-750](#)

Investigated to UL 864 (10th edition)

Relay Module, Model(s): [AS4705-701](#)

Switch Monitor Input/Output Module, Model(s): [AS4705-703](#)

Switch Monitor Module, Model(s): [AS4705-700](#)

Investigated to UL 864 (9th edition)

Contact module, Model(s): [AS6020-00](#), [AS6021-00](#)

Relay modules, Model(s): [AS6052-00](#), [AS6053-00](#), [AS6054-00](#), [AS6055-00](#)

Short circuit isolators, Model(s): [AS6003-00](#)

Last Updated on 2024-12-06

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL Solutions' Follow - Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL Solutions' Follow - Up Service. Always look for the Mark on the product.

UL Solutions permits the reproduction of the material contained in Product iQ subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from Product iQ with permission from UL Solutions" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "©2024 UL LLC."

Smoke Detectors for Fire Alarm Systems

COMPANY

Avenger Systems LLC

11586 Zagarolo Lane
Las Vegas, NV 89141 United States

S35692

Investigated to UL 268 (7th ed.)

Products Suitable for Ducts, D(I) and D(ST) are investigated to UL 268A

Detector Model	Application	Type	Compatibility Restrictions	Velocity Range (fpm)		date of Manufacture	Time of Manufacture Firmware Version	Firmware Version Update
				Min	Max			
AS2015-00	OAP, D(I)	P	D2	32	4000	2023-01-01	1.4	-
AS5050-250	-	P	D4	0	300	-	-	-
AS5050-350	-	P(IHD)	D5	-	-	-	-	-

Base Model	Related Detector	Control Unit Compatibility Restrictions
AS5000-210	AS5050-250, AS5050-350	B3
AS7013-00	ACC-V, ACC-V (WHT), AIE-EA, ACA-V,-W(d), ALK-V, ALO-V, ALO-V(WHT)	B2
AS7014-00	ACC-V, ACC-V (WHT), AIE-EA, ACA-V,-W(d), ALK-V, ALO-V, ALO-V(WHT)	B2
AS7017-00	ALG-V, ALK-V,-W, ALK-V2,-W,, ACA-V,-W(d), AIE-EA, ALN-V, ALN-V (WHT) (a), ACC-V, ACC-V (WHT), ACD-V (d), (f), ALO-V, ALO-V(WHT)	B2
AS7018-00	ALK-V,-W, ALK-V2,-W,, ACA-V,-W(d), AIE-EA, ALN-V, ALN-V (WHT) (a), ACC-V, ACC-V (WHT), ACD-V (d), (f), ALO-V, ALO-V(WHT)	B2

Investigated to UL 268 (previous editions)

Products Suitable for Ducts, D(I) and D(ST) are investigated to UL 268A

Detector	Compatibility	Velocity Range (fpm)	date of	Time of Manufacture	Firmware Version
----------	---------------	-------------------------	------------	------------------------	---------------------

Model	Application	Type	Restrictions	Min	Max	Manufacture	Firmware Versio	Update
AS2011-00	OAP, D	P	D2	0	4000	-	-	-
AS2012-00	OAP, D	P	D2	0	4000	-	-	-
AS2014-00 (a)	OAP, D(I)	P	D2	0	4000	-	-	-
AS2032-00	OAP	P	D2	0	4000	-	-	-
AS2033-00	OAP	P	D2	0	300	-	-	-
AS2034-00	OAP	P	D2	0	300	-	-	-
AS2041-00	OAP	P	D6	0	1000	-	-	-
AS2042-00	OAP, D, D(I)	P	D2	300	4000	-	-	-
AS2043-00	OAP, D, D(I)	P	D2	300	4000	-	-	-
AS2044-00	OAP, D, D(I)	P	D2	300	4000	-	-	-
AS5013-00	D(ST)	P	D2	300	4000	-	-	-
AS5014-00	D(ST)	P	D2	300	4000	-	-	-
AS5015-00	D	P	D2	0	4000	-	-	-

Base Model	Related Detector	Control Unit Compatibility Restrictions
AS2049-00	AS5015-00	B2
AS2050-00	AS2032, AS2033, AS2034, AS2042-00, AS2043-00, AS2044-00	B2
AS2051-00	AS2032, AS2033, AS2034, AS2042-00, AS2043-00, AS2044-00	B6
AS7001-00	-	B2
AS7002-00	-	B2
AS7003-00	-	B3
AS7004-00	-	B3
AS7005-00 (b)	ALG-V, ALK-V, ALK-V2, ACA-V, AIE-EA, ATG-EA, ATJ-EA, ALN-V,FWC-FSLC-SMK (a), and ACC-V, ACD-V, ACD-VW	B2
AS7008-00	-	B2
AS7015-00	ALO-V, ALO-V(WHT)	B3
AS7016-00	ALO-V, ALO-V(WHT)	B3

B2 - For connection to Listed control units with which compatibility was determined by test or a review of circuit parameters. Interconnection and compatible models indicated on installation wiring diagram for detector (base) and/or control unit.

B3 - For connection to a Listed open area protection smoke or heat detector head with which compatibility was determined by test or a review of circuit parameters. Refer to the manufacturer's installation instructions for a list of compatible models.

B6 - This base is also suitable for connection to any manufacturer's Listed compatible control unit in a four-wire configuration, as indicated on the installation drawing of control unit and/or detector/base.

D2 - For connection to Listed control units with which compatibility was determined by test or a review of circuit parameters. Interconnection and compatible models indicated on installation wiring diagram for detector (base) and/or control unit.

D4 - For connection to any manufacturer's Listed compatible control unit.

D5 - For use only with Listed control units with which compatibility was determined by test.

D6 - When using 2-wire bases Listing limited to specific system control unit. Information on compatible control unit indicated on installation drawing of control unit and/or detector. When using 4 wire bases, no restriction on compatibility.

OAP - Open Area Protection

D(I) - Duct Detector - Installation Inside Duct

P - Photoelectric

IHD - Includes Integral Heat Detector

D - Duct Detector

D(ST) - Duct Detector - Sampling Tubes

date of Manufacture identifies the manufacturing start date of all product models that will use the specific Time of Manufacture Firmware Version. The date of manufacture is noncoded and in the format YEAR (in 4 digits), MONTH (in letters), DAY (in 2 digits).

Time of Manufacture Firmware Version identifies a numerical and/or alphabetic series designation that is product and date-code specific and will only identify the Firmware Version at the time the product was manufactured. The numeric and/or alphabetic sequence is defined by the manufacturer.

Firmware Version Update is a numerical and/or alphabetic sequential identification that is product and date-code specific and sequentially identifies the Firmware Version Update from the previous version of firmware. The numerical and/or alphabetic sequence is defined by the manufacturer.

(a) - Complimentary Listed (UQGS, File S35692) as a Heat-Automatic Fire Detector

(b) - Low Frequency 520Hz Detector Sounder Base, also complimentary Listed (ULSZ, File S35913) as an Audible Signal Appliance.

Last Updated on 2024-11-07

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL Solutions' Follow - Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL Solutions' Follow - Up Service. Always look for the Mark on the product.

UL Solutions permits the reproduction of the material contained in Product iQ subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from Product iQ with permission from UL Solutions" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "©2024 UL LLC."

Heat-automatic Fire Detectors

COMPANY

Avenger Systems LLC

11586 Zagarolo Lane
Las Vegas, NV 89141 United States

S35691

Model No.	Type	Compatibility Restrictions	Contact Arrangement	Temp Range (°F)	Spacing (Ft)	
					Smooth Ceiling	to Wall or Partition
AS2010-00 (a)	FT/ROR	D2	-	135-194	70	35
AS2020-00	FT/ROR	None	-	-	-	-
AS2021-00	FT/ROR	None	-	-	-	-
AS2035-00	FT/ROR	None	-	-	-	-
AS2036-00	FT	None	-	-	-	-
AS2037-00	FT	None	-	-	-	-
AS5500-450	FT	D2	-	131-194	50	25

Base Model	Related Detector	Control Unit Compatibility Restrictions
AS2050-00, AS2051-00, AS2049	AS2020-00, AS2021-00, AS2035-00, AS2036-00, AS2037	None
AS7002-00, AS7001-00	AS2010-00	B2

B2 - For connection to Listed control units with which compatibility was determined by test or a review of circuit parameters. Interconnection and compatible models indicated on installation wiring diagram for detector (base) and/or control unit.

D2 - For connection to Listed control units with which compatibility was determined by test or a review of circuit parameters. Interconnection and compatible models indicated on installation wiring diagram for detector (base) and/or control unit.

FT/ROR - Fixed temperature/rate of rise combination

FT - Fixed temperature

(a) - Detector may be set for FT [Mode 0], FT/15° ROR [Mode 1] or 15° ROR [Mode 2] Operation.

Last Updated on 2024-10-17

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL Solutions' Follow - Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL Solutions' Follow - Up Service. Always look for the Mark on the product.

UL Solutions permits the reproduction of the material contained in Product iQ subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from Product iQ with permission from UL Solutions" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "©2024 UL LLC."

Audible-signal Appliances

COMPANY

Avenger Systems LLC
11586 Zagarolo Lane
Las Vegas, NV 89141 United States

S35913

Device	Model	Installation Location	Enclosure Ratings	
			Type Rating Per UL 50	IEC "IP" Rating
Accessories, Backboxes	AS4005-10	Indoor	—	—
Accessories, Enclosures	AS4008-10	Outdoor	—	—
Horns	AS4000-10	Indoor/Outdoor	—	—
Horn/strobes	AS4002-10	Indoor	—	—
Horn/strobes	AS4007-10	Indoor/Outdoor	—	—
Horn/strobes	AS4004-10	Indoor	—	—
Sounder Beacon	AS58000-011	Indoor/Outdoor	None	None

Model AS7005-00 - Low Frequency 520Hz Detector Sounder Base, Listed (UROX, File S35692) as an Audible Signal Appliance.

Last Updated on 2024-10-18

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL Solutions' Follow - Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL Solutions' Follow - Up Service. Always look for the Mark on the product.

UL Solutions permits the reproduction of the material contained in Product iQ subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from Product iQ with permission from UL Solutions" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "©2024 UL LLC."

FM Approvals

Detection, Fire Alarm and Signaling Equipment | Fire Alarm Control Panels | **Local Protective Signaling, Fire**

Model Oasis analog addressable

Product Description

Model Oasis analog addressable fire alarm control panel with Software UL-1204-01 or greater

Models	Description
Oasis	Fire alarm Control; With an 5.25A Power Supply (S406): 120/240VAC input power, 0.915A AC (240VAC), 1.83A AC (120V) input power; With an 10.25A Power Supply (S408): 120/240VAC input power, 1.25A AC (240VAC), 2.5A AC (120V) input power; Maximum Standby Current: S406 PSU - 1.9A; S408 PSU - 3.4A; Maximum Alarm Current: S406 PSU - 4A; S408 PSU - 8A

Oasis Basic System Components and Modules are:

Main Back Board (S722)	Minimum functions: Provides slots for required and optional panel modules, as well as for field wiring and power supply terminations. Minimum functions of the Oasis Fire Alarm Control Panel are provided when Slot A of the Main Back Board contains System A Panel Module, Slot B contains System B Panel Module, and Slots C, D, E, or F contain a Dual Loop Panel Module. Two addressable loops are provided by the Dual Loop Panel Module in this configuration. Modules can be added, configured, and replaced without altering field wiring connections. This modularity allows each Oasis Fire Alarm Control Panel to be customized for a specific operation. Required modules for minimum operation of an addressable Oasis Fire Alarm Control Panel include System A Panel Module (S769); System B Panel Module (S770), Dual Loop Panel Module (S758); Other functions: - NAC terminals 1 to 4 provide 24 VDC @ 2.5 A. In the default state, these circuits can be connected as four Class B supervised outputs. However, they can be configured as two Class A or two Class B and one Class A output. - 5 configurable Relay outputs (Trouble, Fire, Supervisory and two programmable by default)
System A Panel Module (S769)	Its functions: - NAC 1 and NAC 2 Class A or two Class B. Default Class B. - NAC 3 and NAC 4 Class A or two Class B. Default Class B. - 2.5A per Channel (Max 5A combined) - PSU monitor Battery disconnected, power failure, battery low, PSU ground trouble, charger trouble. - Power fail input A connection of - Ground trouble

System B Panel Module (S770)	Its functions: - AUX 24 Output 1 24V DC output @ 900mA - AUX 24 Output 2 24V DC output @ 900mA - Fire Routing Output 2 0V output in standby, switches to 24V when activated, requires End-of-Line (EOL) diode - Fire Routing Input Supervised input, requires 3.3K Ohm EOL resistor - Trouble Routing Output 24V output in standby, switches to 0V when activated, requires 3.3K Ohm EOL resistor - Trouble Routing Input Supervised input, requires 3.3K Ohm EOL resistor - Prog Routing Output Volt-free output measures 3.3K Ohms in standby, switches to 680 Ohms when activated - Prog Routing Input 1 Supervised input, requires 3.3K Ohm EOL resistor - Prog Routing Input 2 Supervised input, requires 3.3K Ohm EOL resistor - Fire Relay Volt-free contact rated at 30V DC, 1A, Resistive - Trouble Relay Volt-free contact rated at 30V DC, 1A, Resistive - Superv Relay Volt-free contact rated at 30V DC, 1A, Resistive - Programmable Relay 1 Volt-free contact rated at 30V DC, 1A, Resistive - Programmable Relay 2 Volt-free contact rated at 30V DC, 1A, Resistive
LCD Main Processor Board (S721)	Provides the touch display (Full color 800 x 480 LCD with resistive touch screen and automatic backlight dimming), central processing, and memory for the Oasis Fire Alarm Control Panel. The LCD Main Processor Board mounts to the fascia of the Oasis Fire Alarm Control Panel and includes hardware features such as connectors, ports, switches, LED indicators, and the internal buzzer
Dual Loop Panel Module (S758)	Monitors loop device status and provides status to the panel processor. It holds device configurations and operates in a standalone manner when catastrophic failures occur. The Dual Loop Panel Modules can be connected in any available slot (C-K) on the Main Back Board to provide this operating function SLC Loops rating (in/out)-- 36 VDC@400mA
Housings	4 Slot Standard Cabinet - 420mm (W) x 590mm (H) x 153mm (D), approximately 16.5in (W) x 23.2in (H) x 6in (D) 8 Slot Standard Cabinet - 540mm (W) x 720mm (H) x 160mm (D), approximately 21.3in (W) x 28.3in (H) x 6.3in
Standby Batteries with S406 PSU	Two 12 VDC, rechargeable, valve regulated, lead-acid, 60 AH Maximum
Standby Batteries with S408 PSU	Two 12 VDC, rechargeable, valve regulated, lead-acid, 100 AH maximum
Optional Modules below:	
Network Module (S723)	Provides supervised, enhanced high-speed communication for networking up to a maximum of 128 fire control panels. The network provided by this module can support combinations of Oasis Fire Alarm Control Panels and Oasis Vision Annunciators.
Printer (S768)	Printer is an optional feature for printing fire system events as they occur
Zone LED Module (S771)	The Zone LED module contains 48 LEDs and is connected to the LCD Main Processor Board of the Oasis Fire Alarm Control Panel. A maximum of three Zone LED modules can be connected to provide the fascia with 144 Zone LED indicators

FM Approvals

16 Channel I/O Interface Card (S560)	Provides additional input and output capabilities to the Oasis Fire Alarm Control Panel for life safety control signals.. Inputs and outputs can be selected for up to 16 individual channels. All inputs and outputs are configured in the same way as devices connected to addressable loops of the panel. The 16 Channel I/O Interface can be configured to contribute or act upon cause and effect logic.
Vision Unit (S787)	The Oasis Network Vision Annunciator is a display and control unit which duplicates the indications and primary controls of Oasis Fire Alarm Control Panels connected to the same network. The Annunciator connects via the network interface, and any number of repeaters can be connected up to the maximum number of nodes allowed by the network. Comes in the following configurations: OVC00NC-10 (Red), OVC00NC-40 (Gray), OVC00NC-60 (Black)
Media Gateway™ Panel Module (S788)	Provides supervised connectivity to a remote monitoring center via Sur-Gard Fibro or dial-up. SIA is the recommended format for usage, but Contact ID is also supported. Transmission can be made through one or two telephone lines, and/or IP through Ethernet
8 Channel Relay Panel Module (S791)	The 8 Channel Relay Panel Modules have 8 voltage-free, unsupervised changeover relay contacts, each of which can be individually programmed
Extension Board (S786)	Provides connections for 4 additional modules to be used with the Oasis Fire Alarm Control Panel. In this type of configuration, the extension board is installed to the right of the Main Back Board on the back plate. Can only be used with the Eight slot cabinet models
NAC 4 Channel Panel Module	Class A Circuit (1 and 2 or 3 and 4); Class B (separate); 2.5A per channel (maximum 5A combined)

Compatible SLC Devices are:

<i>Description</i>	<i>Hochiki part #</i>	<i>Avenger part #</i>
Ionization Smoke Detector	AIE-EA	
Photoelectric Smoke Detector	ALG-V	
Heat Detector	ATG-EA	AS2003-00
Heat Detector, Fixed Temp, Rate of Rise	ATJ-EA	AS2010-00
Base, 4"	YBN-NSA-4	AS7001-00
Short Circuit Isolator Base 4"	SCI-B4	AS7003-00
Base, 6"	HSB-NSA-6	AS7002-00
Short Circuit Isolator Base 6"	SCI-B6	AS7004-00
Dual Input Monitor Module	DCP-DIMM	AS6007-00
Fast Response Contact Module w/ Pigtales	DCP-FRCME-P	AS6013-00
Fast Response Contact Module w/ screw terminals	FRCME-S	AS6002-00
Fast Response Contact Module, 4" sq box.	FRCME-4	AS6013-00
Fast Response Contact Module w/ Terminals, Miniature	DCP-FRCME-M	AS6024-10
Analog Addressable Duct Detector	DH-98A	AS5001-00

Analog Addressable Duct Detector w/ relay	DH-98AR	AS5002-00
Short Circuit Isolator	DCP-SCI	AS6003-00
Dual Relay Module	R2M	AS6005-00
Analog Sounder Base, Aux Power	ASB	AS7008-00
Analog Sounder Base, Low Frequency, Aux Power	ASBL	AS7005-00
Supervised Output Module	SOM	AS6004-00
Conventional Zone Module	DCP-CZM	AS6011-00
Fast Response Contact Module, Class A	DCP-FRCMA	AS6020-00
Fast Response Contact Module, Class A w/ Short Circuit Isolators	DCP-FRCMA-I	AS6021-00
Fast Response Contact Module, Class A w/ Pigtails	FRCMA-P	AS6022-00
Fast Response Contact Module, Class A w/ Pigtails & Short Circuit Isolators	FRCMA-PI	AS6023-00
Dual Relay Module, 1 Amp	DCP-R2ML	AS6052-00
Dual Relay Module, 8 Amp	DCP-R2MH	AS6054-00
Dual Relay Module, 1 Amp w/ Short Circuit Isolators	DCP-R2ML-I	AS6053-00
Dual Relay Module, 8 Amp w/ Short Circuit Isolators	DCP-R2MH-I	AS6035-00
Supervised Output Module, Class A	DCP-SOM-A	AS6040-00
Supervised Output Module, Class A w/ Short Circuit Isolators	DCP-SOM-AI	AS6041-00
Supervised Output Module Release w/ Disable Keyswitch	DCP-SOM-R	AS6043-00
Addressable Manual Pull Station, Single Action w/ Cat 30 Key	DCP-AMS-KL	AS3032-10
Addressable Manual Pull Station, Single Action w/ Hex key	DCP-AMS	AS3031-10
Addressable Manual Pull Station, Dual Action w/ Cat 30 Key	DCP-AMS-KL-LP	AS3029-10
Addressable Manual Pull Station, Dual Action w/ Hex Key	DCP-AMS-LP	AS3030-10
Pull Station, Addressable, Single-Action	SG-32BK2-VG-B	AS3001-00
Pull Station, Addressable, Dual-Action	SG-32BK1-VG-B	AS3002-00
Analog Photoelectric Smoke Sensor	ALK-V	AS2005-00
Multi-Sensor	ACD-V	AS2014-00
Multi-Criteria Heat, Photo Sensor	ACC-V	AS2012-00
Multi-Criteria Heat, Photo Sensor	ACA-V	AS2008-00
Smoke Detector, Duct, Photoelectric	ALG-DH	AS2004-00
Smoke Detector, Duct, ALK	DH-99-A	AS5013-00
Smoke Detector, Duct, Relays, ALK	DH-99-AR	AS5014-00
Photoelectric Smoke Detector	ALN-V	AS2011-00
Remote Test Station for Duct Detectors – Alarm LED	MS-RA	AS5020-00

FM Approvals

Remote Test Station for Duct Detectors – Alarm LED w/ Reset Button	MS-RA/R	AS5021-00
Remote Test Station for Duct Detectors – Alarm LED w/ Reset Key Switch	MS-KA/R	AS5023-00

(See also CENTRAL STATION SIGNALING SYSTEMS.)

Details

Category	Local Protective Signaling, Fire
Class of Work	3010 - Fire Alarm Systems
Certification Type	FM Approved
Listing Country	United States of America

Company

Avenger Systems, LLC
11586 Zagarolo Lane, Las Vegas ,
Nevada 89141
United States of America
<http://avengersystems.com>

Detection, Fire Alarm and Signaling Equipment | Fire Alarm Control Panels | **Local Protective Signaling, Fire**

Supreme RS

Product Description

Supreme RS-H Series Fire Alarm Control Panels. The Supreme RS Series controls use firmware revision 07.xxxx. The controls use 12AH to 18AH batteries for inside the panel mount and up to 60AH for remote cabinet mount. Below see the table for model number breakdown for the Supreme RS Fire alarm Control Panels:

AS08bc-d0

b = This is reserved for definition of the number of loops, defined by the numbers 1, 2, 3:

1 – 1 Loop Hochiki Protocol;

2 – 2 Loop Hochiki Protocol;

3 – 1 Loop Hochiki Protocol; non expandable;

c = This is reserved for definition of the type of Communication Board that is installed on the panel, defined by the numbers 0, 5, 6 and 7:

0 – No communicators installed;

5 – e-Net interface is installed;

6 – Integrated Dialer is installed;

7 – e-Net interface and Integrated Dialer are installed.

d = This is reserved for definition of the enclosure color, defined by the numbers 1, 4:

1 – Red enclosure

4 – Grey enclosure.

a = This is reserved for definition of the loop protocol, defined by the numbers 1, 2, 3, 5, 6 and 7.

b = This is reserved for definition of the type of Communication Board that is installed on the panel, defined by the numbers 0, 1, 2, 3, 4, 5, 6 and 7 (see above).

<i>Description</i>	<i>Avenger part #</i>	<i>Hochiki part #</i>	<i>VES part #</i>
Ionization Smoke Detector		AIE-EA	VF2001-00
Photoelectric Smoke Detector		ALG-V	VF2002-00
Heat Detector		ATG-EA	VF2003-00
Fixed Temperature / Rate of Rise Heat Sensor	AS2010-00	ATJ-EA	VF2010-00
ALN-V Photoelectric Smoke Sensor	AS2011-00	ALN-V	VF2011-00
ACC-V Multi-Criteria Sensor	AS2012-00	ACC-V	VF2012-00
Base, 4"	AS7001-00	YBN-NSA-4	VF7001-00
Base, 6"	AS7002-00	HSB-NSA-6	VF7002-00
Dual Input Monitor Module	AS6007-00	DIMM	VF6007-00
Fast Response Contact Module w/ screw terminals		FRCME-S	VF6001-00
Fast Response Contact Module, 4" sq box.		FRCME-4	VF6002-00
Analog Addressable Duct Detector	AS5013-00	DH-99A	VF5013-00

Approvals

Analog Addressable Duct Detector w/ relay	AS5014-00	DH-99AR	VF5014-00
Short Circuit Isolator	AS6003-00	SCI	VF6003-00
Analog Sounder Base	AS7008-00	ASB	VF7008-00
Analog Sounder Base Low Frequency	AS7005-00	ASBL	VF7005-00
Supervised Output Module		SOM	VF6004-00
Conventional Zone Module	AS6011-00	CZM	VF6011-00
Fast Response Contact Module, Class A	AS6020-00	FRCMA	VF6020-00
Fast Response Contact Module, Class A w/ Short Circuit Isolators	AS6021-00	FRCMA-I	VF6021-00
Fast Response Contact Module, Class A w/ Pigtails	AS6013-00	FRCME-P	VF6013-00
Fast Response Contact Module, Class A w/ Pigtails & Short Circuit Isolators	AS6023-00	FRCMA-PI	VF6023-00
Dual Relay Module, 2 Amp	AS6052-00	DCP-R2ML	VF6052-00
Dual Relay Module, 8 Amp	AS6054-00	DCP-R2MH	VF6054-00
Dual Relay Module, 1 Amp w/ Short Circuit Isolators	AS6053-00	DCP-R2ML-I	VF6053-00
Dual Relay Module, 8 Amp w/ Short Circuit Isolators	AS6055-00	DCP-R2MH-I	VF6055-00
Supervised Output Module, Class A	AS6040-00	SOM-A	VF6040-00
Supervised Output Module, Class A w/ Short Circuit Isolators	AS6041-00	SOM-AI	VF6041-00
Addressable Manual Pull Station, Single Action, Hex Key	AS3031-10	DCP-AMS	VF3031-00
Addressable Manual Pull Station, Single Action w/ Cat 30 Key	AS3032-10	DCP-AMS-KL	VF3032-00
Addressable Manual Pull Station, Dual Action w/ Cat 30 Key	AS3029-10	DCP-AMS-KL-LP	VF3029-10
Addressable Manual Pull Station, Dual Action, Hex Key	AS3030-10	DCP-AMS-LP	VF3030-10
Analog Photoelectric Smoke Sensor		ALK-V	VF2005-00
Multi-Sensor	AS2014-00	ACD	VF2014-00
Remote Test Station for Duct Detectors – Alarm LED	AS5020-00	MS-RA	VF5020-00
Remote Test Station for Duct Detectors – Alarm LED w/ Reset Button	AS5021-00	MS-RA/R	VF5021-00
Remote Test Station for Duct Detectors – Alarm LED w/ Reset Key Switch	AS5023-00	MS-KA/R	VF5023-00
Short Circuit Isolator Base, 4"	AS7003-00	SCI-B4	VF7003-00
Analog Short Circuit Isolator Base, 6"	AS7004-00	SCI-B6	VF6024-00
Fast Response Contact Monitoring Mini Module	AS6024-00	FRCME-M	VF6024-00

Each of the models in the Matrix will be capable of interfacing with:

- eMatrix AS13xx-yyy
- eView Display AS1172-xx
- 16 Channel I/O AS1171-00

(See also CENTRAL STATION SIGNALING SYSTEMS, AUTOMATIC RELEASES FOR EXTINGUISHING SYSTEMS AND OTHER FIRE PROTECTION EQUIPMENT and AUTOMATIC RELEASES FOR PREACTION AND DELUGE SPRINKLER SYSTEMS).

Details

Category	Local Protective Signaling, Fire
Class of Work	3010 - Fire Alarm Systems
Certification Type	FM Approved
Release Control Panel Grouping (For use with Solenoid Valves)	Group 4 - Rated 22.6W and below
Listing Country	United States of America

Company

Avenger Systems, LLC
11586 Zagarolo Lane, Las Vegas ,
Nevada 89141
United States of America
<http://avengersystems.com>

Detection, Fire Alarm and Signaling Equipment | Fire Alarm Control Panels | **Central Station Signaling Systems, Fire**

Supreme RS

Product Description

Supreme RS-H Series Fire Alarm Control Panels. The Supreme RS Series controls use firmware revision 07.xxxx. The controls use 12AH to 18AH batteries for inside the panel mount and up to 60AH for remote cabinet mount. Below see the table for model number breakdown for the Supreme RS Fire alarm Control Panels:

AS08bc-d0

b = This is reserved for definition of the number of loops, defined by the numbers 1, 2, 3:

1 – 1 Loop Hochiki Protocol;

2 – 2 Loop Hochiki Protocol;

3 – 1 Loop Hochiki Protocol; non expandable;

c = This is reserved for definition of the type of Communication Board that is installed on the panel, defined by the numbers 0, 5, 6 and 7:

0 – No communicators installed;

5 – e-Net interface is installed;

6 – Integrated Dialer is installed;

7 – e-Net interface and Integrated Dialer are installed.

d = This is reserved for definition of the enclosure color, defined by the numbers 1, 4:

1 – Red enclosure

4 – Grey enclosure.

a = This is reserved for definition of the loop protocol, defined by the numbers 1, 2, 3, 5, 6 and 7.

b = This is reserved for definition of the type of Communication Board that is installed on the panel, defined by the numbers 0, 1, 2, 3, 4, 5, 6 and 7 (see above).

<i>Description</i>	<i>Avenger part #</i>	<i>Hochiki part #</i>	<i>VES part #</i>
Ionization Smoke Detector		AIE-EA	VF2001-00
Photoelectric Smoke Detector		ALG-V	VF2002-00
Heat Detector		ATG-EA	VF2003-00
Fixed Temperature / Rate of Rise Heat Sensor	AS2010-00	ATJ-EA	VF2010-00
ALN-V Photoelectric Smoke Sensor	AS2011-00	ALN-V	VF2011-00
ACC-V Multi-Criteria Sensor	AS2012-00	ACC-V	VF2012-00
Base, 4"	AS7001-00	YBN-NSA-4	VF7001-00
Base, 6"	AS7002-00	HSB-NSA-6	VF7002-00
Dual Input Monitor Module	AS6007-00	DIMM	VF6007-00
Fast Response Contact Module w/ screw terminals		FRCME-S	VF6001-00
Fast Response Contact Module, 4" sq box.		FRCME-4	VF6002-00
Analog Addressable Duct Detector	AS5013-00	DH-99A	VF5013-00

Approvals

Analog Addressable Duct Detector w/ relay	AS5014-00	DH-99AR	VF5014-00
Short Circuit Isolator	AS6003-00	SCI	VF6003-00
Analog Sounder Base	AS7008-00	ASB	VF7008-00
Analog Sounder Base Low Frequency	AS7005-00	ASBL	VF7005-00
Supervised Output Module		SOM	VF6004-00
Conventional Zone Module	AS6011-00	CZM	VF6011-00
Fast Response Contact Module, Class A	AS6020-00	FRCMA	VF6020-00
Fast Response Contact Module, Class A w/ Short Circuit Isolators	AS6021-00	FRCMA-I	VF6021-00
Fast Response Contact Module, Class A w/ Pigtails	AS6013-00	FRCME-P	VF6013-00
Fast Response Contact Module, Class A w/ Pigtails & Short Circuit Isolators	AS6023-00	FRCMA-PI	VF6023-00
Dual Relay Module, 2 Amp	AS6052-00	DCP-R2ML	VF6052-00
Dual Relay Module, 8 Amp	AS6054-00	DCP-R2MH	VF6054-00
Dual Relay Module, 1 Amp w/ Short Circuit Isolators	AS6053-00	DCP-R2ML-I	VF6053-00
Dual Relay Module, 8 Amp w/ Short Circuit Isolators	AS6055-00	DCP-R2MH-I	VF6055-00
Supervised Output Module, Class A	AS6040-00	SOM-A	VF6040-00
Supervised Output Module, Class A w/ Short Circuit Isolators	AS6041-00	SOM-AI	VF6041-00
Addressable Manual Pull Station, Single Action, Hex Key	AS3031-10	DCP-AMS	VF3031-00
Addressable Manual Pull Station, Single Action w/ Cat 30 Key	AS3032-10	DCP-AMS-KL	VF3032-00
Addressable Manual Pull Station, Dual Action w/ Cat 30 Key	AS3029-10	DCP-AMS-KL-LP	VF3029-10
Addressable Manual Pull Station, Dual Action, Hex Key	AS3030-10	DCP-AMS-LP	VF3030-10
Analog Photoelectric Smoke Sensor		ALK-V	VF2005-00
Multi-Sensor	AS2014-00	ACD	VF2014-00
Remote Test Station for Duct Detectors – Alarm LED	AS5020-00	MS-RA	VF5020-00
Remote Test Station for Duct Detectors – Alarm LED w/ Reset Button	AS5021-00	MS-RA/R	VF5021-00
Remote Test Station for Duct Detectors – Alarm LED w/ Reset Key Switch	AS5023-00	MS-KA/R	VF5023-00
Short Circuit Isolator Base, 4"	AS7003-00	SCI-B4	VF7003-00
Analog Short Circuit Isolator Base, 6"	AS7004-00	SCI-B6	VF6024-00
Fast Response Contact Monitoring Mini Module	AS6024-00	FRCME-M	VF6024-00

Each of the models in the Matrix will be capable of interfacing with:

- eMatrix AS13xx-yyy
- eView Display AS1172-xx
- 16 Channel I/O AS1171-00

(See also CENTRAL STATION SIGNALING SYSTEMS, AUTOMATIC RELEASES FOR EXTINGUISHING SYSTEMS AND OTHER FIRE PROTECTION EQUIPMENT and AUTOMATIC RELEASES FOR PREACTION AND DELUGE SPRINKLER SYSTEMS).



Details

Category	Central Station Signaling Systems, Fire
Class of Work	3010 - Fire Alarm Systems
Certification Type	FM Approved
Listing Country	United States of America
Release Control Panel Grouping (For use with Solenoid Valves)	Group 4 - Rated 22.6W and below

Company

Avenger Systems, LLC
11586 Zagarolo Lane, Las Vegas ,
Nevada 89141
United States of America
<http://avengersystems.com>

Avenger Approvals



شركة الراجحي للبناء والتعمير

Al-Rajhi Building & Constructions Co.

س.ت. ١٠١٠٠٨٩٨٠٨٠

عضوية رقم ٤٠٨٢١

عقد توريد نظام الإطفاء بغاز FM200 لمشروع إنشاء معهد ريادة الأعمال بالرياض

إنه في يوم الاثنين الموافق ٢٥/٠٦/٢٠١٨ م تم الاتفاق بين كل من:

الطرف الأول: شركة الراجحي للبناء والتعمير عنوانها الرياض، ص. ب ٣٥٠٠٩ سجل تجاري: ١٠١٠٠٨٩٨٠٨٠

هاتف: ٤٢٣٥٠٦٨ فاكس: ٤٢٣٥٠٦٨ يمثلها المهندس/ عبدالله عبدالمحسن العصيمي.

الطرف الثاني: شركة أصال المقاولين للتجارة والمقاولات وعنوانها الرياض - حي الفاروق طريق المدينة المنورة - مقابل العويضة ، ص ب ٤١٢٠٨ ، الرياض ١١٥٢١ ، سجل تجاري : ١٠١٠١٤٢٤٩١ ، هاتف : ٤٧١٣١٧٦ فاكس : ٢٤٢٠١٤٠٠ ويمثلها في التوقيع المدير التنفيذي / المهندس مجدى عبد العزيز

مقدمة:

حيث أن الطرف الأول المقاول الرئيسي لمشروع إنشاء معهد ريادة الأعمال بالرياض (المالك: المؤسسة العامة للتدريب التقني والمهني) ومن متطلباته نظام الإطفاء بغاز FM200 وحيث أن الطرف الثاني يمتلك شركة لتوريد الأعمال المطلوبة وتوابعها وبناء عليه أبدى الطرف الثاني استعداده وقبوله للقيام بتوريد المواد موضوع العقد وقد اتفق الطرفان وهما بكامل الأهلية الشرعية والنظامية على ما يلي:

مادة (١) مقدمة العقد:

تعتبر مقدمة هذا العقد جزء لا يتجزأ منه.

مادة (٢) وثائق العقد:

تعتبر الوثائق التالية جزءاً لا يتجزأ من هذا العقد، ويرجع إليها في كل ما لم يرد عليه النص في هذا العقد:

١- هذا العقد.

٢- خطاب اعتماد الغاز لغرفة الارشيف والدايتا رقم ٤٣/٦٦٠٣٥ وتاريخ ١٥/٠٤/١٤٣٩ هـ .

٣- خطاب الاعتماد من المالك - المؤسسة العامة للتدريب التقني والمهني رقم ٤٣/١٦٩٥٠٤ وتاريخ ٠١/١٢/١٤٣٨ هـ

وخطاب اعتماد المواد رقم ٤٣/١٤٣٧٣٥ وتاريخ ١٢/٠٩/١٤٣٩ هـ .

٤- عرض السعر المقدم من الطرف الثاني برقم QT22532-11-17REV05 وتاريخ ٢٤/٠٦/٢٠١٨ م.

٥- تعتبر جميع الوثائق والمستندات المذكورة أعلاه والمرفقة بالعقد تمثل وحدة واحدة وتفسر بعضها بعضاً وفي حال وجود أي تعارض تسود الوثيقة التي تأتي أولاً حسب الترتيب أعلاه.

مادة (٣) موضوع العقد:

أن يقوم الطرف الثاني بتوريد نظام الإطفاء بغاز FM200 حسب العينات والمواصفات المعتمدة من المالك بموجب الشروط والأسعار والأحكام المدرجة في هذا العقد، وهي نفس الغاية من أصال العقد حيث يجب أن تكون المواد الموردة حسب المواصفات المطلوبة وتخضع للموافقة من قبل الإدارة أو المهندس أو الطرف الأول وبيانها حسب خطاب المالك والعينات المعتمدة .

مادة (٤) نطاق الأعمال Scope of Works المطلوب من الطرف الثاني:

١- تقديم المواصفات مع العينات للطرف الأول لاعتمادها من المالك وعلى الطرف الثاني تقديم التوضيحات اللازمة والمراجعة

لاستيفاء أي ملاحظات أو تعديلات حال طلبها من المالك وعلى الطرف الثاني مراجعة الجهة المختصة لدى المؤسسة العامة

للتدريب التقني والمهني لإنهاء كامل الاعتمادات.



Owner:  Gulf Real Estate Closed Joint Stock Company	Consultant:  اتحاد المستشارين CONSOLIDATED CONSULTANTS	Contractor:  ADEX Contracting Maintenance & Operation
PROJECT: Olaya Lifestyle Retail Riyadh		

SUBMITTAL FORM (SHOP DRAWING) (SMS)

SUBJECT: FM200 FIRE SUPPRESSION SYSTEM DRAWINGS

Discipline: ☐ Arch ☐ Civil ☒ Mech. ☐ Elect ☐ HVAC ☐ LS

Specs. Code	IFC DWG Ref.	Submittal no:	RLF-OLS-M-SD-061-Rev.00
21 20 00 - PRE ENGINEERED FIRE SUPPRESSION SYSTEM	-	☒ New sub ☐ Re-submitted	1 st sub date: 20-09-2022 Present sub date: Previous sub date:


ITEM NO	DOCUMENT NUMBER	TITLE	REV	APPROVED CODE	SUBMITTAL SCHEDULED DATE
1	OLS-SD-M-FM200-SVR-101	SERVER ROOM (B1-15)	00		
2	OLS-SD-M-FM200-ELR-102	ELECTRICAL ROOM (GF-15)	00		
3	OLS-SD-M-FM200-RMR-103	RMU ROOM (GF-17)	00		

Sub-contractor Name:

Contractor's Comments:

See Attachment ☐

01 SET / 02 CDs

Note: This review does not relieve the contractor of his responsibilities under the terms of the contract nor authorize additional compensation. Contractor Signature:  Date: 20-9-2022



Consultant's Comments:

Refer comments sheet. (Attached)
Refer to comments on attached A4 sheet.

See Attachment ☒

Construction Manager & Client Comments:

See Attachment ☐

Status:	A ☐ Approved	B ☒ Approved as noted	C ☐ Revise and submit	D ☐ Rejected	E ☐ No Action
Sign & Date	Consultant	Construction Manager	Client		
☐ Arch ☐ Civil ☐ Mech ☐ Elec ☐ HVAC ☐ LS	Sign:  Date: 21/9/2022	Sign:  Date: 21/9/2022	Sign:  Date: 21/9/2022		
Consolidated Consultants Received Date: 20/09/2022 8:50 AM					
Doc. Ref: CSF08a/3 Issue Date: 11 sept. 2019					

Consultant's Comments

Subject: FM200 System Shop Drawings

Submittal No.: OLS-SD-061-R0

Submission Date: 20TH Sep 2022

Approval Status: **B-Approved as Noted**

1. All the pipes should be seamless schedule-80, confirming to ASTM A106.
2. Nozzle location to be in accordance with respective room's equipment layout.
3. Integrate ventilation system with FM200 system.
4. Final approval is subject to acceptance by civil defence.

Reviewed by:

Anwar Quadri
20/09/2022

Anwar Quadri

Mechanical engineer – CCG

Anwar Quadri
21/09/2022

OLAYA LIFE STYLE RETAIL

SUBMITTAL NO.: RLF-OLS-M-SD-061-REV.00

DATE: 20-SEPT-2022

DESCRIPTION: FM200 fire suppression system drawings (Server room at B1, RMU Room and Electrical Room at GF).

Electrical Consultant Comments:

1. FM200 control panel shall be provided with battery backup minimum of 24-hours with 5-mins alarm.
2. System shall interface with the fire alarm system to indicate: -
 - a. System operational Status
 - b. System stage alarm
 - c. System discharging
 - d. Common fault alarm
3. FM 200 cabling shall be fire resistant FP 200 cables
4. Wiring for all bell circuits shall be minimum 2.5 mm2 and wiring for all signaling circuits shall be minimum 1.5 mm2.
5. Contractor shall provide a power from the emergency source. Wiring for 230 V AC power to each FM200 CP shall be minimum 2.5 mm2.
6. All exposed conduit shall be GI conduit. Pull box shall be accessible if above the false ceiling, below raised floor and any other area.
7. FM 200 contractor shall submit material submittal for the Conduit, boxes and wiring for approval or use the same material approved for main contractor (ADEX).
8. FM200 system shall be interfaced with HVAC equipment for the dedicated room. The operation of HVAC shall be as per approved sequence of operation.
9. Sequence of operation shall comply with project specification section 21 20 00, Part-3.1 and subject to mechanical engineer approval.
10. Testing and commissioning of clean agent system as required by NFPA 2001 for approval of systems.
11. Contractor shall submit method statement of FM200 system with all supported documents.
12. Comments on material submittal RLF-OLS-M-MT-068 shall also be compiled.
13. Final approval of FM200 system subject to acceptance of local Civil defense authority.

K. S. M.
20/9/2022

20/9/2022

Owner 	ADVANCED LEARNING SCHOOL 	Client: الخاليجية للاستثمار والتنمية AL KHALIJYAH INVESTMENT & DEVELOPMENT 
Consultant 	Contractor: 	

MATERIAL SUBMITTAL FORM

Submittal Number:	301-ALS-ADX-DAO-MAR-M-00311	Original Submittal Date:	08-06-2023
Submittal Revision:	R0	Previous Submittal Date:	
		Present Submittal Date:	

- ☐ Civil ☐ Structural ☐ Architectural ☐ Electrical ☒ Mechanical ☐ General ☐ Interior ☐ Urban/ Planning
☐ Landscaping

No.	Material	Manufacturer	Supplier	Country of Origin
1	FM 200 & CO2 FIRE FIGHTING SYSTEM	AVENGER - LUXEMBURG	CSC CO.	AS PER PART LIST
	SUPPLY, INSTALLATION & CALCULATION			

Specification References / BOQ Reference DIV.15 ITEMS (AS PER COMPLY STATEMENT)	Drawing Reference /Location / Use THROUGHOUT FIRE FIGHTING PROJECT DRAWINGS	Information submitted and attached: ☒ Certificates ☒ Technical Brochure / Catalogs ☒ Manufacturer's Data & Specs. ☐ O & M Manual ☐ Spare Parts List ☐ As Built Drawings ☐ Samples ☐ Warranty ☐ Others ()	Approval Status Action Code: B ☐ A-Approved ☒ B-Approved with Comments ☐ C- Revise & Resubmit ☐ D- Rejected ☐ E- No Action
--	---	---	---

Contractor: Project manager: Bashar Zidan Signature:  Date: 08/06/2023	
--	---


DAO Comments:

Refer to the Comments on the attachments (7 page)

Comments

(Print) Name: M. Bakhit	Position: Mech. Eng	Signature: 	Date: 13-6-2023
DAO Representative: (Print) Name: Ahmad Hatis Hasan Aly		Signature: 	Date: 13/6/2023
Position: Resident Engineer		Date Returned:	
Contractor signature		Receive for	Date:

This review does not relieve the contractor of his responsibilities under the terms of the contract nor authorize additional compensation.

Consultant:  دارال عمران DAR AL-OMRAN	ADVANCED LEARNING SCHOOL 	Client:  مجموعة الاسفادي AL-SAFADI GROUP
شركة التعلیم المتطور ADVANCED LEARNING COMPANY 	Contractor:  فديكس FDEX	


ATTACHMENT TO SUBMITTAL			
Submittal No.	301-ALS-ADX-DAO-MAR-M-00311	Submittal Date:	2023-06-13
Submittal Revision	R0		

DAO Comments:

FM200 & CO2 FIREFIGHTING SYSTEM:

- 1- Final approval from the Client.
- 2- Certificate of warranty from the initial delivery of the project 3 years.
- 3- Compliance with the attached project specifications, any violation of the specification is the responsibility of the contractor and supplier.
- 4- The supplier is responsible for the installation, commissioning, testing, and compliance of materials with Civil Defense and NFPA requirements.
- 5- Submit Operation and Maintenance data, certificate, Origin and spare parts list.
- 6- Submit VO before to delivery and installation.
- 7- Any delay on the responsibility of the contractor.
- 8- Coordination with the electrical.

9- Justification attached letter in page ③



(Print) Name: Mohammed Bakhit Position: Mech.Eng Signature:  Date: 13/06/2023

DAO Representative: Hosam Aly
 Position: Project Architect / Director

Signature: 
 Date Returned: 17/6/2023



Shop Drawing

Ref. No: ALMA-SD-2025-02-R01	Date: 22-05-2025
Project No.: 1382 - 1384	ITP No. & Item No.:
Supervision Consultant: CSI	Contractor: ALMA HILLS FOR FIRE SOLUTIONS
Subject: SD for FM-200 Control Room in WH01-04	

Scheduled Inspection Details

This section is completed by the Contractor and copied to the Supervising Consultant 24 hours prior to the proposed inspection

Civil	☐	Structural	☐	Architectural	☐	Mechanical	☒	Electrical	☐						
HVAC	☐	Plumbing	☐	Lifts	☐	Utilities	☐	Fire Life & Safety	☐						
Level :				Location :	WH01-04										
Inspection Date :	22-05-2025			Inspection Time :	10:00 PM										
Drawing Ref. :				Attachments :											
Testing Requirements: SD for FM-200 Control Room in WH01-04															
Submitted by (Name) :				Submitted by (Signature) :											

Contractor Inspection

This section is completed by the Contractor and handed to the Supervising Consultant prior to the inspection

Comments :	
The Contractor confirms that the work presented for inspection has been executed as per the approved drawings, specifications, materials, method statements and quality plan.	
Contractor Construction Manager : Eng: Sati Sign :	Contractor QC Manager : Eng: ABDUL RAHEEM Sign :

Supervising Consultant Inspection

Comments :		
1. Rigid support to be provided in each change of direction, near to the cylinder outlet and near to the nozzle to prevent the pipe movement due to thrust forces occurs during the gas discharge		
Does the work presented for inspection fully comply with the approved drawings, specifications, materials, method statements and quality plan?		
Approved ☐	Approved with Comments ☒	Revise&Resubmit ☐ Rejected ☐
Inspector's Name : Eng.Jamsheer Kappakunnan	Inspector's Signature : 	Date : 24/05/2025



Shop Drawing

Ref. No: ALMA-SD-2025-02	Date: 18-05-2025
Project No.: 1382 - 1384	ITP No. & Item No.:
Supervision Consultant: CSI	Contractor: ALMA HILLS FOR FIRE SOLUTIONS
Subject: SD for FM-200 Communication Room in WH01-04	

Scheduled Inspection Details					
This section is completed by the Contractor and copied to the Supervising Consultant 24 hours prior to the proposed inspection					
Civil ☐	Structural ☐	Architectural ☐	Mechanical ☒	Electrical ☐	
HVAC ☐	Plumbing ☐	Lifts ☐	Utilities ☐	Fire Life & Safety ☐	
Level :		Location :	WH01-04		
Inspection Date :	18-05-2025	Inspection Time :	10:00 PM		
Drawing Ref. :		Attachments :			
Testing Requirements: SD for FM-200 Communication Room in WH01-04					
Submitted by (Name) :		Submitted by (Signature) :			

Contractor Inspection	
This section is completed by the Contractor and handed to the Supervising Consultant prior to the inspection	
Comments :	
The Contractor confirms that the work presented for inspection has been executed as per the approved drawings, specifications, materials, method statements and quality plan.	
Contractor Construction Manager : Eng: Sati Sign : 	Contractor QC Manager : Eng: ABDUL RAHEEM Sign : 

Supervising Consultant Inspection			
Comments : 1. Ensure the design complies with NFPA 2001 (latest edition), local civil defense regulations. 2. General notes are not clear to read, provide clear file. 3. Dimensions for the room to be provided 4. Confirm integration with BMS, fire alarm system, HVAC shutdown, door release, and power isolation as applicable 5. Typical installation details for control panel, manual release, detectors, Bell, flasher, piping and supports are missing.			
Does the work presented for inspection fully comply with the approved drawings, specifications, materials, method statements and quality plan?			
Approved ☐ Approved with Comments ☐ Revise&Resubmit ☒ Rejected ☐			
Inspector's Name : Eng. Jamsheer Kappakunnan		Inspector's Signature :  Date : 19/05/2025	

Client: 	Project: ALBASATEEN OFFICES	Consultant:  شركة و.د. عبد الوهاب محمد الهندسة والبناء Waleed A. Al Dubaieki Engineering Consulting Co.	MEP Contractor 
--	---------------------------------------	---	---

MATERIAL SUBMITTAL	TRM NO.	CONT	PROJ	PART	TRADE	NO	REV
		APT	ABO	SAM	ME	25	02

To: Consultant Technical Office	From: MEP Contractor Technical Office
Attention: Eng. MOHAMED EISA	By: Eng. MOHAMED Hamed
☐ Civil	☐ Arch
☐ Electrical	☒ Mechanical
☐ Others	

1. Material Description:	Date: 06/01/2025
--------------------------	------------------


FM-200 SYSTEM (AVENGER)			
Area of Application:	ALL PROJECT AREA	Design Type :	FM-200 SYSTEM
Plot :		B.O.Q. Ref. No. :	
Drawing Ref. :	FM-200 SYSTEM	Material Color :	
ITEM NO BOQ	Discription		Supplier Approval
			AL-ALYAA
Specification Ref. :		Material code:	

2. MANUFACTURER/SUPPLIER :			
Company Name :		AVENGER / CSC / AL-ALYAA	
Address :	Riyadh	Tel No.	
Approved TRM No. :	APT-ABO-SAM-MECH-025-R2		
Local Agent :			
3. DELIVERY :			
Country of Origin :			

Availability	☒ Locally Manufactured	☐ Overseas
--------------	--	-----------------------------------

We certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated; the submitted items in conformity with the above and deliver same timely. Also that the material sources indicated above have been reviewed in detail and that they will supply


Submitted By: Eng. Mohamed Hamed	Signature: 	Date: 06/01/2025
----------------------------------	--	------------------

FM-200 manufactured by AVENGER Systems (USA) is acceptable with following notes: Tech. Support Engineer: * Submit method statement & T&C procedure. Sign:  Date: 09/01/25	☒ A- Approved ☒ B- Approved As Noted ☐ C- Revise & Resubmit ☐ D- Rejected
--	--

3. Tech. Support Comments: * Submit all certificates / warranties ① All pipes must be ERW Gal. Steel, Sch. 40. Grade A, ASTM 53. & use rigid support. ② Manifold: Sch. 80. Black Seamless Threaded. Guaranteed for 2" and below. & welded for 2 1/2" & above. ③ Fittings: For sizes 50 mm & below are ASTM A105. Cast/Forged. Threaded good. For sizes 60 mm & above are grooved painted red.	☐ Sample Required ☒ Tests Required ☐ Additional Info. Required ☒ Manufacturer's Guarantee Required
--	---

Consultant Tech. Engineer:	Consultant Project Manager:
----------------------------	-----------------------------

Client Tech. Engineer:	Client Tech. Project Manager:
------------------------	-------------------------------

Sign: 	Sign: 
Date:	Date:

AMC	By
-----	----

All pipe size shall be based on approved hydraulic calculations. All standard sizes of U-Bolts/Clamps, washers, nuts. Shall be as per NFPA Codes & Electric Code. All system components, pipe, sheet, calculation & drawings to be submitted for civil defense department for final approval. All equipment shall be UL/FH approved for system. Submit Schedule & Sequence of operation for system.



PRSD Submittal Revision

 Submittal

General

Project Name: EMERGING PHARMACEUTICAL SITE READINESS	Project Number: C/0081/23
Contract No: C/0081/23	Contractor: RITEC
Submittal Record #: SBMT-C/0081/23-0131	Rev#: 2
Creator: Khalid Hussein	Creation Date: 10/16/2024 05:13 AM (UTC-8)
Status: Completed	Trade: Mech

Submittal Details

Submittal Title: FM 200 SYSTEM	Specify:
Submittal Description: FM 200 SYSTEM	Ref. No.:

Submittal Type

Drawing: No	Material: Yes	Samples: No	Catalogue: No
Mockup: No	Other: No	Specify:	

Contractors Remarks

Remarks:	Contractor, Project Manager:
Enclosures No	Attached No
Returned:	Remarks:

Reviewed By PRSD Engineers

Comment: Action Code: B The manufacturer AVENGER for FM200 is acceptable. The contractor is to submit a complete Consolidated Report for each system including a complete layout by the specialized company CSC.
Date: 10/17/2024
PRSD Engineer Name / Arturo Ongoco
Signature:

Reviewed By PMD PM

Comment:
PRSD Project Manager: Jessie Laya

Revision Decision

Revision B – Approved as noted. (Work may proceed, Action(s): res)ubmission not required	Decision 10/19/2024 08:53 PM (UTC-8) Date:
---	---

 Revision Items

1 Item(s)

No.	Sm	Item Description	Trade	Item Action
001		Avenger HFC227ea FM200 System (Profile)	Mech	B

 Record - General Comments

1 Item(s)

Comment Date	Created By	Company
10/17/2024 06:22 AM (UTC-8)	Arturo Ongoco	KFSHRC
Comment Text Action Code: B The manufacturer AVENGER for FM200 is acceptable. The contractor is to submit a complete Consolidated Report for each system including a complete layout by the specialized company CSC.		

1 Item(s)

File Name	Title	Revision No.	Size	Issue Date
KING FAISAL SPECIALIST HOSPITAL.pdf			46 MB	
Comment Date		Created By		Company
Comment Text				
Attachments				

 <Revision Items> - Line item - details**Line Item No: 001**

General

Item No.:
Description: Avenger HFC227ea FM200 System (Profile)
Trade: Mech
Line Item Status: B

Please Use the Up Comment Tap

Steps to fill the submittal form:1- Open attachment link below2- Select attachment3- Click comment above4- Fill your comment5- For action code: Please Fill this Item status from this wizard A/C:A or A/C:B or A/C:C or A/C:D or A/C:E

Attachments (1)**Linked Records (0)****Linked Mail (0)**



REQUEST FOR INFORMATION

Project Name:	SAFIRA RAK FABRICATION YARD	Project Location:	Ras Al-Khobar, Kingdom Of Saudi Arabia
Project Number:	245-1-18	Client:	MCDERMOTT

RFI No.:	Subject:	Date:
D7365-RFI-MDR-ZP-FF-001	Clean Agent Fire suppression system	7/1/2024

Location/Area: all packages

TOS:

Information Requested:

In Reference to IFC drawings for package 4 & 5 ,clean agent fire suppression is required to be installed in specified rooms.However since there is no specifications for the subject system ,Zamil is hereby proposing the following brand :

brand Name: Avenger

Proposed clean agent :Avenger 5112 (FK-5-1-12 chemical name as per NFPA 2001)

Approvals: UL Listed /FM approved

please check and confirm to proceed furthur for design and shop drawings for this system .

Attachments:

1. Avenger technical submittal

Block 1



REQUEST FOR INFORMATION

Project Name:	SAFIRA RAK FABRICATION YARD	Project Location:	Ras Al-Khobar, Kingdom Of Saudi Arabia
Project Number:	245-1-18	Client:	MCDERMOTT

RFI No.:	Subject:	Date:
D7365-RFI-MDR-ZP-FF-001	Clean Agent Fire suppression system	7/1/2024

Location/Area: all packages

TOS:

Reference(s):

1.Avenger technical submittal

Attachment(s): ☒ Yes (List) ☐ No

Response Required By Date:

Requested By:

Mahmoud Kishly

Print Name

Mechanical Engr

Function

Signature

7-Jan-24

Date



REQUEST FOR INFORMATION

Project Name:	SAFIRA RAK FABRICATION YARD	Project Location:	Ras Al-Khobar, Kingdom Of Saudi Arabia
Project Number:	245-1-18	Client:	MCDERMOTT

RFI No.:	Subject:	Date:
D7365-RFI-MDR-ZP-FF-001	Clean Agent Fire suppression system	7/1/2024

Location/Area: all packages

TOS:

Time/Date Received:

Recommended Action:

- The proposed suppression system is approved.
- MDR Approval is on the consideration that the suggested system meets the Approval requirements of HCIS.
- Performance of the selected system shall be inline with the Warranty requirements.

MDR urgent reply on requested information will be highly appreciated.

Cost Impact:	☐ Yes	☒ No	☐ Unsure
Schedule Impact:	☐ Yes	☒ No	☐ Unsure
Attachment(s):	☒ Yes (List)	☐ No	
Transmit a Copy of this RFI to the Client?	☒ Yes	☐ No	



REQUEST FOR INFORMATION

Project Name:	SAFIRA RAK FABRICATION YARD	Project Location:	Ras Al-Khobar, Kingdom Of Saudi Arabia
Project Number:	245-1-18	Client:	MCDERMOTT

RFI No.:	Subject:	Date:
D7365-RFI-MDR-ZP-FF-001	Clean Agent Fire suppression system	7/1/2024

Location/Area: all packages

TOS:

Distribution:

- | | | |
|---|---|--|
| ☒ Site Construction Manager | ☐ S/C Administrator | ☐ QA/QC Manager |
| ☐ Craft Superintendent | ☐ Project Controls Manager | |
| ☐ Technical Specialist | ☒ Engineering | |

Signed:

Mansoori MR

Engineering-Lead

MMR

11 February 24

Print Name

Function

Signature

Date

Print Name

Function

Signature

Date

Material Submittal طلب اعتماد المواد

اسم المشروع: الأعمال الميكانيكية لهيئة كفاءة الإنقاذ والمشاريع الحكومية الجديدة

3/2/2025	تاريخ الطلب:	EP-MS-MECH-005	رقم طلب الاعتماد:	طلب جديد ☒
----------	--------------	----------------	-------------------	--

□ طلب معد تقديمه رقم الطلب السابق: تاريخ الطلب السابق:

سبب تقديم طلب الاعتماد: ☐ من أجل معلومات ☐ من أجل الملاحظات والتعليقات ☒ من أجل الاعتماد

التخصص:

☐ معصاري ☐ مقلبي ☒ ميخانيكا ☐ كهرباء ☐ تيار خفيف ☐ أمن وسلامة ☐ لغوي

المرفقات:

☒ كتب المورد
 ☐ مخططات
 ☒ المواصلات الفنية
 ☐ شهادات
 ☐ عينات
 ☐ ملف الاستئصال
 ☐ أخرى

جدول الموائد:

[illegible]

المهندسين المطاول :

مدير المشروع والمفاوض :

الاسم:	بشار المعطي	التوقيع:		الاسم:	فادي بوعزم	التوقيع:	
--------	-------------	----------	---	--------	------------	----------	---

التاريخ:	3-2-2026	التاريخ:
----------	----------	----------

النتيجة المطلوبة:

A معتمد بدون ملاحظات **B** معتمد مع ملاحظات إعادة التقديم غير ضرورية **C** معتمد مع ملاحظات ويجب إعادة التقديم

الملاحظات:

1. آفات و بیماری های گیاهی Arthropods Arthropods Arthropods

التي هي من أجل أن تكون قادرة على القيام بواجباتها

٢٠ جميع المواد من مادة ١٨

٤١٤ | علاج منبه فناء كبر من مقلوبة لعل

المهندس المعتمد / الاستشاري :

مدير المشروع / الاستشاري :

الاسم:	التوقيع:	الاسم:	التوقيع:
		عبد الله السراة	

الوظيفة:	التاريخ:	التاريخ:
----------	----------	----------

المهندس المعتمد / المالك :

مدير المشروع / المالك :

الاسم:	الاسم:	الاسم:	الاسم:
اللقب:	اللقب:	اللقب:	اللقب:

التاريخ:	التاريخ:	الوظيفة:
----------	----------	----------

Product Approval Form

☐ Civil
 ☐ Structural
 ☐ Architectural
 ☒ Mechanical
 ☒ Electrical
 ☐ Telecom

Supplier Name : **Contractors Services Co**

Submittal No. : -
 Date : **1-Jun-2023**
 Project Title : **TAWAL Projects**
 Package Name : **Fire Fighting System**
 Revision : -
 No. of Copies : -
 Vendor : -



Description:

AVENGER - HFC227ea System (Trading name FM200) Using for Capex Rooms

Product Information:

Site Model:	Tower Type:	Total EPA:	Site Dim. :
Num. of Tenant's:	Tower Capacity:	Tower Height:	HVAC :
Shelter/ODU :	Power Sup:	Rectifiers :	Battery :
IBS:	Connectivity:	Small Cell:	WiFi :
Planned Inspection Date:	27-Jul-2023		

Attention :

For : **Contractors Services Co**

Date : 27-Jul-2023 Name: **Engr.Bahaa Zuhair** Signature :
 Mobile: **547078789** Stamp :

For : **TAWAL – Telecommunications Towers Company Ltd**

Approval Codes :

☒ **A**
APPROVED


☐ **B**
APPROVED with comments,
Incorporate Comments & Proceed

☐ **C**
REJECTED

Comments :

Signature :
TAWAL - Design Director

Name : **Alhassan Bin Saleh**
 Date :
 Signature :



Signature :
TAWAL - GM / ES & OP Planning

Name : **Naif Salem Alenazy**
 Date :
 Signature :



☐ Tower ☐ Shelter / ODU ☐ Power Supply ☐ Battery ☐ Rectifiers ☐ HVAC

Supplier Name : Contractors Services Co

Submittal No. : -
Date : 1-Jun-2023
Project Title : TAV TAWAL Projects
Package Name : Fire Fire Fighting System
Revision : -
No. of Copies : -
Vendor : -



Description and efficiency:

1. GAS CYLINDER & STAINLESS STEEL VALVE ASSEMBLIES UL/FM APPROVED
2. FM-200 Fire suppression agent UL/FM APPROVED
3. LATCHING SOLENOID ACTUATORS UL APPROVED
4. LOCAL MANUAL CONTROL HEAD FOR 383L018 UL APPROVED
5. PRESSURE SUPERVISORY SWITCH (N/C) 360 PSI UL APPROVED
6. NOZZLES (ALUMINUM) UL APPROVED
7. CAUTION-ROOM PROTECTED UL APPROVED
8. Supreme XT Conventional Releasing Panel Red 230V UL
9. Supreme XT Abort Switch Surface Mount Red UL APPROVED
10. Manual Pull Station SPST w/TB Dual Action Key Lock Yellow for Releasing UL APP
11. Back Box for Manual Pull Station, Yellow Color UL APPROVED
12. FIXED TEMPERATURE HEAT DETECTOR UL APPROVED
13. Conventional Photo Electric Smoke - H UL APPROVED
14. Conventional 4 inch base - H UL APPROVED
15. 24V DC Fire Alarm Bell -6 inch UL APPROVED
16. Horn/Strobe, Wall Red Multi Candela (GEC3) UL APPROVED

Signature :

Reviewed by		Approved by	
Name :	Adel Ayub	Name :	Kareem R. Elmallah
Date :	9-10-2023	Date :	10-10-23
Signature :	[Signature]	Signature :	[Signature]
Job Titel :	Exp. Expert	Job Titel :	Design Manger

Compliance Terms & Conditions

☐ Tower	☐ Shelter / ODU	☐ Power Supply	☐ Battery	☐ Rectifiers	☐ HVAC
--------------------------------	--	---------------------------------------	----------------------------------	-------------------------------------	-------------------------------


Supplier Name :	Contractors Services Co.	
Submittal No. :	-	
Date :	1-Jun-2023	
Project Title :	TAWAL Projects	
Package Name :	Fire Fighting System	
Revision :	-	
No. of Copies :	-	
Vendor :	-	



Material's	All materials supplied under this approval must be brand new and not refurbished or repaired. (Comply)
Warranty / Guarantee	The warranty period for materials will be (2/5/7) years against all defects in workmanship and material bearing labor, maintenance, repair, and replacement cost for all activities. The warranty/guarantee will be applied as per TAWAL standard related procedures starting from certification date of site acceptance. (COMPLY 2 YEARS)
End of Life (EOL) End of Support (EOS)	Supplier must inform TAWAL minimum prior 6 months of EOL (End of life), and 1-year prior of EOS (End of service) (Comply)
Spare Parts	The Supplier is requested to insure that all the material which will be supplied to Tawal in any project must have a minimum 3% buffer material available in its warehouse to cover any damage material and cover spare parts during and after warranty period until EOS. (Comply) The Supplier must be obliger to sell and provide all the spare parts to either Tawal or any contractor or vendor assigned by Tawal. (Comply)
Right to Substitute Enhanced Product	During the term of the Approval, products, equipment and software ..etc. supplier shall conduct continuous modifications, upgrades , update and enhancements with complete technical support. Moreover, Supplier shall inform TAWAL about this enhancement on that products, which exceed that approval limits, Supplier shall also provide TAWAL any updates or upgrades which related to the products whether positive or negative requirement. Supplier shall commit to provide any updates required whether products, equipment and software etc.. without additional costs to TAWAL (Comply)
Confidentiality	Supplier shall comply with Confidential Information includes, but is not limited to proprietary or confidential commercial, financial, marketing, business and technical or other data, including know-how, trade secrets, specifications, algorithms, calculations, formulae, processes, procedures, business methods, diagrams, drawings and all other confidential information of whatever nature relating to the Disclosing Party or its businesses (whether written or oral, in any form or medium) given to the Recipient in the course of exploring the purpose of the Agreement signed with TAWAL. (Comply)

This Form shall be governed by the Agreement that is, or will be, signed between TAWAL and the Supplier. If there is any conflict or discrepancy between the Agreement and this Form, the Agreement shall supersede and prevail to the extent of such conflict or discrepancy.

Signature :

TAWAL - Telecommunications Towers Company Ltd		Contractors Services Co.	
Name :	Kareem R. Elmallah	Name :	Engr. Bahaa Zuhair
Date :	10-10-23	Date :	26-07-2023
Signature :		Signature :	
Job Titel :	Design Manger	Job Titel :	Safety & Security Senior Engineer



Main Contractor الرئيسي المقاول
شركة راية التجديد للمقاولات
Renewals Banner For Contracting Co



الإستشاري Consultant
مكتب مساز للإستشارات الهندسية
Maz Engineering Consulting Office



المالك Owner
الأوقاف الصحية
Health Endowments

المشروع : إنشاء مركز الفوزان للنساء والأطفال بمستشفى الزلفي العام
Project: Establishing the Al-Fawzan Center for Women and Children at Al-Zulfi General Hospital

تقديم التأهيل المسبق : Pre-Qualification Submittal

MAR-ZULFI-MEC-019	رقم الطلب Request No	Pre-qualification & Tech. Submittal for FIRE SUPPRESSION SYSTEMS from CONTRACTORS SERVICES COMPANY	وصف المواد Material Description								
	رقم البند Item No										
10/8/2025	تاريخ التقديم :Submission date	تقديم جديد New submission		☒							
	تاريخ الإستلام :Receipt date	إعادة تقديم Resubmission		☐							
OTHERS أخرى	☐	SPACE مساحة	☐	ELECTRICAL كهرباء	☐	MECHANICAL ميكانيكا	☒	ARCHITECTURAL معماري	☐	STRUCTURAL إنشائي	☐

- على المقاول إرفاق صورة من العينة أو الكatalog أو احضار العينة للموقع.

- The contractor must attach a copy of the sample or catalog or bring the sample to the site

- يتعهد المقاول بأن المواد المقدمة للاعتماد مطابقة للمواصفات

- The contractor undertakes that the materials submitted for approval conform to the specifications

المقاول Contractor

Project Manger مدير المشروع	Implementation engineer مهندس التنفيذ
Eng Youssef Ismail	
Name الاسم	Name الاسم
signature التوقيع	signature التوقيع

ملاحظات الإستلام Receipt notes

لا مانع من الاعتماد مع مراعاة ما يلي:

- 1- الالتزام التام بالمواصفات الفنية المعتمدة وأصول الصناعة والتركيب.
- 2- تقديم شركات أخرى للاعتماد.
- 3- الالتزام بكود NFPA واشتراطات الدفاع المدني حيثما ينطبق.
- 4- تقديم حسابات مفصلة قبل عمل selection للنظام للغرف التي تحتاج clean agent.
- 5- الالتزام بالمخططات التنفيذية المعتمدة.
- 6- تقديم شهادة منشأ (Certificate of Origin) وضمان المصنع لمدة لا تقل عن سنتين.

الإستشاري Consultant

Project Manger مدير المشروع	Supervision engineer مهندس الإشراف
Eng Amjad Abdel Mowla	
Name الاسم	Name الاسم
signature التوقيع	signature التوقيع

21/10/2025

مرفوض REJECTED	D	بعد التقديم REVISED AND RESUBMIT	C	معتمد بملاحظات APPROVED AS NOTED	B	معتمد APPROVED	A	حالة الاعتماد : STATUS CODE
Date of receipt تاريخ الإستلام				Receiving the application after review استلام الطلب بعد المراجعة				
signature التوقيع				لم يتم Not Done				تم Done

إستشاري مشاريع

جامعة تبوك

الرقم ٢٠٢٣/ع/٢٠٣

التاريخ ١٤٤٤/٠٨/١٤ هـ

الموافق ٢٠٢٣/٠٢/٠٦ م

المحترمين

المحترم

السادة/ الفئار للإنشاءات فرع شركة الفئار

عناية المهندس / مدير المشروع

مشروع إستكمال إنشاء كلية العلوم - المرحلة الأولى والمرحلة الثانية (للأعمال المتبقية)

الموضوع:

إعتماد مورد و مقاول الإطفاء بالغاز FM200.

السلام عليكم ورحمة الله وبركاته ، ، ،

إشارة الى الموضوع أعلاه ، وإلى خطابكم رقم EL60-228 بتاريخ ٢٠٢٣/٠٢/٢٥ م ، بخصوص تأهيل مورد ومقاول FM200 لتوريد وتنفيذ نظام الاطفاء بالغاز.

وبناءً على خطاب سعادة مدير إدارة المشاريع رقم ٤٤/٠٥٢/٤٢٧٥٥ بتاريخ ١٤٤٤/٠٨/٠٩ هـ، تفيدكم بالموافقة على اعتماد شركة أعمال المقاولين للتجارة والمقاولات CSC لتوريد نظام اطفاء الغاز شركة AVENGER - بلد المنشأ USA كمورد فقط ، على أن يتم الإلتزام بما يلي :-

١- تقديم الحسابات الخاصة بالنظام والمخططات التنفيذية و مخططات ثلاثية الابعاد لكل غرفة (ISOMETRIC DRAWINGS) والالتزام التام بشروط ومواصفات المشروع وتعليمات الدفاع المدني.

٢- تقديم تسلسل تشغيل Sequence of operation .

٣- تقفيل جميع الفتحات وتركيب دناير أتوماتيكية لجاري الهواء في الغرف المحمية بهذا النظام لاستطاعة عمل اختبار INTEGRITY TEST .

٤- التوريد وتركيب طبقاً لمواصفات المشروع والكود السعودي والكود NFPA2001 وجداول الكميات والمخططات المعتمدة من هيئة الدفاع المدني.

٥- تركيب انظمة الكشف و التشغيل و الإنذار والتحكم واختبارها وصيانتها وفقاً لمعايير NFPA 70 & NFPA 72.

٦- توفير علامات تحذير و ارشادات عند مداخل المناطق المحمية و داخلها. يجب ان يكون لون علامة الامان وفقاً لمعيار ANSI Z535.2 .

٧- ربط نظام FM200 مع نظام الانذار بالمبني و نظام BMS .

٨- تقديم شهادات ضمان والمنشأ و الاختبار موثقة من الجهات المعتمدة.

وتقبلوا تحياتي ...

مدير المشروع

المهندس / حسن عطالله

MATERIAL INSPECTION REQUEST - MIR

Project Name	Construction and operate Phase-1 Green Riyadh Nyrsera	MIR Ref.No	MAG-MEC-MIR-00261
Client	RCRC	Request submission (Date & Time)	22/7/2024
Employer		Inspection (Date & Time)	22/7/2024
PMC	DORSCH	Rev No	
Engineer		MIR Submitted By	SHAIK WASEEM
Contractor	Consortium of Al Majal Al Arabi and ADVACON	MIR Submitted To	Consultant Dorsch

Part A: By the Contractor

Materials Submittal Approval References: GRP-07-NU002-MAG-MEC-MAT-00091

Description of Supplied Materials: NOVEC System for IT Room At Administration Building.

Manufacturer - Country of Origin: AVENGER

Supplier : CSC- CONTRACTORS SERVICES COMPANY.

Delivery Note Number: RUH-240100245

Date of Receipt of Material On Site: 24/6/2024

Storage Location: Site

Contractor:

Name: SHAIK WASEEM

Signature: 

Date: 22/7/2024

Part B: By the Engineer

Inspection Reports:

Physical Damage? ☐ Yes ☒ No

Details Given in Delivery Note Correct? (Type, Size, Wt., Qty. etc.) ☒ Yes ☐ No

Conform with Approved Submission? (Certified etc.) ☒ Yes ☐ No

Inspector / Material Engineer Remarks:

Name:

Signature:

Date:

Engineer's Decision:

The above materials have been inspected on site and found, at time of inspection, to be:

- ☐ A- Approved -Fully satisfactory and can be used for permanent works at site.
- ☒ B- Approved - with CommentsPartially satisfactory and can be used for permanent works after taking into consideration our comments mentioned in remarks
- ☐ C - Revise and Resubmit - Correct documents / provide additional information requested
- ☐ D - Rejected - Can not be used for permanent works at site

All the components should be stored as per the manufacturing recommendations till they are taken-up for installation

Comments:

Name: Abdul Jabbar, Sr. Mech. Engg.

Signature: 

Date: 05.07.2024



MATERIAL SUBMITTAL FORM

Part A: Project & Record Information:

Project Name	Green Riyadh Programme	Submittal No:	GRP-07-AJ002-MAG-MEC-MAT-00091
Client	Royal Commission for Riyadh City	Revision No:	01
Employer		Drawing Ref.	
PMC	Dourch Group DC Abu Dhabi	BOQ Ref. if any	Bill No. 4
Engineer		Approx. Qty	
Contractor	Al Majal Al Arabi Group JV Advanced Concepts Contracting co	Submission Date	27-MAY-24

Part B: Material Submittal Discipline:

Related Discipline	☐ Civil Material	☐ Architectural Material	☐ Electrical Material
	☒ Mechanical Material	☐ Others (Specify):	

Part C: Material Details

Spec's. Ref.			1	Material Approval Form	✓
Specified Material	NOVEC System for IT Room at Administration Budling		2	Compliance statement based on project Specification Contractor to add Design projection, threshold levels as applicable.	
			3	Manufacture & supplier details with contact including country of manufacture.	✓
Proposed Material	NOVEC System for IT Room at Administration Budling		4	Manufacture Technical data sheet.	✓
			5	Previous test Reports.	✓
Manufacturer's	Name	SFK-5-1-12 AGENT-AVenger	6	Manufacture/ supplier warranty.	✓
	Address	AVenger	7	Copy of relevant page of Specification attach project Specification, Saudi Standards/Specifications etc.	
Supplier's	Name	CSC-CONTRACTORS SERVICES COMPANY	8	Copy of relevant page of Bill of Quantities Highlight the item.	
	Address	RIYADH	9	Copy of Drawings where applicable with Design parameters, calculations etc.	
Estidama Approval			10	Copies of previous other approvals by external entities for reference only.	✓
Justification of Alternative Material			11	Copy of operating manual & Original Equipment manufacture (OEM) maintenance recommendations.	
Part C: Contractors Review			12	Any other relevant information.	
	M.E	HSE	QA/QC	Project Manager	
Name				Ahmed Shoban	
Signature					
Date				06-MAY-24	

We do certify that the material submitted herewith has been reviewed in details and in accordance with the Contract Documents except as otherwise stated here above.

Part D: Engineers Review / Approval

Employer/ Engineer Approval	☐ A - Approved ☐ B - Approved with comments	☐ C - Revised and resubmit ☐ D - Rejected
-----------------------------	--	--

Note(1): Employer's/ Engineer's approval is for conformance with information given and design concept expressed in Contract Documents. Approval does not authorize changes to Contract Documents. Employer's/ Engineer's approval does not relieve the Contractor from his contractual obligation to ensure conformance to all Contract Documents. Any deviations, to the Contract Documents found subsequent to Employer's/ Engineer's approval are to be corrected by the Contractor at no extra Cost/Time to the Employer.

	Engineer's ME / SE	Engineer's RE	For RCRC
Name			
Signature			
Date			

Submittal #373.01 - Shop Drawing and Calculation for Novec System

Revision	01	Submittal Manager	Amr Saeed (Dar Al-Riyadh)
Status	Open	Date Created	Aug 31, 2025
Issue Date		Spec Section	
Responsible Contractor	Shade	Received From	
Received Date		Submit By	
Final Due Date	Sep 17, 2025	Lead Time	
Location		Type	Material Submittal
Submittal Package			
Approvers	Amer khabbaz (Dar Al-Riyadh), Wajid Khaja Ali (Dar Al-Riyadh), Osman Mohamed (Dar Al-Riyadh), Amr Saeed (Dar Al-Riyadh), Bilal Hassouneh (Dar Al-Riyadh), Khalifa Aldossary (Dar Al-Riyadh), Ahmed Bumtaia (King Fahd Causeway Authority)		
Ball in Court	Bilal Hassouneh (Dar Al-Riyadh)		
Distribution			
Description			

Note 1	- Approval shall not relieve the Contractor of his liabilities under the Contract or Constitute authorization of any change to the Contract Documents. - The Contractor certifies that the material submitted herewith has been reviewed in detail and is in compliance with the contract drawings and specifications. - This check is only for review of general conformance with the design concept of the project and general compliance with the information given in Contract Documents. The Contractor is responsible for confirming and correlating all quantities and dimensions selecting fabrication processes and techniques of the construction; coordinating his work with that of other trades, and performing his work in a safe and satisfactory manner.
---------------	--

Submittal Workflow

Name	Sent Date	Due Date	Returned Date	Response	Attachments
General Information Attachments					SERVER ROOM.pdf update.pdf SERVER ROOM.pdf SERVER ROOM new update (1) (3).dwg NEW IT ROOM.pdf IT ROOM.pdf NOVEC SYSTEM COMMENT COMPLIANCE..pdf 500PSI Avenger 5112 Manual.pdf NEW IT - CABIN- PLAN (1) (1) (4) (3).dwg
Amer khabbaz	Sep 1, 2025	Sep 5, 2025	Sep 1, 2025	Approved as Noted	
Wajid Khaja Ali	Sep 1, 2025	Sep 5, 2025	Sep 2, 2025	Approved as Noted	
Comment	There must be void detectors in server room similar to It room in above ceiling. The locations for IT and server room are to strictly as per coordination layouts approval.				

Name	Sent Date	Due Date	Returned Date	Response	Attachments
NFPA standards for battery backup of the Novec panel is to be complied.					
Osman Mohamed		Sep 5, 2025	Sep 1, 2025	Approved as Noted	
Comment	- Manual Release To be out of Server Room. - Cylinder Location to Coordinate with other Services and Devices. - IT Cabin Door Location to be As Approved Drawing. - Shift IT Manual Release to Other side of Door.				
Amr Saeed	Sep 1, 2025	Sep 5, 2025	Sep 2, 2025	Approved as Noted	
Comment	mep comments to be addressed				
Bilal Hassouneh	Sep 2, 2025	Sep 9, 2025		Pending	
Khalifa Aldossary		Sep 13, 2025		Pending	
Ahmed Bumtaia		Sep 17, 2025		Pending	

FM-E-P07-01: Manufacturer, Agent/Distributor & Sub-Contractor Approval

اعتماد الجهة المصنعة، الوكيل / الموزع ومقاول الباطن

File No.

16-7-2023

Forward to

Sami


Main Contractor : المقاول الرئيسي : AL MAJAL AL ARABI	Consultant : الاستشاري : KHATIB & ALAMI	Submission # ME-AL-FCRD-045-REV-00
Submittal Title : عنوان التقديم	Location/Use: الموقع / الاستخدام: All Buildings	Project # : المشروع : 00000000000000000000
Project Title : General Hospital Hail-300-Bed عنوان المشروع	Ref. # : الرقم المرجعي	Date: 12/07/2023
New Submittal: ☐ تقديم جديد	Re-Submittal: ☒ إعادة التقديم	Sub-Contractor ☐
Manufacturer ☒ الجهة المصنعة	Agent / Distributor ☒ الوكيل / الموزع	
Details of Equipment / Materials /Services to be Supplied تفاصيل المعدات / المواد / الخدمات التي يتم توريدها		

PRALIFICATION FOR CONTRACTORS SERVICES CO FOR TRADING & CONTRACTING COMPANY Fm200 & co2 & foam system fire fighting valves

If Manufacturer, please provide the following information on a separate sheet إذا كان جهة مصنعة، يرجى تقديم المعلومات التالية في ورقة منفصلة	
1. Details of Product Range and Capabilities	1 - تفاصيل نطاق المنتج والقدرات
2. Details of Main Manufacturing Processes and Equipment	2 - تفاصيل عمليات التصنيع الرئيسية والمعدات
3. List of Existing Customers in the Healthcare Sector	3 - قائمة العملاء الحاليين في قطاع الرعاية الصحية
4. Details of Quality Systems Employed	4 - تفاصيل أنظمة الجودة المستخدمة
5. Country of Manufacture	5 - دولة الجهة المصنعة
If Agent / Distributor, please provide the following information on separate sheet إذا كان وكيل / موزع، الرجاء إرفاق المعلومات التالية في ورقة منفصلة	
1. List of Agencies / Distributorships held	1 - قائمة الوكالات / التوزيع التي تم عملها
2. Details of Items normally held in stock	2 - تفاصيل البضائع التي يتم الاحتفاظ بها عادة في المخزون
3. Income and balance sheet for the last three years	3 - قائمة الدخل والميزانية العمومية لأخر ثلاث سنوات
4. Agency certificate stamped from KSA embassy in country of origin and certified from chamber of commerce.	4 - شهادة الوكالة معتمدة من سفارة المملكة العربية السعودية في دولة الأصل ومعتمدة من الغرفة التجارية
If Sub-Contractor, please provide the following information on a separate sheet إذا كان مقاول الباطن، الرجاء إرفاق المعلومات التالية في ورقة منفصلة	
1. Registration Certificates for proposed Service	1 - شهادات التسجيل للخدمة المقترحة
2. Annual turnover & last 3 years certified accounts	2 - الدوران السنوي والحسابات المعتمدة لأخر ثلاث سنوات
3. Healthcare Experience	3 - الخبرة في القطاع الصحي
4. Current Capacity	4 - القدرة الحالية
Contractor Comments ملاحظات المقاول	
PM Name: Ahmed Sami اسم مدير المشروع	Signature: التوقيع
Date: التاريخ	

Consultant's Review مراجعة الاستشاري	
Consultant Comments ملاحظات الاستشاري	Consultant Stamp ختم الاستشاري
PM Name: أحمد سامي	Signature: التوقيع
Date: التاريخ	
A): Approved ☐ معتمد	B): Approved with comments ☒ معتمد مع ملاحظات
C): Resubmit ☐ إعادة التقديم	D): Rejected ☐ مرفوض
MOH Review: مراجعة وزارة الصحة	
Control Observation & Submittal Review Check sheet complete ☐	Engineering Observation & Submittal Review Check sheet complete ☒
PM Observation & Submittal Review Check sheet complete ☐	PM Name: وليد العنكي
Signature: التوقيع	Date: التاريخ
Supervision Manager Comments: ملاحظات مدير الإشراف	
A): Approved ☐ معتمد	
B): Approved with comments ☒ معتمد مع ملاحظات	
C): Resubmit ☐ إعادة التقديم	
D): Rejected ☐ مرفوض	
SM Name: مدير الإشراف فواز سعيد آل عاتق	Signature: التوقيع
Date: التاريخ	
General Managers Review- Sub-Contractors only مراجعة المدير العام - مقاولي الباطن فقط	
General Manager Comments: ملاحظات المدير العام	
A): Approved ☐ معتمد	
B): Approved with comments ☐ معتمد مع ملاحظات	
C): Resubmit ☐ إعادة التقديم	
D): Rejected ☐ مرفوض	
GM Name: المدير العام محمد بن عبد الحميد الديحان	Signature: التوقيع
Date: التاريخ	

MOH Projects Internal Observation Report

Project No.: رقم المشروع:	405110100	Project Title: إسم المشروع:	مستشفى حائل 300 سرير
Date: التاريخ:	2023 / 8 / 2	Sent to: المرسل إليه:	مدير إدارة الاشراف على المشاريع
Subject: الموضوع:	اعتماد مقاول باطن لتنفيذ أعمال نظام الاطفاء بالغاز التنظيف وثاني اكسيد الكربون والقوقم FM200 , CO2, Foam	Observation No.: رقم تقرير الملاحظات:	
Consultant: الاستشاري:	خطيب وعلمي	Main Contractor: المقاول الرئيسي:	مجموعة المجال العربي للمقاولات
Prepared by: تم الإعداد بواسطة:	صبري شرف	Other: اخرى:	
Observations and Comments			الملاحظات
			اللغة العربية
1- نوصي باعتماد الملف الفني لشركة أعمال المقاولين للتجارة والمقاولات (CSC) كمقاول باطن لأعمال توريد وتركيب واختبار وتشغيل لأنظمة اطفاء الحريق بالغاز التنظيف (FM200) وبغاز ثاني أكسيد الكربون (CO2) وبنظام القوقم (Foam) وذلك حسب اعتماد وملاحظات وتوصيات الاستشاري . 2- يتم تقديم الملف الفني مشمول بكافة التفاصيل والمكونات والمخططات التصميمية والحسابات المعتمدة من الاستشاري لجميع الغرف بالمشروع حسب متطلبات الدفاع المدني. 3- تقديم عينات من المواد المستخدمة . 4- الالتزام بالموصفات الفنية واشتراطات العقد , والقياسية (NFPA) ومتطلبات الدفاع المدني . 5- الالتزام بالجدول الزمني للمشروع .			
Completed By (print name): الوجهة (الاسم طباعة):	Signature: التوقيع:	Date: التاريخ:	
م / صبري شرف		2 / 8 / 2023	
Approved By (print name): الجهة (الاسم طباعة):	Signature: التوقيع:	Date: التاريخ:	
م / سامي المنيف		١٢٢٥ / ١ / ١٥	
DISTRIBUTION			
☐ General Manager	☒ Supervision Dept. Manager	☐ Regional Manager	☐ Construction Manager
☐ Engineering Support Team Manager	☐ Control Team Manager	☐ QA/QC Manager	☐ Other

REQUEST FOR MATERIAL & EQUIPMENT APPROVAL

Project Site / موقع المشروع Replacement and Development of the Electric Infrastructure Network at The MAGARDA General Hospital
إحلال و تأمين مصادر التغذية الاحتياطية الكهربائية لمستشفى المجاردة العام

Request No. / رقم الطلب : MGH_EE_MRA_010_Rev01
Date / التاريخ : 5 SEP - 2024

Discipline:

- ☐ Civil / مدني ☐ Architectural / معماري ☐ Structural / انشائي ☐ Mechanical / ميكانيكي
☐ Electrical / كهربائي ☐ Others / اخرى _____

Attached References / المرفقات

- ☐ Catalogues / دليل المستخدم ☐ Drawings / المخططات ☐ Certifications / الشهادات ☐ Samples / العينات
☐ Test / اختبار ☐ Calculations / الحسابات ☐ Specifications / المواصفات ☐ Others / اخرى _____

Item # رقم البند	Description الوصف	Quantity الكمية	Manufacturer/ Supplier المورد / المصنع	Country of Origin بلد المنشأ	Specs. Ref. مراجع المواصفات	BOQ Ref. مراجع جدول الكميات	Action Code رمز الحالة
1	GENERATOR ROOM FM200 SYSTEM	1	CSC/AVENGER	kSA	SECTION 21 00 00	BOQ(1)	B

Action Code / رمز الحالة A = Approved / موافقة B = Approved as noted / موافقة مع شروط C = Resubmit / إعادة تقديم حسب الملاحظات D = Rejected / مرفوض

Contractor Signature & Stamp / توقيع المقاول و الختم

Name / الاسم : ALRASHID

Signature / التوقيع

Date / التاريخ : 5 sep - 2024



We certify that above submitted items are correct and in strict compliance to the project drawings, specification, and contract except otherwise stated

تعهدنا على صحة البند المسلمة أعلاه و كذلك على الالتزام بالام محضرات المشروع، والمواصفات والعقد باستثناء ما ينص على خلاف ذلك

MOH Technical Team Comments and Remarks / تعليق و ملاحظات الفريق الفني بالوزارة

Approval Section / القبول

MOH Technical Team الفريق الفني بالوزارة	MOH Head Technical Support Unit رئيس وحدة الدعم الفني	Assistant General Director مساعد مدير العام للشؤون الهندسية والدعم الفني
Reviewed by / راجعها : Name / الاسم : Signature / التوقيع : Date / التاريخ : ٢٠٢٤ / ٩ / ١٨	Noted by / لاحظها : Name / الاسم : Signature / التوقيع : Date / التاريخ :	Approved by / اعتمدها : Name / الاسم : Signature / التوقيع : Date / التاريخ :



وزارة الصحة
Ministry of Health

تاريخ التقديم 2024/09/05

رقم التقديم 010 رقم المراجعة 01

Code (B)

مشروع: إحلال تأمين مصادر الاحتياطية الكهربائية لمستشفى المجاردة العام

الموافقة على نظام الإطفاء النظيف FM200

علي المفاول:

- 1- بعد الانتهاء من التركيب والاختبارات تقديم ما يفيد بإعتماد وموافقة الدفاع المدني بإكمال الاعمال حسب الشروط والمواصفات الخاصة بالدفاع المدني.
- 2- الأسطوانات واللوحات وجميع الأكسسوارات يجب ان تتوافق مع اختبارات UL ومعتمدة من FM ومناسبة للغاز النظيف السائل.
- 3- الأسطوانات يجب ان تكون ذات تفريغ سريع وفعال في 10 ثواني او اقل، وتكون مناسبة لإعادة التعبئة.
- 4- يجب تركيب اللوحة في موقع جيد التهوية وبعيد عن الحرارة والأتربة والاهتزازات.
- 5- مفتاح التشغيل اليدوي يجب ان يكون في موقع يسهل الوصول إليه ومحمي بصندوق زجاجي قابل للكسر.
- 6- تحديد مدة التأخير بين تنشيط المفتاح وبدأ الانطلاق حتى يتمكن الموجودين من إخلاء المكان قبل إنطلاق الغاز.
- 7- تركيب Motorize damper على جميع منافذ اللوفرات وفتحات التكييف ومراوح السحب.
- 8- تركيب رداد على الأبواب.
- 9- ربط مراوح السحب مع إنذار الحريق على ان تتوقف عند حدوث حريق.

 DESIGN • BUILD • DELIVER	 وزارة الثقافة Ministry of Culture	
MAIN CONTRACTOR	CLEINT	MEP CONTRACTOR
MATERIAL INSPECTION REQUEST		
Project No.: 586		Date : 03-Nov-21
Submittal No.: MOC-MIR-MECH-022		Specs Ref. No.:
Contract Drawing Ref. No. :		B.O.Q Ref. No.:
DISCIPLINE		
☐ Arch. ☐ Civil ☐ Elec. ☒ Mech/HVAC ☐ L.S. ☐ H.S. ☐ Others		
Material Description: FM200 Fire Supprisson System		
Date of Arrival: 03/11/2021 Material Submittal Reference No: Mech-034-REV-01 Manufacturer/Supplier's Details (CSC) Contractors Services CO. Country of Origin: KSA Serial No : Quantity/Unit: As Attached		
Attachments: ☒ Delivery notes ☐ Site Photo ☐ Ware House Receipt ☐ Certificate of Compliance ☐ Packing List ☐ Invoice / Bill		
SUBMITTED BY:		RECEIVED BY:
MEP Contractor:		Main Contractor:
Name: Eng. Ahmad Issa		Name: Tamer Ababneh
Signature: 		Signature: 
Date: 03-Nov-21		Date:
Consultant's Approval		
Code:	A	B ☒
	Approved	Approved as noted
		C
		Revise and Resubmit
		D
		Rejected
		E
		Review Not Required
Comments:		
+ exp and approval Subject to test A Commission + all Material to be UL/FM Certified		
Inspection Report	YES	NO
Physical Damage ?		
Confirm with the approved submittal		
Accessories/Parts included ?		
Client / CONSULTANT'S FINAL APPROVAL		
Inspected/Reviewed by:		Approved by:
Name: I mad		Name: AM
Date: 7/11/21		Date:
Sign: 		Sign: 
Acknowledgement of receipt (kindly acknowledge receipt and return this sheet to the sender) Recipient's Name: Job title: Signature: Date:		

MOC-MIR-MEP-0022


 03/11/21 3:18

 MAC DESIGN • BUILD • DELIVER	 وزارة الثقافة Ministry of Culture	 TECHNO ج.س.م.			
MAIN CONTRACTOR	CLIENT	MEP CONTRACTOR			
MATERIAL SUBMITTAL FORM					
MECHANICAL					
Project No.: MINISTRY OF CULTURE JAX A		Date: 19-Sep-21			
Submittal No.: MOC-MS-MECH-034 REV-001		Specs Ref. No.:			
Contract Drawing Ref. No.: -		I.D.Q. Ref. No.: -			
DISCIPLINE					
☐ Arch. ☐ Civil ☐ Elec. ☒ Mech/Fi ☐ L.S. ☐ H.S. ☐ Others					
Attachments					
☒ Technical Brochure ☒ Manufacturer's Specs ☐ Sample ☐ Oper. Manual ☐ Others					
Material Description:1 FM200 Fire Supprison on System					
SUBMITTED BY:					
MEP Contractor: Technical Electromechanical Works Co. Ltd. (Techno) Name: <u>Eng. Ahmad Issa</u> Signature: _____ Date: <u>19-Sep-21</u>		Client Contractor: Mahmoud A Chaaban & Partner Co. (MAC) Name: _____ Signature: _____ Date: _____			
Name of Manufacturer/Supplier: (CSC) Contractors Services CO. Postal Address: P.O Box.No: 41206, Postal Code 11521 Riyadh Tel #: 966 11 4713176 Fax #: 966 11 2420140 Web site: www.csc.com.sa E-mail Address: info@csc.com.sa					
Client's Approval					
Code:	A	B ✓	C	D	E
	Approved	Approved as noted	Revise and Resubmit	Rejected	Review Not Required
Comments:					
- Gas Cylinder Foundation to be Construct - Integrity test to be perform - test and Commission for system to be as per NFPA standards - all part/ components must be UFM					
Client's Final Approval					
Inspected/Reviewed by:			Approved by:		
Name: <u>Imad</u> Date: <u>4/10/2021</u> Sign: _____			Name: <u>AM</u> Date: _____ Sign: _____		
Acknowledgement of receipt (kindly acknowledge receipt and return this sheet to the sender)					
Recipient's Name: _____		Job title: _____		Signature: _____ Date: _____	

FSK
 10:10 AM
 05-10-21



MATERIAL REQUEST FORM - MR

DATE		MR NO.		SERIAL NO.	
13-Aug-22		151		MR-0172	
PROJECT/CC NO.		WBS ELEMENT.		4112-10 FM 200	
151-NUPCO Damman Warehouse					
BRAND/SUBMITTAL APPROVED		DATE REQUIRED (ON SITE)			
S.No	ITEM DESCRIPTION	UNIT	QUANTITY	DETAILED SPECIFICATION	REFERENCE BOQ
	SPECIALIST SERVICES FOR FM-200 SYSTEM (DESIGN, SUPPLY, INSTALLATION, TESTING, COMMISSIONING & HANDING OVER)			☐ MS ☐ SD ☐ Sample ☐ Quotation	
	Note: As per attached Take Off & Approved Brand is AVENGER from CSC, approval no. CRT-NPC-DMM-MAR-MEP-00029.			☐ MS ☐ SD ☒ Sample ☐ Quotation	
				☐ MS ☐ SD ☐ Sample ☐ Quotation	
				☐ MS ☐ SD ☐ Sample ☐ Quotation	
General Notes					
PREPARED BY: SHERWIN		VERIFIED BY: (Site Incharge/Construction Manager) <i>[Signature]</i> 13-Aug-2022		APPROVED BY: PROJECT MANAGER <i>[Signature]</i>	APPROVED BY: PROJECT DIRECTOR
Material - MR Attachments			Subcontractor - MR Attachments		
1. Material Submittals (Approved) 2. Calculation sheet (signed by PM) 2. Approved Shop Drawing (if required) 3. Approved pre-qualification (if any) 4. Approved Sample			1. Approved quotation signed by PM / PD 2. Government Documents - Company CR - VAT Registration - IBAN Bank (Stamped from Bank) 3. signed contract 4. Calculation sheet (signed by PM)		

Approved

Cost Control - Crete International
Contracting

Aug 14, 2022, 1:54 PM GMT+3:00

NUPCO DAMMAM WAREHOUSE

Materials Take-off

FM-200 System



شركة كرييت للمقاولات العامة
Creet International Contracting Co. Ltd
Tel : +9662294 94762 Fax : +966214452758 P.O.Box 12744 Jeddah 21522 Saudi Arabia

No.	Item	Unit	QTY
	FM-200 System		
1	SDB Room, Ground Floor, GF 04	LS	1
2	Electrical Room, Ground Floor, GF 41	LS	1
3	SDB Room, Mezz. Floor, MF 02	LS	1
4	Hazardous Store, Mezz. Floor, MF 08	LS	1
5	Hazardous Store, Mezz. Floor, MF 09	LS	1
6	Hazardous Store, Mezz. Floor, MF 10	LS	1
7	Hazardous Store, Mezz. Floor, MF 11	LS	1
8	Hazardous Store, Mezz. Floor, MF 12	LS	1
9	Electrical Room, Mezz. Floor, MF 20	LS	1
10	Electrical Room, First Floor Location: between GRIDS (1- 2) & GRIDS (C' - C1)	LS	1
11	Hazardous Store, First Floor, FF 13	LS	1
12	Hazardous Store, First Floor, FF 14	LS	1
13	Hazardous Store, First Floor, FF 15	LS	1
14	Hazardous Store, First Floor, FF 16	LS	1
15	Hazardous Store, First Floor, FF 17	LS	1
16	Hazardous Store, First Floor, FF 18	LS	1
17	Hazardous Store, First Floor, FF 19	LS	1
18	Hazardous Store, First Floor, FF 20	LS	1
19	IT Room, First Floor, FF 47	LS	1
20	UPS Room, First Floor, FF 48	LS	1
21	Electrical Room, Roof Floor, RF 01	LS	1
22	Electrical Room, Roof Floor, RF 03	LS	1

NOTES

- 1 Approved Brand is **AVENGER** from CSC, approval no. CRT-NPC-DMM-MAR-MEP-00029 "Attached".

Document Title:	MATERIAL SUBMITTAL FORM			
Project Name:	NUPCO-AI Dammam Logistic Centre			
Project Number:		Project Consultant:	JASARA	
Project Contractor:	Creet	Document Ref. Number:	CRT-NPC-DMM-DCM-TRA-00572	
SUBJECT				
Material Submittal for FM-200 (AVENGER)- (CSC)				
Specs. Code & Ref.	B.O.Q. Code Ref.	Drawing No.	Submittal No.	
			CRT-NPC-DMM-MAR-MEP-00029 REV 02	
			Date :	
			1-August-22	
			Date Returned:	
Sub-contractor				
Name:	CSC	Address:		
Address:		Phone:		Telex:
Manufacturer		Supplier/Agent	CSC	
Name:		Name:		
Address:		Address:		
Phone:		Phone:		
Fax:		Telex:		Telex:
Information submitted and attached:				
Certificates	☐	Operation & Maintenance Manual	☐	
Technical Brochure	☐	Spare Parts List	☐	
Manufacturer's Data & Specs.	☒	As Built Drawings	☐	
Shop Drawings	☐	Warranty	☐	
Samples	☐	Others (specify)	☐	
Contractor's Comments: ✓				
Material Submittal for FM-200 (AVENGER)				
Supplier :- CSC				
Consultant's Comments:				
1. Installation and testing method statement to be submitted to JASARA team for review/approval 2. All system component to be approved in detailed design from MODON 3. Contractor to submit detailed shop drawings based on the project requirements 4. Main contractor is fully responsible for all works done on the site, must be compatible with the submitted procurements plan dates 5. All installation for the work must be under the manufacture trained team and supervise by engineers & supervisor this including submitting all necessary for installation & required details & coordination drawings and have to be confirm from the manufacture including submitting mockup before delivery 6. Provide all valid legal and warranty certificate 7. This Approval doesn't relieve the contractor for any obligation under the contract and under MODON regulation and is independent of any future review and submitted approved design 8. mock up for the all items to make sure of the specs & quality				
Status:		Discipline	Sign & Date	Resident Engineer
Approved	1	☐ Arch	Amr Baraka	
Approved as noted	2	☐ Civil	Mechanical Engineer	Sign :
Revise and submit	3	☐ Mech	03 Aug 2022	Date :
Rejected	4	☐ Elect		
		☐ HVAC		
		☐ LS		

Consultant: 	Project:  مصنع بن زقر للمواد العازلة - JF2 bfim - JF2	Contractor: 
--	---	--

MATERIAL SUBMITTAL

Ref. No. :	MS-BFIM-AOC-113	REV-00	Date :	1 4	1 0	2 0 2 5	☒ New Submittal ☐ Resubmittal
------------	-----------------	--------	--------	-----	-----	---------	---

☐ Architectural ☐ Structural	☐ Electrical ☒ Mechanical	☐ Civil ☐ Electrical	☐ Furniture/Equipment ☐ HVAC	Specs. No.	Drwg. No.
---	---	---	---	------------	-----------

S.N	SUPPLIER / MANUFACTURE	Description / Title	No. of Copy	Remarks
1		FIRE FIGHTING		
2		FM200 - Clean Agent Room	1	
3	MANUFACTURE	Avenger	1	
4				
5				
6				
7				
8				
9				
10				
11				
12				

* Description: (Manufacture, Model, Type, Size, Colour, etc.)

☐ Catalogue	☐ Drawing	☐ Sample	☐ Certificate	☐ Calculation	☒ Document
------------------------------------	----------------------------------	---------------------------------	--------------------------------------	--------------------------------------	--

Having checked this submittal, we certify that it conforms to the requirements of the Contract Documents in all respects, except as otherwise indicated herein ()

Engineer:

Received by:

_____ Date _____ Name & Signature of Consultant

Remarks / Comments:

approved as a brand .

capacity & quantity calculations to be submit for approval

to submit full detailed drawing (shop drawing) for the system

Status	☒ A Approved ☐ B Approved as noted	☐ C Revise & Resubmit, Work shall not proceed ☐ D Rejected - Resubmit	☐ N No Action
--------	--	--	-----------------------------------

Contractor Construction Manager KHALED ATTIA 	Project Manager IBRAHIM SAMI 	Consultant-For Approval Faheem Badaw 15/10/2025 	Client Representative - For Review
--	---	---	------------------------------------

Date _____ Name & Signature _____ Date _____ Name & Signature _____

CONSULTANT	OWNER	CONTRACTOR
 التاخم للاستشارات الهندسية Tanaghom Consulting	 بندو Panda	 شركة إعمار الحديد للمقاولات EHCCO

PROJECT NAME:	Panda 40009	LOCATION:	AL-FANAR MALL KHQBAR
---------------	-------------	-----------	----------------------

DRAWING SUBMITTAL FORM

☒ NEW SUBMITTAL	☐ RE-SUBMITTAL	SUBMITTAL DATE:	25-Jul-2023	MEC-SH-07
PURPOSE OF SUBMITTAL				
☒ FOR APPROVAL ☐ FOR COMMENTS ☐ FOR INFORMATION				
DRAWING DISCIPLINE	☐ ARCHITECTURAL ☒ H. V. A. C.	☐ STRUCTURAL ☐ PLUMBING	☐ CIVIL ☐ OTHERS... Specify:	☐ ELECTRICAL
TYPE OF DRAWING	☒ SHOP DRAWING	☐ AS-BUILT DRAWING	☐ VENDOR DRAWING	☐ OTHERS
DRAWINGS				
NOTE: PLEASE USE THE ATTACHMENT IN CASE ITEMS ARE MORE THAN THE PROVIDED SPACE				
S. No.	DRAWING NO.	NO. OF COPIES	ITEM DESCRIPTION	REVISION NO.
1	ME-102	1	FM-200	-
2			(DATA AND UPS ROOM)	-
3				-
4				-
5				-
SUBMITTED BY:		ABDUL RHAMAN	DC	25-Jul-2023
		NAME	SIGNATURE	DATE SUBMITTED

CONTRACTOR REMARKS:	We clarify that the above submittal is strictly adhered with contractor drawing & specifications except otherwise as stated below.

CONSULTANTS RECOMMENDATION:	Approval of the above does not relieve the contractor from his contractual obligations.
* The calculation reviewed based on concentration 7% . * There no safety factor used with this calculation . * Room light not more than 3m . * The installation shall be as per manufacture specification. * All system components shall be UL / FM listed or approval agency.	


CONTRACTOR	CONSULTANT	OWNER'S REPRESENTATIVE (FOR INFORMATION)
NAME: Eng. SAAD MAZEN ALGHUZAWI	NAME: Eng. ABDEL WAHAB ALI	NAME: Eng. SALEH A. BAHARITH
POSITION: PROJECT MANAGER	POSITION: PROJECT MANAGER	POSITION: PROJECT MANAGER
SIGNATURE: 	SIGNATURE: 	
DATE: 25-Jul-23	DATE: July 26, 2023	
APPROVAL STATUS:		
☐ A APPROVED ☐ D DISAPPROVED	☒ B APPROVED AS NOTED	☐ C REVISE AND RESUBMIT

RECEIVED BY:	SIGNATURE: 	RECEIVED BY:	SIGNATURE:
(CONSULTANT)	DATE: July 26, 2023	(CONTRACTOR)	DATE:

PURCHASE ORDER
RIYADH METRO PROJECT
CONFIRMING PURCHASE ORDER - DO NOT DUPLICATE



BUYER: Riyadh Metro Project Civil Works Joint Venture Comprising: - Saudi Arabian Bechtel Company - Almajani General Contractors - Consolidated Contractors Company WLL VAT No: 300951375300003 BACS Headquarters Building Building Number 7703, Secondary Number 2117 Othman Ibn Afaan Branch Road, Al Ezdihar District, Riyadh 12487, Kingdom of Saudi Arabia, Tel: 966 11 5105600 / Fax: 966 11 5105601	ORDER NUMBER. M-BCW-1SPARE-G000-FOR0-00002 Rev. 0	AWARD DATE: November 08, 2025 REQUISITION NO. M-BCW-1SPARE-G000-FMR-00002 Rev. 0 MATERIAL DESCRIPTION: OPM-L1-and-L2 Foam Water Spares	
	SELLER: <u>Contractors Services Company (CSC)</u> P.O. Box 41208, Riyadh 11521 Riyadh, 11521 Saudi Arabia Attention: Yahya Zuhir Telephone No: 059 420 5600 Fax No: E-mail: yahya@csc.com.sa VAT No:		
	Ship and Consign To: Attention: Mohammad (RMP) Mubarak Ref. No.: M-BCW-1SPARE-G000-FOR0-00002 Contact Authorized Procurement prior to Shipment		Promise Ship Date: December 27, 2025 Shipper: Contractors Services Company (CSC) Origin: Saudi Arabia
	Notes: All prices shown herein are firm unless stated otherwise. Subject to the attached General Conditions Attachments: General Conditions Delivery Package: COMPLETIONS Engineering Inspection required? ☐ No ☒ Yes Material Test Certificate required? ☒ No ☐ Yes		Bill To: Civil Works Joint Venture Comprising: - Saudi Arabian Bechtel Company - Almajani General Contractors - Consolidated Contractors Company WLL Attention: Accounting Department P.O Number: M-BCW-1SPARE-G000-FOR0-00002 0 Invoice Instructions: 1. SEND Original Invoice and Original Bill of Lading 2. PO Number must appear on all Invoices, Correspondence, Shipping Papers, and Packing Lists.
FOR CWJV USE ONLY: Job Number: 25872.100 Cost Code: 7600511 Duns Number: zEBS1000003264 Commitment Register No.: PO Sequence Number: 312633.12065	Total Value in SAR 775.00 Name: Faizal Kandy Title: Procurement Supervisor Signature: Faizal Kandy Finance & Commercial Director Name: <i>Pierrot Hek</i> Title: <i>10.11.2025</i> Signature: <i>10.11.2025</i> Sellers Acceptance Name: _____ Title: _____ Signature: _____ Date: _____		

 الشركة العامة للتصنيع (The General Manufacturing Company)		 وزارة الصحة Ministry of Health		 ARTAR TECHNOLOGY	
اسم المشروع:		إحلال وأمن مصادر الطاقة الاحداثية الكهربائية لمستشفى الملك خالد بنعمران		رقم:	
الموقع:		13623000001000		التصنيف:	
MATERIALS SUBMITTAL (MS) - طلب اعتماد المواد					
رقم التقديم العالي	1	REV. NO	00	الرقم المزمع /	Power-KKNH-ARTAR-ME-01-R00
تاريخ التقديم العالي	04/02/2025	المو. الق.	05/08/1448	إعادة لتقديم	
سبب التقديم		☒ للإعتماد ☐ للتعلم ☐ للملاحظات			
التخصص		☒ ميكانيكا ☐ كهرباء ☐ معماري ☐ ميكانيكا ☐ انشائي ☐ أخرى			
المرفقات		☐ ملاحظات ☐ ملاحظات ☐ ملاحظات ☐ ملاحظات ☐ ملاحظات ☐ ملاحظات			
رقم البند	Item No	الوصف	التصنيع / المورد	بلد المنشأ	مراجع المواصفات
		Description	Manufacturer/ Supplier	Country of Origin	Specs. Ref.
1		FM200 Calculation & Shop Drawing Details For TR Rooms -			
2		KKNHEE-DRW-010-REV00			M5
3		KKNHEE-DRW-011-REV00			M6
4		KKNHEE-DRW-012-REV00			M7
5		KKNHEE-DRW-013-REV00			M8
6		KKNHEE-DRW-014-REV00			M3
Conformance / التوافق We certify that above submitted items are correct and in strict compliance to the proper drawings, specifications, and contract except otherwise stated. نؤكد على صحة المواد المستلمة أعلاه وكذلك على الالتزام التام بمخططات المشروع والمواصفات والعقد باستثناء ما ينص على خلاف ذلك.					
Consultant / الاستشاري مكتب الجية الـ 1023 Please Refer To The Attached Conformance					
 المهندس الاستشاري إيه إيه تيليو وشركاه (AAW PARTNERS) الإشراف على تنفيذ مشاريع البنية التحتية والكهربائية MOH Technical Team Comments and Remarks					
Director of Engineering Support Department / مدير إدارة الدعم الهندسي		MOH Project Manager / مدير المشروع بالوزارة			
Name / الاسم		Name / الاسم			
Signature / التوقيع		Signature / التوقيع			
Date / التاريخ		Date / التاريخ			
Note: All materials must be MOH and comply with the relevant standards and specifications.					

اسم المشروع : احلال وتأمين مصادر التغذية الاحتياطية الكهربائية لمستشفى الملك خالد بنجران
الموقع : نجران

رقم التقديم : MOH-AAW-KKNH-ME-DRW-04-REV.01

تاريخ التقديم : ٢٠٢٥/٢/٤

الموضوع : Shop drawing and calculation clean agent (fm200) for TR rooms

الاعتماد : B

General comments

1. Fire fitting system (FM200) shall be UL listed
2. Calculation shall be matching as per site survey
3. Ventilation system shall be shut down upon activation at the fire suppression system (interface)
4. Discharge time shall be not exceed 10 seconds



Handwritten signature and initials in Arabic script.



QHSE Management System Formats
DESIGN
Material Submission Sheet Form

Project & Document Details			
Project ID / Name:	R24-028 - SURJ	Issue Date:	08-Sep-2024
Document Reference:	R24-028-MNE-ZZ-MAS-FL-007	Return By:	11-Sep-2024
Revision:	00		
Material Details			
Material Type:	FIRE FIGHTING	Image	
Description:	FIRE SUPPRESSION SYSTEM (NOVEC)		
Location:	PROJECT WIDE		
Code On Design Drawing:	TBC		
Supplier/Manufacturer:	AVENGER		
Color/Finish:	AS PER SPEC SHEET		
Dimensions	TBC		
Additional Information:			
Review Details			
	A	APPROVED	
	B	APPROVED WITH COMMENTS	
	C	REVISE AND RESUBMIT	
	D	REJECTED	
NAME:	Tomaz Copar		
SIGNATURE:	Tomaz Copar		
DATE:	16/09/2024		
Comments:			
Ensure that the fire suppression system is in line with the MEP specifications. Ensure that the Fire Suppression system is approved by the local civil defence /local Authorities. All components to be UL and FM approved. Provide calculation, sizing, drawings and schematics relevant to the project.			



QHSE Management System Formats
DESIGN
Material Submission Sheet Form

Project & Document Details	
Project Name: R24-067 - Kirkland & Ellis	Issue Date: 25-May-2025
Document ID: R24-067-ZZ-MNE-31-MAS-FL-0005	Return By: 29-May-2025
Revision: 02	
Material Details	
Description: FM200	Image
Location: LEVEL - 31; SERVER ROOM	
Drawing Code:	
Supplier / Manufacturer: AVENGER	
Supplier Code: CONTRACTORS SERVICES CO	
Review Details	
☐ A APPROVED	NAME: <u>Christopher C. Escobar</u>
☒ B APPROVED WITH COMMENTS	
☐ C REVISE AND RESUBMIT	
☐ D REJECTED	
SIGNATURE: _____	
DATE: <u>May 28, 2025</u>	
Comments:	
1. Submit method statement for installation and testing of FM200 system to include the following. a. Submit Sequence of Operation for the proposed FM200 system. Describe in detail the complete sequence of operation, including alarm functions, shutdown functions, remote signaling, damper operation, time delay and agent discharge for each zone or system. b. Submit a test plan describing procedures to be used to test the system. Include a step by step description of all tests to be performed and the type and location of test apparatus to be employed. c. Submit Operation and Maintenance Manuals following the requirements of the specification section 212203, Part 1.4, H-Test Plan. 2. Ensure that the FM200 System shall comply with the electrical requirements and is coordinated with the following. a. Power supply to the fire suppression system panel. b. Interlock wiring and conduit for shutdown of HVAC system and motorized dampers. c. Interface with building fire alarm systems. d. FM200 control panel shall be provided with battery backup minimum of 24-hours with 5-mins alarm. e. FM200 cabling shall be fire resistant cables CWZ. f. include the system in the electrical shop drawing for all system components (wall devices, ceiling devices) 3. All exposed equipment, controls and devices shall be submitted to Architect for final approval.	

MATERIAL SUBMITTAL									
PROJECT NAME : Dining Riyadh- Kingdom Tower					LOCATION : RIYADH - Kingdom Tower				
									
REF NO :- RAK-SER-MS-ME-021		REV 00		DATE : 15-Sep-22		☒ SUBMITTAL			
☐ ARCHITECTURAL		☐ ELECTRICAL		☐ CIVIL		☐ RE-SUBMITTAL			
☐ STRUCTURAL		☒ MECHANICAL		☐ OTHER PRE QUALIFICATION					
PLEASE FIND THE ENCLOSED FOLLOWING DOCUMENTS AND MATERIAL									
NO		DETAILS				REV		NOTE:-	
1		FIRE SUPPRESSION SYSTEM FM 200 -AVENGER				0			
SPECIFICATION REF:		NO SPECIFICATION							
DRAWING REF:		BH2688-FF-FNB-21-102-00-C							
DELIVERY LEAD TIME:		Within one week							
PRODUCT LOCATION :		Level 2- Server room & Electrical Room							
MATERIAL COMPLIANCE		Yes				No			
If No" Reason"									
FIRE SUPPRESSION SYSTEM FM 200 - HFC- 227 (UL/ FM APPROVED) -AVENGER									
 Mary Jane Gombio 10-Oct-22 www.bluehausgroup.com ☐ Approved ☐ Approved with comments ☒ Revise & Resubmit ☐ Rejected Notes and Comments: - No objection with the proposed brand/manufacture. - Contractor to provide detailed FM 200 calculation based on manufacturers standard for the actual requirement of sizes of nozzles, clean agent, etc. - Provide complete sequence of operation. - Provide warranty certificate for the whole FM 200 system									
<u>APPROVED STATUS</u>						C ☐ D			
COMMENTS:-									
PREPARED BY: Ali Khalil		RAKAL		TRANSMITTER SIGNATURE					
PROJECT MANAGER				CONSULTANT REPRESENTATIVE					
Rayan Shamaa									
☐		A - APPROVED		☐		B-APPROVED WITH COMMENTS			
☐		C - REVISE & RESUBMIT		☐		D - REJECTED			
This Approval does not release the contractor of his contractual obligations									
PROJECT MANAGER				SIGNATURE					
Engr.									
Inspected By				Date : Name & Signature of Consultant					
Remarks / Comments									

Material Submittal Checklist							
							
Project Name	Kingdom Social Dinning					Issue Date	15-September-2022
From	Company	RAKAL/ MOTIVE		To	Company	BLUEHAUS	
	Attention	Ali Khalil					
Material Submittal Description:							
Submittal Number	Doc. Type	Discipline	Comp. Initial	Serial No.	Rev. No.	Level	Lev. 2
	RAK-SER-MS- ME-021	MEP	RA/MO	021	00	Area	SERVER& ELECTRICAL ROOM
Item	Description					Status (Tick)	Remarks (if any)
1	Transmittal Form (Rakal Template)					OK	
2	Cover Sheet (Details of Trade contractor, Supplier, etc)					OK	
3	Index					OK	
4	Copy of previous Consultant comments (if not REV0)					N/A	REV0
5	Reply Sheet to Consultant Comment (stamped by supplier)					N/A	REV0
6	Material schedule (item description, model, brand, COO, qty, location)					OK	
7	Copy of relevant project specification sections (i.e. standard, material, spares, warranty, etc...)					OK	
8	Compliance Statement to project Specs (per clause, stamped by supplier)					OK	
9	Manufacturer Technical Sheets					OK	
10	Manufacturer Selection Schedule – if applicable					OK	
11	Valid Type Test Certificate					OK	
12	Valid Authority License i.e. ICD, Municipality, etc – as applicable.					OK	
13	Draft Warranty Certificate (by supplier)					NO	
14	Additional relevant Docs (specify)					NO	
15	Supplier / Manufacturer Company Profile – if applicable					OK	
16	Sample required? If YES, submitted?					NO	
17	Specified material or alternative? If alternative why?					NO	Specified
Submitted By							
Designation		Name		Date: 15-09-2022			
RAKAL Project Manager:		Rayan Shamaa					
Review Comments:							
Reviewed By		Company		BLUEHAUS ENGINEERING			
Main Contractor		Name					
		Signature				Date	



الرقم ٢١٠٠٤٩٢٤
التاريخ ١٤٤٦/٠١/١٥
المرفقات ١١

وزارة البيئة والمياه والزراعة
Ministry of Environment Water & Agriculture
Kingdom of Saudi Arabia المملكة العربية السعودية
(٣٧٤) الإدارة العامة للشؤون الهندسية
إدارة الإشراف على التنفيذ
٨١٦



المحترمين

السادة/ مكتب سجل العربية للإستشارات الهندسية

الرياض الرمز البريدي: ١٣٣٢٧ رقم المبنى: ٣٣٦٩ رقم الوحدة: ١ الرقم الإضافي: ٨٤٧٨
طريق الملك سلمان بن عبدالعزيز - حي النرجس سجل تجاري: ١٠١٠٤٣١٤٥١ جوال: ٥٩١٥٠٠٧٥

المحترمين

انسحة للسادة/ شركة الأولات للصناعة والإنشاء المحدودة

المدينة المنورة الرمز البريدي: ٤٣٣١٧ رقم المبنى: ٦٩٨٨ رقم الوحدة: ٩ الرقم الإضافي: ٤٦٨٢
شارع: ثابت بن خفصاء - حي الخالدية سجل تجاري: ١٠١٠٢٦٧٨٤٨ جوال: ٥٥٥١٩٠٧٩٦-٠٥٤٤٤٤٩٩٣٦

السلام عليكم ورحمة الله وبركاته...

إشارة إلى خطابكم الوارد برقم (٢٥٠٠٨٩٧٢) وتاريخ ١٤٤٥/٠١/١٠ هـ (مرفق نسخة)، بشأن الإشراف الفني على مشروع إنشاء مركز التميز الوطني بمنطقة مكة المكرمة، تميم رقم (٥٢٠٠٠٠٩٨٤٨) والمتضمن طلب المقاول (شركة الأولات للصناعة والإنشاء المحدودة) اعتماد المواصفات الفنية للمواد الخاصة بنظام إطفاء الحريق (FM200) وصناديق إطفاء الحريق للمشروع. عليه نفيدكم بأنه لا مانع من اعتماد المواصفات الفنية للمواد الخاصة بنظام إطفاء الحريق (FM200)، وصناديق إطفاء الحريق للمشروع (مرفق نسخ)، مع الإلتزام بالمواصفات الفنية وجدول الكميات التعاقدية ومتطلبات الدفاع المدني، والإلتزام بالقائمة الإلزامية للمحتوى المحلي، للإطلاع وسرعة إكمال اللازم.

مع أطيب تحياتي...

نائب مدير عام

الإدارة العامة للشؤون الهندسية



م. تركي بن عبد العزيز الجديد



المرفقات : بدون



70. 4140





شركة أسكن لتطوير وإدارة المدن الصناعية
AAE for Developing & Operating Industrial Cities



ARCH VIEW COMPANY

شركة الباسل للمقاولات
المقاول

شركة أساس لتطوير وتشغيل المدن الصناعية
المالك

شركة ارك فيو للاستشارات المهنية
الاستشارات

REQUEST FOR SHOP DRAWING APPROVAL

طلب اعتماد مخططات تنفيذه

رقم التقديم	نوع التقديم	إعادة تقديم	تاريخ التقديم:	25-04-2024
اسم المبنى:	رقم المبنى		جزء المبنى	صالة الأرشيف
نوع المخطط	التقديم السابق:		نوع التقديم	حسابات نظام الإطفاء والمخططات تصميمية
موضوع التقديم				

م	اسم المخطط	المنطقة	كود اعتماد المخطط	تاريخ المخطط
1	نظام الإطفاء بالغاز (full layout)	صالة الأرشيف		
2	Detectors & Notification	صالة الأرشيف		
3	Isometric for Lengths & Diameters part 1	صالة الأرشيف		
4	Isometric for Lengths & Diameters part 1	صالة الأرشيف		
5	Layout view pipes lengths & Diameters	صالة الأرشيف		
6	S.L.D Riser Diagram & Design data			
7	HFC227 ea system (shop drawing)			

Contractor's Stamp & Sign

توقيع و ختم المفاوض:

اقرار المفاوض: يتعهد المفاوض بأن التقديم ملتزم التزاما تاما بمواصفات العقد

المهندس المقاول المختص : الاسم : <u>محمد بن عبد الله</u> التوقيع : <u>[Signature]</u>	مدير المشروع المقاول : الاسم : <u>محمد بن عبد الله</u> التوقيع : <u>[Signature]</u>	التاريخ : ختم المشروع
--	--	-------------------------------------

Consultant's Stamp & Comments

ملاحظات و توصيات الاستشاري :

☐	كود (A)	التوصية بالموافقة على المخطط بدون ملاحظات
☒	كود (B)	التوصية بالموافقة على المخطط مع ملاحظات
☐	كود (C)	التوصية بالرفض للمخطط مع إعادة التقديم
☐	كود (D)	يعاد لعدم كفاية أو إكمال المعلومات

لا مانع من اعتماد حبات وحفظات لطفاء الحريق بنظام FM200 لصلابة الأرضية
- ضرورة توضيح كيفية تثبيت ماسورة خرطوم القار السفلى لكابت الخرطوم السفلية
- ضرورة عمل النظام تحت مسؤولية القابل، وليس له المتخصصه من مكتب نظام
FM200 وذلك، وفقاً للمواصفات NFPA 801 - NFPA 801

يجب الالتزام بالمواصفات و الكميات و الشروط العقدية ،الالتزام باشتراطات الكود السعودي للبناء، الالتزام بتوصيات الدفاع المدني و السلامة العامة

المهندس الاستشاري المختص: الاسم: <u>صبيح الحكيم</u> التوقيع: <u>[Signature]</u>	مدير المشروع الاستشاري: الاسم: <u>أحمد عيسى</u> التوقيع: <u>[Signature]</u>	التاريخ:
المهندس الاستشاري المختص: الاسم: <u>محمد عبد الوهاب</u> التوقيع: <u>[Signature]</u>	مدير المشروع الاستشاري: الاسم: <u>أحمد عيسى</u> التوقيع: <u>[Signature]</u>	التاريخ:

اعتماد الخططات لا يعفى الما قول من التزاماته التعاقدية

رئيس القسم الإثني — راف

ممثل الم — الك:



MATERIAL SUBMITTAL

PROJECT NAME: SUPPORTING BUILDINGS PROJECT PHASE 2 ZONE B

SUBJECT: TECHNICAL SUBMITTAL OF FM-200 SYSTEM BY M/S. CONTRACTOR SERVICES CO.

B.O.Q. Code Ref.	ATTACHMENT INCLUDED: A TECHNICAL SUBMITTAL FORM AND SOFT COPY.	Submittal No. Q5-PH2-ZB-ME-MT-091
		Date Received: 25/5/2022
		Date Returned:

Sub-contractor
Name: MASAH CONTRACTING CO. Address: P.O. Box 272000 Riyadh 11352, Kingdom of Saudi Arabia
Address: Phone: 966 55 500 3427 Telex: 9665 011 215 7354

Manufacturer	Supplier/Agent
Name: CSC	Name: CSC
Address: P.O BOX-41208, Al Riyadh 1152 K.S.A	Address: P.O BOX-41208, Al Riyadh, 1152 K.S.A
Phone: +966 11 4713176	Phone: +966 11 4713176
Fax: +966 11 2420140	Fax: +966 11 2420140
Telex:	Telex:

Information submitted and attached:

Certificates	☐	Operation & Maintenance Manual	☐
Technical Brochure	☐	Spare Parts List	☐
Manufacturer's Data & Specs.	☐	As Built Drawings	☐
Shop Drawings	☐	Warranty	☐
Samples	☐	Others (specify)	☐

Contractor's Comments:

PQD OF M/S. VOLTMATIC CO. IS ALREADY APPROVED AS SUPPLIER IN MODA UNDER SUBMITTAL Q5-PH2-ZB-ME-DC-087

Note: This review does not relieve the contractor (Contractor)
Of his responsibilities under the terms of the contract Signature:
nor authorize additional compensation. Date: 23/05/2022

Consultant's Comments: (1) For-200 system components from CSC is acceptable, subject to following:
(2) Final component list shall be as per the calculations & shop drawings, Submit calculations & shop drawings for the system installed by For-200.
(3) Electrical control panel & other items (distributors, Alarms, Calling etc..) shall be verified & approved by electrical department.

See Attachment ☐ (4) Final approval is subject to client acceptance.

Status:	Discipline	Sign & Date	Resident Engineer	Client Note
A - Approved ☐	Arch ☐			
B - Approved as noted ☒	Civil ☐		Sign:	Sign:
C - Revise and submit ☐	Mech. ☒	Mr. Ibrahim 23/5/2022	Date:	Date:
D - Rejected ☐	Elect ☐	Ref: 23/5/2022	Name:	Name:
E - Noted/ NA ☐	HVAC ☐			
	LS ☐			

Remarks:

- The drawings and materials submitted by the contractor should be covered by the contract value. Any additional materials or drawings should be mentioned in the submittal.
- Copies and Attachments: Original (For Consultant), Copy No. (1) (For Consultant), Copy No. (2) (For Site Manager).

 ZUHAIR FAYED PARTNERSHIP CONSULTANT	 وزارة الدفاع MINISTRY OF DEFENSE	MASAH CONTRACTING CO.  شركة مساح MASAH CO. Specialized Contractor في التخصصات SUB CONTRACTOR
--	--	--

DOCUMENTS SUBMITTAL

PROJECT NAME: SUPPORTING BUILDINGS PROJECT (PHASE-2) ZONE-II

SUBJECT:	PRE-QUALIFICATION OF M/s. CONTRACTOR SERVICES CO. FOR TRADING & CONTRACTING (CSC FIGHTING SERVICES & FM-200 SYSTEM)		
B.O.Q. Code Ref.	ATTACHMENT INCLUDES: A. P/Q DOCUMENTS HARD & SOFT COPY	Submittal No.	Q5-PH2-ZB-ME-DC-089
		Date Received:	18/5/2022
		Date Returned:	

Sub-contractor Name:	MASAH CONTRACTING CO.	Address:	P.O. Box 272000 Riyadh 11352, Kingdom of Saudi Arabia
Address:		Phone:	966 55 500 3427
		Telex:	+966 011 216 7854

Manufacturer Name:	CSC	Supplier/Agent Name:	CSC
Address:	P.O BOX-41208, Al Riyadh, 1152 K.S.A	Address:	P.O BOX-41208, Al Riyadh, 1152 K.S.A
Phone:	+966 11 4713176	Phone:	+966 11 4713176
Fax:	+966 11 2420140	Fax:	+966 11 2420140
Telex:		Telex:	

Information submitted and attached:	
Certificates ☐	Operation & Maintenance Manual ☐
Technical Brochure ☐	Spare Parts List ☐
Manufacturer's Data & Specs. ☐	As Built Drawings ☐
Shop Drawings ☐	Warranty ☐
Samples ☐	Others (specify) ☐

Contractor's Comments:	
	
Note: This review does not relieve the contractor	(Contractor)
Of his responsibilities under the terms of the contract	Signature:
nor authorize additional compensation.	Date: 18/05/2022

Consultant's Comments: *Pre Qualification as a Contractor for 'CSC' for fire system can be acceptable subject to complying with specification & project requirements. Final approval is subject to client approval.*

See Attachment ☐

Status:	Discipline	Sign & Date	Resident Engineer	Client Note
A - Approved ☐	☐ Arch			
B - Approved as noted ☐	☐ Civil		Sign:	Sign:
C - Revise and submit ☐	☒ Mech.	18/5/22	Date:	Date:
D - Rejected ☐	☐ Elect		Name:	Name:
E - Noted/ NA ☐	☐ HVAC			

Remarks:

- The drawings and materials submitted by the contractor should be covered by the contract value. Any additional materials or drawings should be mentioned in the submittal.
- Copies and Attachments: Original (For Consultant), Copy No. (1) (For Consultant), Copy No. (2) (For Site Manager).

ISO

اسم المشروع : اعمال تنفيذ الجبهة الشمالية
والمرافق المساندة لإدارات القطاع الشمالي

الجهة المستفيدة : القوات الجوية الملكية السعودية

الموقع : محطة رادار جبل اللوز

رقم العقد : 41/9 هـ

شعار المقاول



شركة العيوني للاستثمار والمقاولات
AL-AYUNI INVESTMENT & CONTRACTING CO.

ترويسة المقاول

اسم المقاول : شركة العيوني للاستثمار والمقاولات

طلب اعتماد عينات

رقم الطلب: 79

التاريخ : 12 / 02 / 1444 هـ

الوصف

رقم البند في جدول
الكميات

اسم المادة

1- شركة اعمال المقاولين للتجارة والمقاولات (CSC)

نظام اطفاء الحريق بنظام الغاز

(HFC227ea)

توقيع الممثل

وقت وتاريخ التسليم: 1444/02/12 هـ
10.00 ص

التوقيع



اعتمادات الإشراف

موافق بشروط



غير موافق



موافق



الملاحظات والاصحاحات :

* يتطلب تقديم الضمانات وكتيبات التشغيل والصيانة وتدريب

المختصين على الأنظمة والإلتزام بمعايير الحقد وإجراء كافة

الاختبارات من المورد قبل تسليم المشروع *

توقيع المهندس المشرف: النقيب المهندس هاني سعد

التاريخ :

توقيع المهندس المختص

الوقت :

توقيع مدير قسم الدراسات والإشراف المقدم المهندس ريان الشريف

CLIENT:-



CONSULTANT:-



Contractor:-



PROJECT NAME:- توريد وتركيب وتشغيل وإشراف نظام الإنذار والإطفاء الآلي بمحطة الخدمات البيئية بالرياض

MATERIAL SUBMITTAL

Ref. No.:

F.F-007

Rev 0

Date:

0 5

1 0

2 2

New Submittal

Resubmittal

☐

Architectural

☐

Electrical

☐

Civil

☐

Others

Specs. No.

☐

Structural

☒

Mechanical

☐

Interior Design

Drawg. No.

Please find enclosed the following documents/drawings:

No.	Description*	Manufacturer	Supplier	No. of Catalogue	Code
	FM200 SYSTEM	AVENGER FIRE SUPPRESSION SYSTEM	CSC CO.	1	

Description (Manufacture, Model, Type, Size, Colour, etc.)

☒ Catalogue☐ Drawing☐ Sample☒ Certificate☐ Calculation☐ Document

Having checked this submittal, we certify that it conforms to requirements of the Contract Documents in all respects, except as otherwise indicated here in.

Material Engineer /Name & Signature:

Technical Manager:

Received by:

Eng. AHMED SANDEEDIN

Date: 05-10-2022

Signature:

Remarks / Comments:

All parts to be installed Must comply with Attached
UL Certificates.

Status

A
B

Approved

Approved as noted

C Approved as noted submit again

D Disapproved resubmit

Project Manager

Eng. AHMED SANDEEDIN

Name & Signature of Engineer

06-10-2022

Date

Date

Name & signature

شركة حمود صالح الجريا
للإستشارات الهندسية
ترخيص رقم: ٥١٠٠٠١٦٢١
م.ب.ت: ١٠١٢١٦٤١٥


 	HOUSE OF CONSULTING OFFICE		 
	Drawing Transmittal Sheet IT Room		

Project Name	Film Crew Lodge Phase 2 & 3	Client	Royal Commission for Al-Ula	
Project No.	PR6870	Contractor	Red Sea International (RSI)	
Location	Al-Ula			
Submittal No.	Multiple	New Submittal	Date	25-Aug-23
Rev. No.	00	Re-Submittal	Previous Submittal\Rev. No.	
Discipline				
☐ Architectural ☐ Civil ☒ Electrical ☐ Telecom ☐ Structural ☐ Firefighting ☐ HVAC ☐ Interior Design ☐ Plumbing ☐ Mechanical				
Please find enclosed the following Documents/Drawing:				
S\N	Drawing No.	Rev No.	Description\Title	Code
1	MP2MGDMMD1004-RSH-XX-RB-000-DG-HS-150002	00	IT Room - Fire Suppression System Layout	B
2	MP2MGDMMD1004-RSH-XX-RB-000-DG-HS-150003	00	IT Room - Fire Suppression System Layout	B
See the comments in the attached excel sheet				
Submitted for				
☒	Approval	☐	Further Action	☐
☐	Filing	☐	For Information	☐
Comments				
Approval Status (Code)				
☐ A	Approved	☐ B	Approved as Noted Resubmittal is Not Required	☐ C
☐ D	Disapproved	☐ N	No Action	☐
Submitted By	Red Sea Document Controller Red Sea International	Checked\ Approved By		
Date	25-Aug-23	Date		

CLIENT	ROYAL COMMISSION FOR ALULA	المدينة الملكية لمحافظة الالوة Royal Commission for AlUla
	HOUSE OF CONSULTING OFFICE	HCO
	ATKINS	ATKINS

OCCUPANCY CLASSIFICATION	GROUP - B
OCCUPANT LOAD	1
TYPE OF CONSTRUCTION	II-B

BUILDING PROFILE



LEGEND / NOTES:

APPROVED FOR SUBMISSION TO CLIENT

CONTRACTS:		D	
ENGINEERING:		A	
		T	
		E	
CLIENT APPROVAL		APPROVAL TYPE:	
APPROVED BY:		A - APPROVED.	
DATE APPROVED:		B - APPROVED AS NOTED, RESUBMITTAL ISN'T REQUIRED.	
APPROVAL TYPE:		C - APPROVED AS NOTED, RESUBMITTAL IS REQUIRED.	
		D - DISAPPROVED.	
		N - NO ACTION.	

CONSULTANT APPROVAL (CONSULTANT SUPERVISOR)

APPROVED BY:	
DATE APPROVED:	
APPROVAL TYPE:	

REV. NO.	DESCRIPTION	DATE	BY
00	FOR CLIENT APPROVAL	16 AUG 2023	FH

CLIENT NAME:	ROYAL COMMISSION AL ULA (RCU)
WORK ORDER NO.:	90-1222-0051
DRAWING TITLE:	IT ROOM
MODEL NUMBER:	RSS-2-72865
QUANTITY:	6 EACH
SPECIFICATION:	FIREMASTER SERIES
VOLTAGE/CYCLE:	400/230V, 3Ph., 60Hz., 4W+G
BUILDING SIZE:	1850mm x 2440mm
PROD. SERIAL NO.:	25538 to 25540 (P2) 25541 to 25543 (P3)



DRAWN BY:	FH	
CHECKED BY:	AN	
APPROVED BY:	AZ	
DATE:	22 AUGUST 2023	
SCALE:	1:50	SIZE: A4
SHEET NO.:	E311	




FITTINGS:
SHALL BE OF TYPE ASTM A234 GR. WPB FOR 2½" SIZES AND LARGER AND SHALL BE OF TYPE THREADED GALVANIZED FORGED STEEL WITH ASTM A105, CLASS 3000 FOR 2" SIZES AND SMALLER.

ITEM	DESCRIPTION	QUANTITY
1	25mm 90 DEGREE ELBOW	03



ITEM	DESCRIPTION	MANUFACTURER
1	CYLINDER WITH VALVE C/W TOP PLUG ADAPTER	AVENGER
3	CYLINDER STRAP	AVENGER
4	LATCHING SOLENOID	AVENGER
5	LOCAL MANUAL CONTROL HEAD FOR 383L018	AVENGER
6	PRESSURE SUPERVISORY SWITCH (N/C) 360 PSI	AVENGER
7	FLEXIBLE HOSE	AVENGER
8	CAUTION-ROOM PROTECTED	AVENGER
9	NOZZLE ALUMINUM	AVENGER

PIPES :
SHALL BE OF TYPE STEEL WITH ASTM A53, GR.B, SCH40, SEAMLESS/ERW

ITEM	PIPES	LENGTH (METER)
1	25mmØ	3.010



S.NO.	HAZARD NAME	WIDTH (m)	LENGHT (m)	HEIGHT (m)	VOLUME (m³)	MINIMUM DESIGN CONCENTRATION	AGENT REQUIRED PER CYLINDER	CYLINDER QTY.	AGENT REQUIRED	NOZZEL QTY.
1	IT ROOM	1.850	2.440	2.140	9.659	7.0%	20LBS	2	40LBS	1



FIRE SUPPRESSION SYSTEM (SHEET 1 OF 2)

VIEW SCALE

1:35 METERS



- c. Second Party will be responsible for any mishap during the inspection or service due to negligence of Technician/Engineer.
- d. Second Party shall maintain equipment in accordance with manufacturer recommendation.
- e. Ensure adherence to all relevant client Environmental, Health and safety Regulations, Code of Conduct and policies and procedures.
- f. Second Party shall use standard tools & Supplies which is approved by NFPA to perform the required job and ensure all statutory inspection are carried out.
- g. Second Party shall respond to the First Party's Emergency request within 24 hours.
- h. Second Party shall provide separate quotation for spare parts if needed.
- i. Second Party shall submit invoice for the services to be provided.

3. General Obligations of the First Party:

- General Obligations of the First Party:**
- a. In case of emergency or any abnormal operation and/or stoppage of subject equipment it is the responsibility of the First party to communicate with the Second Party at the following contact Mobile : 0545103634 email address a.zakaria@csc.com.sa
- b. First Party shall pay the Maintenance charges SR 70,000/- in 2 equal instalments in advance as agreed thru previous contract reference # QT 18193-08-16

4. **Contract duration – Continuation:**

Contract duration – Continuation:
The period of this contract will start from 07-Aug-2016 to 06-Aug-2017 and it will be considered as automatically renewed with mutual understanding unless otherwise either party give a written notice prior 30 days of contract termination.

5. Price:

Maintenance charges are fixed per year SR Seventy Thousand (70,000) per year only to be paid in 2 equal installments in advance.

6. Governance:


- Verne:**
- The parties undertake to immediately inform one another of matters or circumstances that preclude proper performance of the Agreement.
 - The parties will consult on the level of department / Supply chain managers in accordance with the requirement of this contract.
 - A written report will be compiled of each consultation by the department/service manager of the First Party of Second Party (depending on where the meeting has held) as quickly as possible but within Three (3) working days, which will record at least any decision that are relevant to management of the agreement. This report will be submitted to the other party for comments, which will notify any comments within the same Three (3) working days. The report will then be adopted during the next consultation, if necessary indicating any points in the report over which the parties do agree.
 - Communication between parties will take place in English otherwise agreed.

7. **Evaluating Methodology and Performance Indicator(s) :**

Average Breakdown time = number of hours equipment down divided by 180 days.
Response time = sum of number of hours divided by total emergency calls.

8. Monitoring:

- a. **Reporting:** The Second Party shall provide the First Party the plan and scheduled route for each delivery, so as to facilitate monitoring of performance of all work to be conducted under this Agreement. All employees of the Second Party shall perform their duties in accordance with the scheduled plan and routes assigned to them.
- b. **Second Party Authorization:** The second party shall submit to the First Party a copy of valid Commercial Registration (CR), Saudi Food and Drug Authority (SFDA), Saudi Standards, Metrology and Quality Organization (SASO) certificates, Manufacturer authorization(s) and any other certificate if available.





Saudi German Hospitals Riyadh (Branch)

10. Liability:

- If First Party fails to make payment within the prescribed time, the Second Party will have the right to suspend any service until and unless due payments received by the Second Party.
- If Second Party fails to comply with the clauses mentioned under the section of Obligations then the First Party reserves the right to report to the Government accredited authorizations.

11. Force Majeure:

A party shall not be liable for any failure or delay in the performance of this Agreement for the period that such failure or delay is due to causes beyond its reasonable control, including but not limited to acts of God, war, strikes or labor disputes, embargoes, government orders or any other force majeure event.

12. Confidentiality:

The terms and conditions of this Agreement are absolutely confidential between the parties and shall not be disclosed to anyone else, except as shall be necessary to effectuate its terms. Any disclosure in violation of this section shall be deemed a material breach of this Agreement.

13. Termination:

The period of this contract is one (1) year from the date of signature and stamps from the both parties and it will be considered as automatically renewed with mutual understanding unless otherwise either party give a written notice prior 30 days of contract termination.

14. Dispute Resolution Procedure:

This Agreement shall be governed by provisions of regulations prevailing in Saudi Arabia. Disputes arising between the parties concerning the interpretation of the agreement shall be reconciled through Saudi Court Riyadh.

Both parties confess that the addresses written in the beginning of this contract are the chosen locations for each and any messages sent to those addresses are rightful, legal, effective and incontestable.

In witness thereof, the parties hereto have set their hands on the date stated below.

First Party (Saudi German Hospital Riyadh)

 Fire & Safety Officer	 Eng. Abdul Rauf Bhatti Maintenance Manager	 Mr. Gaber A. Gaber Legal Officer
 Dr. Amir Rizwan Group QPS Director	 Mr. Rana Sher Muhammad Procurement Manager	 Mr. Abdel Fattah Hassanein Chief Executive Officer

Second Party (Contractors Services Company)**Eng. Magdi Abdul Aziz****Executive Manager**

11/8/2016



ALHaddad Mohammad
AECOM

Final (WF-070107) 14-4800000344/000-IN-Construction - ...
WORKFLOW TRANSMITTAL

12:39 AM
ACM-WTRAN-126877

14 Outer Regions
Riyadh, KSA
Riyadh
Saudi Arabia

AECOM Delivering a better world

MAIL TYPE
Workflow Transmittal

MAIL NUMBER
ACM-WTRAN-126877

REFERENCE NUMBER
ACM-WTRAN-126877

Final (WF-070107) 14-4800000344/000-IN-Construction - IFR

FromMr ALHaddad Mohammad - AECOM

To (2)Mr ALHaddad Mohammad - AECOM (+1 more...)

Cc (7)Mr Abdulrahman AlQarni - AECOM (+6 more...)

SentFriday, 14 April 2023 12:39:41 AM AST (GMT +03:00)

StatusN/A

DOCUMENT ATTACHMENTS (2)

(2 selected)					
File	Document No	Revision	Revision Date	Title	Status
	14-371200-4800000344-BEI-FPR-CRS-000019	01	06/04/2023	4800000344/000 - Technical Submittal for Fire Suppression System - (Avengers-USA)	B - Incorporate Comments - Proceed
	14-371200-4800000344-BEI-FPR-MAT-000005	01	06/04/2023	4800000344/000 - Technical Submittal for Fire Suppression System - (Avengers-USA)	B - Incorporate Comments - Proceed

MESSAGE

Workflow Review History

The attached documents have completed the "14-4800000344/000-IN-Construction - IFR" workflow with the following results :

This transmittal was automatically generated.

Doc No	Step	Participant	Review Outcome	Comments
--------	------	-------------	----------------	----------

14-371200-4800000344-BEI-FPR-CRS-000019	NEOM/AECOM_Review	A Mohammad	B - Incorporate Comments - Proceed	see crs
14-371200-4800000344-BEI-FPR-MAT-000005	NEOM/AECOM_Review	A Mohammad	B - Incorporate Comments - Proceed	see crs



ليوم NEOM

AECOM



Document Submittal Form

Contractor	Beijing Emirates International Construction Company	Document submittal no.	14-371200-4800000344-BEI-FPR-CAL-000002_01
Contract no.	4800000344/000	Date	15-Mar-2023
To PMC	AECOM		

Document no.	Type	Description	Rev no.	Action required
14-371200-4800000344-BEI-FPR-CAL-000002	Calculation	4800000344/000 - Novec System Capacity Calculation for Data Room (GF-26)	01	☒ Approval ☐ Comments ☐ Information ☐ Other
				☐ Approval ☐ Comments ☐ Information ☐ Other
				☐ Approval ☐ Comments ☐ Information ☐ Other

Contractor authorized signatory.


Name	Amir Afifi	Date	15-Mar-2023
Signature			

PMC s comments

<table style="width: 100%;"> <tr> <td style="width: 25%;">Status code</td> <td style="width: 25%;"> ☐ No exception taken ☐ Rejected </td> <td style="width: 25%;"> ☐ Exception as noted revise and resubmit for record ☐ Review not required </td> <td style="width: 25%;"> ☐ Revise and resubmit ☐ Issued for Construction </td> </tr> </table>	Status code	☐ No exception taken ☐ Rejected	☐ Exception as noted revise and resubmit for record ☐ Review not required	☐ Revise and resubmit ☐ Issued for Construction
Status code	☐ No exception taken ☐ Rejected	☐ Exception as noted revise and resubmit for record ☐ Review not required	☐ Revise and resubmit ☐ Issued for Construction	
<table style="width: 100%;"> <tr> <td style="width: 50%;">Engineer's name</td> <td style="width: 50%;">Date</td> </tr> </table>	Engineer's name	Date		
Engineer's name	Date			
Signature				

Received by Contractor

Name		Date	
Signature			



نيوم NEOM

CALCULATION REPORT

4800000344/000 - Novec System Capacity
Calculation for Data Room (GF-26)

14-371200-4800000344-BEI-FPR-CAL-000002_01

15-Mar-2023



Document history

Revision code	Description of changes	Purpose of issue	Date
01	First Submission	For Approval	15-Mar-2023

Document approval

	Prepared by	Reviewed by	Approved by
Name	Hussein Hamdy	Hussein Hamdy	Amir Afifi
Job Title	Technical Director	Technical Director	Project Manager

اعتماد مواد / بند

اسم المشروع ورقم	تأمين، الخلية، لائحة وزارة العدل	رقم العينة	
المقاول الرئيسي للمنظ	شركة ارسكوم	المقاول من المثلث ان وجد	م. قنوات التوريد
تاريخ تقديم العينة	18/1/1435	رقم المنتج ان وجد	21 برصد
رقم المخرج		رقم المرحلة	رقم واحد
مسلي () اشقي () كهربائي () ميكانيكي () إلكتروني () أخرى ()			
الوصف		التفاصيل :	
توريد وتركيب نظام فضاء 2 ضد الحريق		() قنوات () شهادات () متطلبات حسب الموقع () رسومات تنفيذية	
الصانع		شركة اسبال للمقاولين CSC	
ملاحظات المقاول المنظ		يتم تجهيز غرفة التفتيش، المعلومات في غرفة وزارة العدل من نظام ضد الحريق - طبقاً لخواصها - المعلومات	
موقع / مدير المشروع قنوات التوريد		الاسم: <u>فالح العمير</u> التوقيع: <u>9.9</u> الختم:	
الجهة / العميل		الاسم: <u>مجلس إدارة العدل</u> الختم:	
راجع المواصفات من الجهة المشرفة		الاسم: <u>محمد الجب</u> التوقيع:	
اعتماد مدير / مالك المشروع من الجهة المشرفة		الاسم: <u>محمد عبد الله</u> التوقيع:	



SALFO AND ASSOCIATES SA
Engineering & Management Consultants

Discipline: Architectural ☐ Civil / Structural ☐ MEP ☒ Others ☐

Attachments: Product Data Sheet ☒ Catalogues ☒ Samples ☐ Compliance Statement ☐

Others ☐ Please specify: 2 hard copies/1 CD

Received
10 DEC 2016
HALFO
GAZAR

As per our attached Comments Sheet

[illegible]

PROJECT : C4 RESIDENTIAL BUILDING (2B+G+10F)
SUBMITTAL Ref. No. : C0504/MSF/C4/F/FA/002 Rev.0
Date of Issue : 08/12/2016
Material Description : Fire Alarm System
Manufacturer : AVENGER / USA
Supplier : REGENCY / QATAR

COMMENTS SHEET

1. QCDD Product Approvals for all proposed Fire Alarm Equipment, should be valid at the date that QCDD will inspect the Project Fire Alarm and Fire Fighting Systems Installation. In case any of the submitted QCDD Product Approvals is no longer valid at that date, Contractor should have in advance provide Consultant with new (valid at that date) QCDD Product Approval, to be attached in Consultant Application to QCDD for Inspection of Fire Alarm and Fire Fighting Systems Installations.
2. Submitted Cause & Effect Matrix should follow relevant Cause & Effect Matrix of Design Drawing. Please provide compliance statement or refer the deviations and the reasons caused to such deviations.
3. Test Certificates and Certificate of Origin should be transmitted along with any product delivery to site and should be attached to any relevant Material Inspection Request (M.I.R.).
4. Manufacturer instructions for transporting, handling, storage, installation, commissioning, testing and maintenance should be also submitted along with every product delivery at site and should be also attached to any relevant Material Inspection Request (M.I.R.).
5. Material Submittal approval by the Consultant is subject to relevant final approval or rejection by QCDD.

SALFO MEP Engineer

F. HOSSEIN



02/02/2017.

FUNCTION	ACT	CCRT	INFO
HO			
Project Manager			
Engineering			
Construction			
QA/QC			
HSE			
MEP			
Planning			
Contracts			
File			
CE			
QC			
SA			
TK			

ENGINEER'S Document Transmittal Information				
Contract:		Transmittal Number:		
C4, C5, & FV9		UD-143-DTI-768		
		5-Feb-17		
FORWARDED TO:		1. Approved Work May Proceed.		
M/s. Ghantoot Construction & Transport Devt.		2. Approved W/Comm. Work may Proceed subject to incorporation of comments indicated.		
Attn. Engr. Anas Assasah Project Manager		3. Revise & Resubmit. Revise and resubmit. Work may not Proceed.		
		4. Reject Work Rejected. Work may not Proceed		
		5. For Information For Information		
CC:				
DOCUMENT NO.	CONTRACTOR REF. NO.	Rev	DESCRIPTION	Code
3937	C0504-MSF-C4-F-FA-002	0	FIRE ALARM SYSTEM	2
4082	C0504-MSF-C4-F-FF-002	0	FM 200 SYSTEM	2
4081	C0504-MSF-C4-F-FF-003	0	FIRE FIGHTING GROOVED & THREADED GI FITTINGS	2

ANY APPROVAL, CHECK, CERTIFICATE, CONSENT, EXAMINATION, INSPECTION, INSTRUCTION, NOTICE, PROPOSAL, REQUEST, TEST, OR SIMILAR ACT BY THE ENGINEER (INCLUDING ABSENCE OF DISAPPROVAL), SHALL NOT RELIEVE THE CONTRACTOR FROM ANY RESPONSIBILITY HE HAS UNDER THE CONTRACT, INCLUDING RESPONSIBILITY FOR ERRORS, OMISSIONS, DISCREPANCIES AND NON COMPLIANCES.

REMARKS		
Please find the attached reference: C0504-MSF-C4-F-FA-002, C0504-MSF-C4-F-FF-002, C0504-MSF-C4-F-FF-003		
ISSUED BY	DESIGNATION	SIGNATURE
Christos Roussouidis	Project Manager	 CR 05/02/2017
CONTRACTOR'S ACKNOWLEDGEMENT RECEIPT		
RECEIVER'S SIGNATURE:	DESIGNATION:	DATE:
		5/2/2017



ENTERTAINMENT CITY BUILDING C0504-04 (C4)

TRANSMITTAL

S/N	Document Ref		Drawing Ref		Description	Copy	Format	Status
	Ref. No.	Rev	Ref. No.	Rev				
8.	C4-SB-ESC-MT-E-25	0			MS-FIRE ALARM SYSTEM	3 hard copy/2soft copy		
9.	C4-SB-ESC-MT-M-PL-10	0			MS-CATCH BASIN, PLANTER DRAIN, VENT CAP	3 hard copy/2soft copy		
10.	C4-SB-ESC-MT-M-PL-11	0			MS-CONDENSATE DRAIN PIPES & FITTINGS	3 hard copy/2soft copy		
11.		0						
12.		0						
13.	C4-SB-ESC-MT-E-26	0			MS- WIRING DEVICES & ACCESSORIES/CEILING ROSE	3 hard copy/2soft copy		
Remarks:								

PLEASE ACKNOWLEDGE RECEIPT OF THE LISTED ITEMS BY SIGNING AND RETURNING DUPLICATE COPY OF THIS FORM.

EASTERN SYNERGY CONTRACTING

KHALIFA BIN NASSER CONSTRUCTION AND DEVELOPMENT

Prepared by:	Willem C. De Gutzman	Verified by:	Mohamed Yassin	Approved by:	Ahmed Tarek
Company:	ESC	Company:	KBN	Company:	GCT
Designation:	Sr.QS/QC Engineer	Designation:	MEP Coordinator	Designation:	Project Manager
Date:	30/Nov/2016	Date:	30/Nov/2016	Date:	30/Nov/2016
Signature:		Signature:		Signature:	

FOR DCC only:

Acknowledged Receipt by:

File Ref:

Signature:



ok
7.12.2016

		  
ENTERTAINMENT CITY BUILDING C0504-04 (C4)		

TRANSMITTAL

Project Name:	Entertainment City C4 - Project	Date:	30/Nov/2016
Project Number:	C4	Transmittal Ref:	2016-P001-111TR
Subject:	Material Submittal		
Attention To:	Engr. Ahmed Tarek	From:	Mohamed Yassin
Designation:	Project Manager	Designation:	MEP Coordinator
Company:	GCT	Company:	KBN
Tel:	+974 40358282	Tel:	+974 40165864
Fax:	+974 44414751	Fax:	+974 40165869

WE ARE SENDING:		SUBMITTED FOR:		ACTION TAKEN:	
☐	Letter	☒	Approval	☐	Approved
☐	Shop Drawings	☐	Action	☐	Approved as Noted
☒	Material Submittal	☐	Review & Comment	☐	Revise and Resubmit
☐	Plans	☐	For Information Only	☐	Rejected
☐	Samples	☐			
☐	Specifications	SENT VIA:			
☐	Others	☐	Email	☐	By Courier
☐	Others	☒	Hand	☐	Fax

S/N	Document Ref		Drawing Ref		Description	Copy	Format	Status
	Ref. No.	Rev	Ref. No.	Rev				
1.	C4-58-ESC-MT-M-ACMV-11	0			MS-DIELECTRIC UNIONS & FLANGES	3 hard copy/2soft copy		
2.	C4-58-ESC-MT-M-ACMV-12	0			MS-PRESSURE INDEPENDENT CONTROL VALVE	3 hard copy/2soft copy		
3.	C4-58-ESC-MT-M-ACMV-13	0			MS-INERTIA BASE & VIBRATION ISOLATORS	3 hard copy/2soft copy		
4.	C4-58-ESC-MT-M-ACMV-14	0			MS- AIR VENT	3 hard copy/2soft copy		
5.	C4-58-ESC-MT-M-ACMV-15	0			MS- FLEXIBLE CONNECTOR	3 hard copy/2soft copy		
6.	C4-58-ESC-MT-M-ACMV-16	0			MS-THERMOMETER & PRESSURE GAUGES	3 hard copy/2soft copy		
7.	C4-58-ESC-MT-M-ACMV-17	0			MS-VALVES & ACCESSORIES FOR CHILLED WATER APPLICATION	3 hard copy/2soft copy		

ENTERTAINMENT CITY BUILDING C0504-04 (C4)

MATERIAL SUBMITTAL FORM - MSF

MSF No.	C4-58-ESC-MT-E-25	Rev	00	☐ New submittal ☐ Re-submittal	Date	30 Nov 2016		
Material Description	FIRE ALARM SYSTEM							
Country of Origin	U.S.A	Specified	Alternative	Architecture	Structure	Electrical	Mechanical	Other
		☐	☒	☐	☐	☒	☐	☐
Manufacturer		Local Supplier/Agent		Details				
Name	AVENGER	REGENCY		FIRE ALARM SYSTEM OK 7.12.2016				
Tel	+974 44054135							
Fax	+974 44410373							
POBox	PO Box 22360							
Email	Shorby.sanal@aafmq.com							
BOQ		BS		Specs				
Drawings ref.								
Attached	Data Sheet	Sample	Catalogue	Profile	Calculations	Test Results	Other	
	☐	☐	☐	☒	☐	☐		
Prepared by	Name	Signature	Reviewed by	Name	Signature	Approved by	Name	Signature
	Wilyen C. De Guzman			Mohamed Yassin			Ahmed Tarek	
	QA/QC			MEP COORDINATOR			PROJECT MANAGER	
	(EASTERN SYNERGY)			(KBN)			(GCT)	

Received by Consultant

Name	Signature	Date
Consultant comments:		
Approved	Approved With Comments	More Information Required
	Name	Signature
Commented by		
QA/QC		
Project Manager		
Received Back By the contractor		

القاهرة في ٢٠١٩/١٢/١٧
رقم قيد : 6177/19/SE/MB(61735)
السادة / شركة طيبة للتوريدات والهندسة

الموضوع : مشروع تطوير سحل المدنى المحر الاعظم بالحصرة

تحية طيبة... وبعد،،،

بالإشارة إلى الموضوع أعلاه وإيماء إلى خطابكم الوارد إلينا بتاريخ ٢٠١٩/١٢/١٦ لاعتماد اعمال الكهرياء وانظمة التيار الخفيف .

• نفيديكم علماً بالآتى :-

١. لامانع من اعتماد الكابلات ماركة السويدى .
 ٢. لامانع من اعتماد المواسير والبواطات من نوعية نيو إيجا .
 ٣. لامانع من اعتماد المضاتيح والبرايز من نوعية بتشينو من النوع الاوروبى وعلى أن يكون البرايز ٢ بول وليس ٢ بول مع أن يكون البرايز الخاصة UPS لون مختلف من النوع المجوف .
 ٤. لامانع من اعتماد وحدات إضاءة TU على أن يتم تقديم عينات قبل التوريد .
 ٥. لامانع من اعتماد نظام إنذار الحريق من نوع Avenger الأمريكى على أن يكون حاصل على اعتماد UL .
 ٦. لا يوجد توريد كابلات فى شبكة المعلومات ولا نظام الكاميرات ولا نظام الترحيم المرئى ويتم عمل مواسير فقط بشدادات .
- مرسل لتكريم بالعالم واتخاذ اللازم ،،،
ونفضلوا يقبول فائق الإحترام...

بيت الخبرة
المحفي للاستشارات الهندسية
د.أ. حكيم المحفي

بيت الخبرة
د.أ. حكيم المحفي
سجل رقم : ٩١/١٢٧ قيد رقم : ٢/٢٥٣٦
قيد مكتب استشاري رقم : ٢/١٤٦
بيت خبرة رقم : ٢٠٠
المحفي للاستشارات الهندسية

صورة إلى :-
المهندس / محمد فتيل
د.أ. علي حسن
د.أ. أحمد إبراهيم
محمود بدوي

PROJECT: Rectification of FA, FF, EL System (Existing)																					
Consultant/ Client 	Contractor: 																				
MATERIAL SUBMITTAL																					
☐ MATERIAL ☒ EQUIPMENT ☐ OTHER PURPOSE OF SUBMITTAL: ☒ For Approval ☐ For Construction / Fabrication ☐ FOR INFORMATION																					
DISCIPLINE: ☐ WET RISER SYSTEM ☒ FIRE ALARM ☐ SPRINKLER SYSTEM ☐ EMERGENCY LIGHTING																					
☒ New Submittal ☐ Resubmitted	Submittal No. _____ Date of Submittal: 25/2/2020 Prev. Submittal No. _____ Date of Receipt: ____/____/2020 Sub-Cont./Manufacturer: _____ REF# FLSA-2020-0486-011 Name and Address: _____																				
☐ Information Submitted Attached ☐ Operation & Maintenance Manual ☐ Test Results ☐ Certificates ☐ Spare Parts List ☐ Calculations Report ☐ Technical Brochure ☐ Drawings ☐ Proposals ☐ Manufacturer's Data & Specs. ☐ Warranty ☐ Catalogue																					
MATERIAL / EQUIPMENT Note: Please use attachment in case items are more than provided space																					
Item	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Name, No. and Description</th> <th style="width: 10%;">Origin</th> <th style="width: 20%;">Manufacturer/supplier</th> <th style="width: 10%;">Spec Ref.</th> <th style="width: 10%;">S.O.Q Ref.</th> <th style="width: 10%;">App. Code</th> <th style="width: 10%;">Sample</th> </tr> </thead> <tbody> <tr> <td style="height: 40px; vertical-align: top;">AVENGERS FIREALARM CONTROL PANEL AND DEVICES</td> <td style="vertical-align: top;">USA</td> <td style="vertical-align: top;">AVENGERS</td> <td style="vertical-align: top;">—</td> <td style="vertical-align: top;">—</td> <td style="vertical-align: top;">—</td> <td style="vertical-align: top;">—</td> </tr> </tbody> </table>	Name, No. and Description	Origin	Manufacturer/supplier	Spec Ref.	S.O.Q Ref.	App. Code	Sample	AVENGERS FIREALARM CONTROL PANEL AND DEVICES	USA	AVENGERS	—	—	—	—						
Name, No. and Description	Origin	Manufacturer/supplier	Spec Ref.	S.O.Q Ref.	App. Code	Sample															
AVENGERS FIREALARM CONTROL PANEL AND DEVICES	USA	AVENGERS	—	—	—	—															
Contractor's Remarks & Exceptions: _____ Reply required by: ____/____/2020																					
Exact Quantity in DO, sample to be provided for inspection.																					
Submitted by Contractor: General International Name & Signature: Khurram Shahzad / Site Engineer Date: 25/2/2020 <i>K. Shahzad</i>																					
Recd. By Gulf Food Company Americana Name & Signature: _____ Date: ____/____/____																					
Consultant's Comments/Remarks: _____ As inspection it's approved for these materials depends on the installation area.																					
ACTION	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30px; text-align: center;">A</td> <td style="width: 300px;">Approved As Submitted</td> <td style="width: 30%;">For: Gulf Food Company Americana</td> <td style="width: 30%;">General Information</td> </tr> <tr> <td style="text-align: center;">B</td> <td>Approved As Noted Resubmission not required</td> <td>Name: Abdallah Nabil</td> <td>Name: Khurram</td> </tr> <tr> <td style="text-align: center;">C</td> <td>Approved As Noted Resubmission required</td> <td>Position: Electrical Engineer</td> <td>Signature: <i>Khurram</i></td> </tr> <tr> <td style="text-align: center;">D</td> <td>Disapproved</td> <td>Signature: _____</td> <td>Date: 26/2/2020</td> </tr> <tr> <td style="text-align: center;">E</td> <td>No Action Taken</td> <td>Date: 26/2/2020</td> <td></td> </tr> </table>	A	Approved As Submitted	For: Gulf Food Company Americana	General Information	B	Approved As Noted Resubmission not required	Name: Abdallah Nabil	Name: Khurram	C	Approved As Noted Resubmission required	Position: Electrical Engineer	Signature: <i>Khurram</i>	D	Disapproved	Signature: _____	Date: 26/2/2020	E	No Action Taken	Date: 26/2/2020	
A	Approved As Submitted	For: Gulf Food Company Americana	General Information																		
B	Approved As Noted Resubmission not required	Name: Abdallah Nabil	Name: Khurram																		
C	Approved As Noted Resubmission required	Position: Electrical Engineer	Signature: <i>Khurram</i>																		
D	Disapproved	Signature: _____	Date: 26/2/2020																		
E	No Action Taken	Date: 26/2/2020																			



الإدارة العامة للإطفاء Kuwait Fire Service Directorate



الإشارة: م ط / و ق / 150 -

تاريخ الاعتماد: 2017/10/15

تاريخ الإنتهاء: 2019/8/2

المحترمين

السادة / شركة أنظمة الخرافي للتجارة والمقاولات
تحية طيبة وبعد،،

الموضوع: اعتماد معدات نظام إنذار الحريق

صنع الشركة الأمريكية Avenger Systems انتاج امريكا - بريطانيا

بالإشارة الى الموضوع أعلاه، وردا على طلبكم المؤرخ (2017/8/20) وبعد دراسة التكنولوجيات الفنية والشهادات المقدمة من مختبر (UL) المعتمد لدى الإدارة العامة للإطفاء وبناء على موافقة لجنة المعدات رقم (2017/11) بتاريخ (2017/10/10)، نود أن نعلمكم بأنه لا مانع لدينا من اعتماد معدات إنذار الحريق صنع الشركة الأمريكية المذكورة حسب البيانات الواردة في الجدول التالي:

No.	ITEMS	MODEL NO.	UL FILE NO.
Supreme Analog Fire Control Panels			
1	Supreme RS-H Analog FACP 1-Loop	AS0810-10	UOJZ.S35689
2	Supreme RS-H FACP 1-Loop w/eNET Network Card	AS0815-10	
3	Supreme RS-H Analog FACP 2-Loop	AS0820-10	
4	Supreme RS-H FACP 2-Loop w/eNET Network Card	AS0825-10	
5	Supreme [H] 2 Loop Panel, Red	AS1420-10	
6	Supreme [H] 2 Loop Panel, Red w/eNET Network Card	AS1425-10	
7	Supreme [H] 4 Loop Panel, Red	AS1440-10	
8	Supreme [H] 4 Loop Panel, Red w/eNET Network Card	AS1445-10	
9	eNET Communications Interface Card	AS1170-00	
10	16 Channel RS485 Serial I/O Interface Card	AS1171-00	
11	eVIEW Serial Annunciator, Red	AS1172-10	UOXX.S35689



تاريخ الطباعة: 2017/10/15

صفحة 1 من 4



الإدارة العامة للإطفاء Kuwait Fire Service Directorate



الإشارة: م ط / و ق / 150 -

تاريخ الاعتماد: 2017/10/15

تاريخ الإنتهاء: 2019/8/2

No.	ITEMS	MODEL NO.	UL FILE NO.
Addressable Detectors			
1	Addressable Multi Heat detector ROR and FT	AS2010-00	UQGS.535691
2	Addressable Multisensor Smoke and Heat	AS2012-00	
3	Addressable Photoelectric smoke detector	AS2011-00	UROX.535692
4	Addressable Detector Base 4"	AS7001-00	
5	Addressable Detector Base 6"	AS7002-00	
6	Addressable Sounder Base for Detectors	AS7008-00	
7	Analog Addressable Duct Detector (H)	AS5013-00	
8	Analog Addressable Duct Detector w/Relays (H)	AS5014-00	
Addressable Modules			
1	Monitor module (Input module)	AS6024-00	UOXX.535689
2	Dual Input Module (H)	AS6007-00	
3	Conventional Zone module	AS6011-00	
4	Fast Response Contact Modules (Class A Wiring)	AS6020-00	
5	Fast Response Contact Modules (Class A Wiring) with short circuit isolator	AS6021-10	
6	Dual Relay Module Low-H (2A @ 30VDC / 0.5A @ 120 VAC)	AS6052-00	
7	Dual Relay Module Low-H W/Isolator (2A @ 30VDC / 0.5A @ 120 VAC)	AS6053-00	
8	Dual Relay Module High -H (8A @ 30VDC / 4.8A @ 250 VAC)	AS6054-00	
9	Dual Relay Module High -H W/Isolator (8A @ 30VDC / 4.8A @ 250 VAC)	AS6055-00	
10	Supervised output module Class A (to control notification devices)	AS6040-00	
11	Supervised output module Class A with isolator (to control notification devices)	AS6041-00	
12	Short circuit isolator module	AS6003-00	
Addressable Manual Pull Station			
1	Addressable Manual Pull Station	AS3031-00	UNIU.535688
2	Addressable Manual Pull Station, Dual Action w/ Key Lock	AS3029-10	
Audible-signal Appliances			
1	Horns (Indoor/Outdoor)	AS4000-10	ULSZ.535913
2	Horn/strobes (Indoor)	AS4002-10	
3	Horn/strobes (Indoor/Outdoor)	AS4007-10	
4	Horn/strobes (Indoor)	AS4004-10	

تاريخ الطباعة: 2017/10/15





الإدارة العامة للإطفاء Kuwait Fire Service Directorate



الإشارة: م ط / وق / 150 -

تاريخ الاعتماد: 2017/10/15

تاريخ الإنتهاء: 2019/8/2

No.	ITEMS	MODEL NO.	UL FILE NO.
Signaling Appliances and Equipment for the Hearing Impaired			
1	Strobe/Horns	AS4004-10	UUJC.535913
2	Strobe Lights	AS4003-10	
No.	ITEMS	MODEL NO.	UL FILE NO.
Visual-signal Appliances for Fire-protective Signaling Systems			
1	Horn	AS4000-10	UVAV.535913
2	Horn/Strobe	AS4002-10	
3	Horn/Strobe	AS4007-10	
4	Strobe	AS4001-10	
5	Strobe	AS4006-10	
No.	ITEMS	MODEL NO.	UL FILE NO.
Conventional & Releasing Control Panels			
1	Elite XT Conventional Releasing Panel 230V	AS1810-11	UOJZ.535689
2	Elite CP Conventional Panel 2 zones 230 VAC	AS1842-11	
3	Elite CP Conventional Panel 4 zones 230 VAC	AS1844-11	
4	Elite CP Conventional Panel 8 zones 230 VAC	AS1848-11	
Releasing Accessories			
1	Elite XT Abort Switch Surface Mount	AS1823-10	UOXX.535689
2	Elite XT Extinguishant Disablement Switch	AS1832-10	
Conventional Detectors			
1	Conventional Photo Electric Smoke - H	AS2032-00	UROX.535692
2	Conventional Photo Electric Smoke & Heat - H	AS2041-00	UQGS.535691
3	Conventional Heat Sensor 190° F (H)	AS2021-00	
4	Conventional Heat Sensor 135° F (H)	AS2020-00	
5	Conventional 4" base - H	AS2050-00	
6	Conventional 6" base - H	AS2051-00	



تاريخ الطباعة: 2017/10/15

Handwritten signature and date: 2017/10/15



الإدارة العامة للإطفاء Kuwait Fire Service Directorate



الإشارة: م ط / و ق / 150 -

تاريخ الاعتماد: 2017/10/15

تاريخ الإنتهاء: 2019/8/2

No.	ITEMS	MODEL NO.	UL FILE NO.
Conventional Detectors			
1	Conventional Pull Station - Single Action	AS3036-10	UNIU.535688
2	Conventional Pull Station - Single Action (SG-42SK1)	AS3037-10	
3	Conventional Pull Station - Dual Action (SG-42SK2)	AS3038-10	

شريطة التقيد بجميع قوانين ومواصفات الإدارة العامة للإطفاء الخاصة بتجارة وصيانة معدات وأنظمة الإنذار والمكافحة وتوفير الغيار وعمل الصيانة اللازمة لها، حيث يجب توفير اسم وموديل المعدة وأيضا اسم وشعار المختبر ورقم التسجيل على المعدة، وتقديم الكتالوجات الفنية للدراسة والاعتماد لكل مشروع على حده قبل التنفيذ على أن يتم تنفيذ هذه المواد من قبل الجهاز الفني المعتمد.

وتفضلوا بقبول فائق الاحترام والتقدير ،،،

نائب المدير العام لشؤون قطاع الوقاية

مدير إدارة وقاية قطاع الوقاية



تاريخ الطباعة: 2017/10/15

صحة 4 من 4

17/10/15



කොළඹ මහා නගර සභාව / கொழும்பு மாநகர சபை / Colombo Municipal Council



නීති නිවිථි සේවා දෙපාර්තමේන්තුව
தீயணைக்கும் சேவை திணைக்களம்
FIRE SERVICE DEPARTMENT

ටී. ඩී. ජයා මාවත, කොළඹ 10. / தி. பி. ஜயா மாவத்தை, கொழும்பு 10. / T. B. Jayah Mawatha, Colombo 10.
දුරකථන / தொலைபேசி / Telephone : 011-2686087 ෆැක්ස් / பெக்ஸ் / Fax : 011-2692222

හදිසි අංකයන් } 110
தவிர தொலைபேசி } 2422222-3
Emergency Numbers } 4222222

වෙබ් අඩවිය }
වෙබ් } www.cmc.lk
Web }

විද්‍යුත් තැපෑල }
අ-විද්‍යුත් තැපෑල } cmcfireservice@sltnet.lk
E-mail }

FB/APL/FPE/CP/ACC/47/22

October 27, 2022

The Director,
Proneat Holdings (Pvt) Ltd
No 128, Temple Road,
Maradana,
Colombo 10.

Dear Sir,

**APPROVAL FOR AVENGER CONTROL PANELS AND ACCESSORIES FOR
WATERFRONT INTEGRATED RESORT PROJECT, COLOMBO**

This refers to your letter dated 24th October 2022 and the Technical Data furnished to this department.

S/N	Item Description	Model	Approvals/ Standards
<i>Addressable Control Panels, Modules & Other Accessories</i>			
1	1 Loop Addressable Control Panel (SUPREME-RS)	AS0810-XX	UL
2	2 Loop Addressable Control Panel (SUPREME-RS)	AS0820-XX	
3	2-16 Loop Addressable Control Panel (OASIS)	OA 103 H#	UL, FM
4	Modules & Other Accessories.		UL
<i>Addressable Detectors</i>			
5	Heat Detector.	AS2010-00	UL
6	Smoke Detector.	AS2011-00	UL
7	Multi Criteria Detector Smoke/Heat.	AS2012-00	UL
8	Multi Criteria Detector – Smoke/Heat/CO/COH8.	AS2014-00	UL

This department has no objection in installing above Avenger products for Essential Fan Control Systems, Gas Detection Systems, Fire Detection and Alarm Systems of the said project.

Thanking You

Yours Faithfully


H.W.W. KULARATNE
DIVISIONAL FIRE OFFICER
FOR CHIEF FIRE OFFICER

H.W.Wimal Kularatne
Divisional Fire Officer
(Fire Prevention) G. I. Fire Eng.
Fire Service Department
T. B. Jayah Mawatha, Colombo 10.

011-2691637
ප්‍රධාන ඔබ් ඔෆිසර්
தலைவர் இயக்குநர்
Chief Fire Officer

011-2678928
ප්‍රධාන ඔබ් ඔෆිසර්
தலைவர் இயக்குநர்
Deputy Chief Fire Officer

011-2686406
සහකාර ලේකම්
உதவி இயக்குநர்
Assistant Secretary

011-2686801
සහකාර ප්‍රධාන ඔෆිසර් (පරිපාලන)
உதவி தலைவர் இயக்குநர் (அำนวยการ)
Assistant Chief Fire Officer (Op)

011-2364346
සහකාර ප්‍රධාන ඔෆිසර් (ප්‍රවෘත්ති)
உதவி தலைவர் இயக்குநர் (பொது)
Assistant Chief Fire Officer (Trg)

011-2683370
සහකාර ප්‍රධාන ඔෆිසර් (විද්‍යුත්)
உதவி தலைவர் இயக்குநர் (மிது)
Assistant Chief Fire Officer (Prv)

011-2686408
පරිපාලන කාර්යාලය
தலைவர் இயக்குநர்
Administrative Office

List Of Projects

Avenger Systems has successfully delivered Fire Detection and Suppression Solutions across prestigious hospitality venues, international airports, major shopping malls, and high-end developments across the globe, reinforcing its position as a trusted partner for premium projects.



List of Projects

- New Facility – Behn Meyer VSIP (Vietnam)
- Hyatt Palace Ha Long Bay Hotel (Vietnam)
- HIIVE Hotel VSIP 1 (Vietnam)
- HIIVE Hotel VSIP 2 (Vietnam)
- Sky 89 (Vietnam)
- River Panorama (Vietnam)
- Tra Vinh General Hospital (Vietnam)
- Ixora Ho Tram Resort (Vietnam)
- Phin Factory – Nestlé Vietnam (Vietnam)
- Zahra Towers – Ministry of Interior (Egypt)
- 10th of Ramadan Prison (Egypt)
- Director of Security – New Alamein City (Egypt)
- Marsa Mares Hotel – Marsa Alam (Egypt)
- Sakhra Hotel – Marsa Matruh (Egypt)
- Police Mosque – 6th October City (Egypt)
- Engineering Faculty – Mansoura University (Egypt)



List of Projects

- Water Treatment Plant – Al-Raysa, Al-Arish (Egypt)
- Fresh Showrooms – Gesr El-Swiss / Shobra / Al-Obour (Egypt)
- Smart LED Fresh Factory – 10th of Ramadan (Egypt)
- EMPE Head Office – 5th Settlement (Egypt)
- Development Center – Educational Complex, 6th October (Egypt)
- Agora Mall – 5th Settlement (Egypt)
- Amok Company – Alexandria (Egypt)
- Al Furat Alex West Company (Egypt)
- Mina Pharm – 10th of Ramadan (Egypt)
- Toshka Power Station – Aswan (Egypt)
- Qaws Water Station – Qena (Egypt)
- Palm Hills Mall – October (Egypt)
- Asna Traffic Unit – Ministry of Interior (Egypt)
- Mashiakhet Al-Azhar – Asyut (Egypt)
- Civil Registration – Mansoura (Egypt)
- El Amar Foam Factory – Abu Rawash (Egypt)
- Utopia Beach Club Hotel – Marsa Alam (Egypt)



List of Projects

- Residential Compound Phase 1 – Bu Sidra (Qatar)
- Residential Building (2B+G+10F) – Lusail (Qatar)
- Office Building FV9 (2B+G+5F) – Lusail (Qatar)
- Office Building (B+G+3) – Al Sadd (Qatar)
- Workshop & Office Building (G+2) – Industrial Area (Qatar)
- Farmhouse Villa Project (Qatar)
- Al Dar Exchange – Safari Mall Al Khor (Qatar)
- Gulf Exchange – Al Ruwais (Qatar)
- Abu Sedra Compound (Qatar)
- C4 Compound (Qatar)
- Entertainment City FV-09 (Qatar)
- Villa Project (G+1) (Qatar)K-Electric – Maymar Grid (Pakistan)
- Silicon Technologies – IBA Karachi (Pakistan)
- Silliman University (Philippines)
- Hotel Essencia (Philippines)



List of Projects

- Olaya Lifestyle Retail – Riyadh (Saudi Arabia)
- Avance Learning School – Riyadh (Saudi Arabia)
- Al Bassateen Office – Riyadh (Saudi Arabia)
- King Faisal Specialist Hospital – Riyadh (Saudi Arabia)
National Water Company – Environmental Services Station, Riyadh (Saudi Arabia)
- Saudi Telecom Company (TAWAL) – Riyadh (Saudi Arabia)
- University of Tabuk – College of Science, Tabuk (Saudi Arabia)
- General Hospital – Hail (Saudi Arabia)
- Al Magarda Hospital – Aseer (Saudi Arabia)
- Ministry of Culture – Head Office, Riyadh (Saudi Arabia)
- Ministry of Defense – Supporting Building, Riyadh (Saudi Arabia)
- Ministry of Justice – Security Requirements, Riyadh (Saudi Arabia)
- NUPCO Medicine Warehouse – Dammam (Saudi Arabia)
- NUPCO Medicine Warehouse – Al Jouf (Saudi Arabia)
- Ministry of Sport – King Fahd Sports City Development, Taif (Saudi Arabia)
- General Authority of Roads – Riyadh (Saudi Arabia)



List of Projects

- Royal Saudi Air Force – Radar Station, Northern Sector (Saudi Arabia)
- National Bank Archives – Al Kharj (Saudi Arabia)
- SRJ Sports Investment Company – KFAD, Riyadh (Saudi Arabia)
- Safira RAK Fabrication Yard – Ras Al Khobar (Saudi Arabia)
- Royal Commission – Film Crew Lodge Phase 2 & 3, Al Ula (Saudi Arabia)
- National Guard Hospital – King Abdulaziz Medical City, Riyadh (Saudi Arabia)
- Riyadh Metro Project – Riyadh (Saudi Arabia)
- Ritz Carlton Hotel – DIFC, Dubai (UAE)
- Kempinski Hotel – Palm Jumeirah, Dubai (UAE)
- Radisson Blu Hotel – Business Bay, Dubai (UAE)
- Aloft Hotel – Dubai (UAE)
- Westin 5-Star Hotel – Dubai (UAE)
- Viceroy Hotel – Dubai (UAE)
- Park Hyatt Hotel – Dubai (UAE)
- Queen Elizabeth 2 (QE2) Ship Kitchen – Dubai (UAE)
- Mina Al Fajer Resort – Fujairah (UAE)

List of Projects

- Dubai Mall – Multiple Restaurants Projects (UAE)
- Mall of Emirates – Multiple Projects (UAE)
- Nakheel Mall – Vox Cinema, Palm Jumeirah (UAE)
- Ibn Battuta Mall – Multiple Projects (UAE)
- City Walk – Dubai (UAE)
- La Mer Waterfront – Multiple Projects (UAE)
- Dubai Parks & Resorts – Riverland (UAE)
- Dubai International Airport – Terminal 3 (UAE)
- Emirates Flight Catering – Central Kitchen (UAE)
- Air Arabia Flight Catering – Sharjah (UAE)
- Al Naboodah Staff Accommodation – Central Kitchen, Jebel Ali (UAE)
- Deliveroo Central Kitchen – Phase 1, Dubai (UAE)
- VOX Cinema – Nakheel Mall, Palm Jumeirah (UAE)
- Reel Cinema – Jebel Ali, Dubai (UAE)
- Sharjah Cooperative Society – Kalba & Nakhilat (UAE)



List of Projects

- School AL Ameen Babil (Iraq)
- Sidr Farm (Iraq)
- Al-Ameen International Center for Research and Studies (Iraq)
- Sheikh Al-Kulaini Complex (Iraq)
- Al Kout Cinema – Fahaheel (Kuwait)
- Mill Tower – Salmiya (Kuwait)
- Om Kolthoum School – Al Salam (Kuwait)
- Abdullah Khalaf Aldihany School – Al Zahraa (Kuwait)
- Fatima Al Saraoui School – Al Salam (Kuwait)
- Alia International Hospital (Kuwait)
- Kuwait International Bank – Hawally (Kuwait)
- Public Authority of Housing Welfare (Kuwait)
- Starlight sweater Ltd. (Bangladesh)
- Stark Bag Industries Ltd. (Bangladesh)
- Dhaka Wasa (Bangladesh)
- Euro Spinning Ltd. (Bangladesh)
- IHM Garments & Textile Co, LTD (Bangladesh)
- Dispatch Terminal of CDPL Project Under 24 ECB (Bangladesh)



شركة فالكون باور العالمية لاجهزة السلامة



السجل التجاري: 4030500427

رمزك التجاري QR Code

من خلاله يمكنك التحقق المباشر من المعلومات:

- السجل التجاري
- رخصة البلدية
- شهادة السعودة
- برنامج نطاقات
- شهادة الزكاة
- الغرفة التجارية

٧٠٣٣٧٤١٠٠٥

الرقم الموحد :

٤٠٣٠٥٠٠٤٢٧

رقم المنشأة :

١٤٤٤/٠٧/١٤ هـ

التاريخ :

شهادة تسجيل الشركة

Company Registration Certificate

وزارة التجارة
Ministry of Commerce



الاسم التجاري للشركة : شركة فالكون باور العالمية لاجهزة السلامة

نوعها : ذات مسئولية محدودة

جنسيتها : سعودي

مدة الشركة : ٩٩ سنة

تبدأ من : ١٤٤٤/٠٧/١٤ هـ

وتنتهي في : ١٥٤٣/٠٧/١٥ هـ

مركزها الرئيسي : ٠٠٠٠٠٠٠٠

هاتف : ٠٠٠٠٠٠٠٠

النشاط : للاطلاع على بيانات الأنشطة الرجاء مسح الرمز التجاري

ص.ب : ٠٠٠٠٠٠٠٠

سعودية

ملكية الشركة :

رأس المال : ٢٧,٠٠٠,٠٠٠ ريال سعودي

المديرون : 1 منصور حسن محمد حسن

2

4

6

8

10

12

14

16

3

5

7

9

11

13

15

سلطات المدير/المديرون : حسب ما نص عليه عقد الشركة

يشهد مكتب السجل التجاري بمدينة جدة

بأنه تم تسجيل الشركة المذكورة أعلاه بمدينة جدة

وتنتهي صلاحية الشهادات في : ١٤٤٦/٠٧/٢٦ هـ

بموجب الإيصال رقم : ٢٤١٠٣٣٥٢٢٩٦٩

وتاريخ : ١٤٤٦/٠٤/٢٠ هـ



To Verify The Information Of This Certificate Visit <https://mc.gov.sa> يمكنك التحقق من صحة هذه الشهادة بالدخول على

+966 11 294 4444 | الرياض 11162 | Kingdom of Saudi Arabia | المملكة العربية السعودية | www.mc.gov.sa MCgovSA

شركة فالكون باور العالمية لاجهزة السلامة

/ السادة

نسأل الله أن يكتب لكم التوفيق والنجاح في عملكم التجاري وأن تكونوا شريكاً في تعزيز اقتصاد المملكة العربية السعودية.

يسرنا إبلاغكم بأن رقم منشأتكم الموحد هو

٧٠٣٣٧٤١٠٠٥

وقد تم ربطه بالخدمات الحكومية التالية..

٦٣٨٧٦٣٣٢٨

رقم منشأتكم



٤٠٣٠٥٠٠٤٢٧

رقم منشأتكم



٤٨١٨٧٩

رقم منشأتكم



٣١٤٠٠٥٤-٩

رقم منشأتكم



لا يوجد

رقم منشأتكم



٣١٠٣٣٠٩٣٣٠٢

رقم منشأتكم



تحت الاجراء

رقم منشأتكم



للاستفادة من الخدمات المقدمة
من الجهات الحكومية



دليل التاجر





تاريخ الإصدار: 2023/02/08

الرقم المميز: 3115506404



الهيئة العامة للزكاة والدخل
General Authority of Zakat & Tax



شهادة تسجيل في ضريبة القيمة المضافة VAT Registration Certificate

تشهد الهيئة العامة للزكاة والدخل بأن المكلف أدناه مسجل في ضريبة القيمة المضافة
بتاريخ 2023/02/08

Hereby, The General Authority of Zakat & Tax (GAZT) certifies that the taxpayer below is
VAT registered on 08/02/2023

اسم المكلف: شركة فالكون باور العالمية لاجهزة السلامة

رقم التسجيل الضريبي: 311550640400003

تاريخ نفاذ التسجيل: 2023/03/01

عنوان المكلف: جدة، الرحاب، شارع الأمير متعب، 23451



كمكلف مسجل في ضريبة القيمة المضافة، لا يجوز لك تحصيل ضريبة القيمة المضافة من عملائك قبل تاريخ
نفاذ التسجيل بالضريبة. في حال تبين غير ذلك، ستقوم الهيئة العامة للزكاة والدخل بتنفيذ الغرامات المستحقة

هذه الوثيقة مرسلة من النظام الآلي ولا تحتاج إلى توقيع
- الهيئة العامة للزكاة والدخل -



تاريخ الإصدار: 2023/02/08
الرقم المميز: 3115506404



الهيئة العامة للزكاة والدخل
General Authority of Zakat & Tax



اسم المكلف: شركة فالكون باور العالمية لاجهزة السلامة
Taxpayer Name: شركة فالكون باور العالمية لاجهزة السلامة
رقم السجل/الرخصة/العقد: 4030500427
CR / License / Contract No.: 4030500427
الفترة الضريبية: ربع سنوي-Quarterly
Tax Period: Quarterly-ربع سنوي-Quarterly
تاريخ استحقاق أول إقرار ضريبي: 2023/04/30
First Filing due date: 2023/04/30



كمكلف مسجل في ضريبة القيمة المضافة، لا يجوز لك تحصيل ضريبة القيمة المضافة من عملائك قبل تاريخ
نفاذ التسجيل بالضريبة. في حال تبين غير ذلك، ستقوم الهيئة العامة للزكاة والدخل بتنفيذ الغرامات المستحقة

هذه الوثيقة مرسلة من النظام الآلي ولا تحتاج إلى توقيع
- الهيئة العامة للزكاة والدخل -

Proof Number	1051349559	رقم الإثبات
Original Date	24/6/2024	تاريخ الإصدار
Expiration Date	21/12/2024	تاريخ الانتهاء



إثبات عنوان Address Proof

Address Holder Details

بيانات صاحب العنوان

Name	شركة فالكون باور العالمية لاجهزة السلامة	الاسم
Customer Acc.	3 1 3 2 6 2 2 4 7 7 2	رقم الحساب
Reg. Date	24/6/2024	تاريخ التسجيل

Address Details

تفاصيل العنوان

Short Address	J C M B 2 9 9 2	العنوان المختصر
Building No.	2 9 9 2	رقم المبنى
Street	Falasteen	الشارع
Secondary No.	6 1 1 2	الرقم الفرعي
District	Mishrifah Dist.	الحي
Postal Code	2 3 3 4 1	الرمز البريدي
City	JEDDAH	المدينة
	جدة	
	Kingdom of Saudi Arabia	المملكة العربية السعودية



للتحقق To Verify

<https://proof.address.gov.sa/VerifyProofNA.aspx>

تم إصدار هذا الإثبات إلكترونياً ولا يتطلب التوقيع عليه

تم إصدار هذا الإثبات بناءً على طلب الموضح أعلاه، ويحظر قطعياً تقليده أو إدخال أي تعديلات عليه سواءً بالإضافة أو الحذف، ويعد الإثبات لاغياً إذا شابه شيء من ذلك، كما يعرض صاحبه للمساءلة القانونية.

This proof has been issued electronically and does not require a signature

This proof has been issued upon the request of the above-named, and it is absolutely prohibited to imitate it or make any modifications to it, whether by addition or deletion, and the proof is considered void if it is marred by something, and its owner is subject to legal accountability.